

LOCATION OF WORK:	US 136	US 136
	RURAL TWO LANE	RURAL TWO LANE
	BRIDGE REPLACEMENT	BRIDGE REPLACEMENT
	MCLEAN COUNTY	MCLEAN COUNTY
	STA. 415+00 TO STA 442+00	STA. 415+00 TO STA 442+00
	OVER KICKAPOO CREEK	OVER KICKAPOO CREEK
	1.3 MI W OF U.S. 51	1.3 MI W OF U.S. 51

FUNDING BREAKOUT:	80% FEDERAL / 20% STATE	80% FEDERAL / 20% STATE
CONSTRUCTION TYPE CODE:	0004	0011

CODE NO.	ITEM	UNIT	ROADWAY QUANTITY	BRIDGE QUANTITY	TOTAL QUANTITY
54215559	METAL END SECTIONS 24"	EACH	2.0	0.0	2.0
542D1069	PIPE CULVERTS, CLASS D, TYPE 2 24"	FOOT	74.0	0.0	74.0
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	0.0	81.0	81.0
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	0.0	4.0	4.0
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1.0	0.0	1.0
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	212.5	0.0	212.5
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2.0	0.0	2.0
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4.0	0.0	4.0
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1(SPECIAL) TANGENT	EACH	2.0	0.0	2.0
63200310	GUARDRAIL REMOVAL	FOOT	454.0	0.0	454.0
* 63300725	STEEL PLATE BEAM GUARDRAIL (SHORT RADIUS)	FOOT	100.0	0.0	100.0
66600105	FURNISHING AND ERECTING RIGHT OF WAY MARKERS	EACH	2.0	0.0	2.0
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	2.0	10.0	12.0
67100100	MOBILIZATION	L SUM	0.2	0.8	1.0
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	0.0	1.0	1.0
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1.0	0.0	1.0
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1.0	0.0	1.0
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	0.0	1.0	1.0
70106700	TEMPORARY RUMBLE STRIPS	EACH	0.0	6.0	6.0
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1,000.0	0.0	1,000.0
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	6,100.0	0.0	6,100.0

* DENOTES SPECIALTY ITEM

FILE NAME =	USER NAME = hoganbj	DESIGNED - BJH 7/12/2011	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\pwork\hoganbj\00142533\0570552-shr-500.dgn	DRAWN -	REVISOR -	315					121BR-2	MCLEAN	144	9	
PLOT SCALE = 100.0000 / 1"	CHECKED -	REVISOR -	SCALE: _____ SHEET NO. 4 OF 6 SHEETS STA. _____ TO STA. _____			ILLINOIS FED. AID PROJECT						
PLOT DATE = 8/22/2011	DATE -	REVISOR -	CONTRACT NO. 70552									