

LOCATION OF WORK:	US 136	US 136
	RURAL TWO LANE	RURAL TWO LANE
	BRIDGE REPLACEMENT	BRIDGE REPLACEMENT
	MCLEAN COUNTY	MCLEAN COUNTY
	STA. 415+00 TO STA 442+00	STA. 415+00 TO STA 442+00
	OVER KICKAPOO CREEK	OVER KICKAPOO CREEK
	1.3 MI W OF U.S. 51	1.3 MI W OF U.S. 51

FUNDING BREAKOUT:	80% FEDERAL / 20% STATE	80% FEDERAL / 20% STATE
CONSTRUCTION TYPE CODE:	0004	0011

CODE NO.	ITEM	UNIT	ROADWAY QUANTITY	BRIDGE QUANTITY	TOTAL QUANTITY
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2,150.0	0.0	2,150.0
70400100	TEMPORARY CONCRETE BARRIER	FOOT	0.0	687.5	687.5
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	0.0	562.5	562.5
* 70500100	TEMPORARY STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	0.0	50.0	50.0
* 70500665	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	0.0	2.0	2.0
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	5,200.0	0.0	5,200.0
* 78008310	POLYUREA PAVEMENT MARKING TYPE II - LINE 4"	FOOT	0.0	850.0	850.0
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	30.0	0.0	30.0
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	0.0	5.0	5.0
* 78200420	GUARDRAIL MARKERS, TYPE B	EACH	11.0	0.0	11.0
* 78200520	BARRIER WALL MARKERS, TYPE B	EACH	0.0	10.0	10.0
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2.0	2.0	4.0
78300100	PAVEMENT MARKING REMOVAL	SQ FT	0.0	350.0	350.0
78300200	RAISED REFLECTIVE PAVMENT MARKER REMOVAL	EACH	30.0	5.0	35.0
* D2001724	EVERGREEN, PICEA ABIES (NORWAY SPRUCE), 2' HEIGHT, BALLED AND BURLAPPED	EACH	96.0	0.0	96.0
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	0.0	153.0	153.0
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1	EACH	0.0	1.0	1.0
X5020502	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 2	EACH	0.0	1.0	1.0
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	3.0	0.0	3.0
* X7050167	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)	EACH	0.0	2.0	2.0

* DENOTES SPECIALTY ITEM

FILE NAME =	USER NAME = hoganbj	DESIGNED - BJH 7/12/2011	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pr-work\pvidot\hoganbj\00142533\057052-sh1-S00.dgn	DRAWN -	REVISOR -						315	121BR-2	MCLEAN	144	10
PLOT SCALE = 100.0000 "/ 1"	CHECKED -	REVISOR -			CONTRACT NO. 70552			ILLINOIS FED. AID PROJECT				
PLOT DATE = 8/22/2011	DATE -	REVISOR -			SCALE: _____	SHEET NO. 5 OF 6 SHEETS	STA. _____ TO STA. _____					