

SCHEDULES OF QUANTITIES

TEMPORARY RAMP

STA.	VERTICAL DROPOFF (IN)	LENGTH (FEET)	WIDTH (FEET)	TEMPORARY RAMP 40600990 (SQ YD)
415+00	2.0	6.7	26.0	19.3
417+80	1.0	3.3	30.0	11.1
419+13.64	1.0	3.3	30.0	11.1
420+21.43	1.0	3.3	30.0	11.1
426+28.72	20.8	69.2	36.0	276.7
426+28.72	14.0	46.7	36.0	186.7
426+28.72	8.0	26.7	36.0	106.7
426+28.72	2.0	6.7	36.0	26.7
430+04.72	20.3	67.5	36.0	270.0
430+04.72	14.0	46.7	36.0	186.7
430+04.72	8.0	26.7	36.0	106.7
430+04.72	2.0	6.7	36.0	26.7
436+50	1.0	3.3	30.0	11.1
437+63.64	1.0	3.3	30.0	11.1
438+75	1.0	3.3	30.0	11.1
442+00	2.0	6.7	26.0	19.3
CE 424+67.69 RT	20.5	20	60	133.3
CE 424+67.69 RT	14.0	14.5	60	96.7
CE 424+67.69 RT	8.0	8.3	60	55.3
CE 424+67.69 RT	2.0	6.7	60	44.5
CE 424+67.69 RT	2.0	6.7	24	17.8
TR 190 431+72.21 RT	20.4	20.0	60	133.3
TR 190 431+72.21 RT	14.0	14.5	60	96.7
TR 190 431+72.21 RT	8.0	8.3	60	55.3
TR 190 431+72.21 RT	2.0	6.7	60	44.5
TR 190 431+72.21 RT	2.0	6.7	16	11.9
TOTAL:				1981.4
ROUND TO:				2000.0

SHOULDERS

STA.	TO	STA.	LENGTH (FOOT)	WIDTH (FOOT)	AGG SHOULDERS TYPE B, 6" 48101500 (SQ YD)	HMA SHOULDERS 8" 48203029 (SQ YD)
415+00 Rt.		424+17 Rt.	917	3.0	305.7	
425+03 Rt.		426+31.72 Rt	128.72	3.0	42.9	
430+01.72 Rt.		431+13 Rt.	111.28	3.0	37.1	
431+75 Rt.		442+00 Rt.	1025	3.0	341.7	
415+00 Lt.		426+31.72 Lt.	1131.72	3.0	377.2	
430+01.72 Lt.		431+60 Lt.	158.28	3.0	52.8	
432+23 Lt.		436+80 Lt.	457	3.0	152.3	
437+50 Lt.		442+00 Lt.	450	3.0	150.0	
C.E. cl Sta.424+68.11 Rt.			105	2.0	23.3	
TR 190 cl Sta.431+72.21 Rt.			226	2.0	50.2	
415+00 Lt.		426+31.72 Lt.	1131.72	2.0		251.5
430+01.72 Lt.		442+00 Lt.	1198.28	2.0		266.3
415+00 Rt.		426+31.72 Rt.	1131.72	2.0		251.5
430+01.72 Rt.		431+12 Rt.	110.28	2.0		24.5
432+00 Rt.		442+00 Rt.	1000	2.0		222.2
TOTAL:					1533.2	1016.0
ROUND TO:					1,550 SQ YD	1,025 SQ YD

DRAINAGE

LOCATION	PIPE CULVERT REMOVAL 50105220 (FOOT)	P Cul CID 2 24 542D1069 (FOOT)	Prc Flar End Sec 18 54213663 (EACH)	Met End Sec 24 54215559 (EACH)	PCBC 5'x3' 54010503 (FOOT)	PCBC 7'x6' (M273) 54020706 (FOOT)	Box Cul End Sec C1 54001001 (EACH)	Box Cul End Sec C2 54001002 (EACH)	Grated BC End Sec C1 54001061 (EACH)	Grated BC End Sec C2 54001062 (EACH)	Man Adj New T1F CL 60255800 (EACH)									
CE 424+67.69 RT	76.0	74.0		2.0																
FE 431+90.15 LT	31.0				40.0			1.0		1.0										
TR 190 431+72.21 RT	148.0					48.0	1.0		1.0											
STA.428+56, 34' RT	8.0		1.0																	
STA.432+20, 19' RT											1.0									
TOTAL:											263.0	74.0	1.0	2.0	40.0	48.0	1.0	1.0	1.0	1.0