

SCHEDULES OF QUANTITIES

PAVEMENT MARKING

STA.	TO	STA.	Sequence	Short-Term Pavt Mking 70300100 (FOOT)	Temp Pvt Mk Line 4 70300220 (FOOT)	Work Zone Pavt Mk Rem 70301000 (SQ FT)	Paint Pvt Mk Line 4 78001110 (FOOT)	Polyurea Pm T 2 Ln 4 78008310 (FOOT)	Raised Refl Pvt Mkr 78100100 (EACH)	Raised Refl Pvt Mkr Br 78100105 (EACH)	Pavt Marking Removal 78300100 (SQ FT)	Raised Ref Pvt Mk Rem 78300200 (EACH)
415+00		442+00	cl After Bridge Complete	272.0		13.3						
420+21.43		426+31.72	cl After 1st Lift Binder	64.0								
430+01.72		436+50	cl After 1st Lift Binder	68.0								
419+13.64		426+31.72	cl After 2nd Lift Binder	72.0								
430+01.72		437+63.64	cl After 2nd Lift Binder	80.0								
417+83.33		426+31.72	cl After 3rd Lift Binder	88.0								
430+01.72		438+75	cl After 3rd Lift Binder	88.0								
415+00		426+31.72	cl After Surface	116.0		38.7						
430+01.72		442+00	cl After Surface	120.0		40.0						
426+31.72 Lt.		430+01.72 Lt.	Edgeline (4'/100')	16.0		5.3						
426+31.72 Rt.		430+01.72 Rt.	Edgeline (4'/100')	16.0		5.3						
415+00		442+00	cl		680.0	226.7						
415+01		442+00	Edgelines		5,400.0	1,800.0						
415+00		426+31.72	cl				290.0		15.0			15.0
415+00 Lt.		426+31.72 Lt.	Edgeline				1,131.7					
415+00 Rt.		426+31.72 Rt.	Edgeline				1,131.7					
430+01.72		442+00	cl				300.0					
430+01.72 Lt.		442+00 Lt.	Edgeline				1,198.3		15.0			15.0
430+01.72 Rt.		431+04 Rt.	Edgeline				102.3					
432+04 Rt.		442+00 Rt.	Edgeline				996.0					
426+31.72		430+01.72	cl					100.0		5.0		5.0
426+31.72 Lt.		430+01.72 Lt.	Edgeline					370.0				
426+31.72 Rt.		430+01.72 Rt.	Edgeline					370.0				
422+98		425+60	Stage 1 cl								23.3	
424+76.34 Lt.		431+57.10 Lt.	Stage 1 Edgeline								226.9	
430+70		433+41	Stage 1 cl								23.3	
430+69.22 Rt.		431+39.72 Rt.	Stage 2 Edgeline								23.5	
425+62.55 Rt.		424+93.72 Rt.	Stage 2 Edgeline								23.0	
TOTAL:				1,000.0	6,080.0	2,129.3	5,150.0	840.0	30.0	5.0	320.0	35.0
ROUND TO:				1,000.0	6,100.0	2,150.0	5,200.0	850.0	30.0	5.0	350.0	35.0