

SUMMARY OF QUANTITIES

CODE NO.	DESCRIPTION	CONSTRUCTION TYPE CODE: UNIT	LOCATION OF WORK:				
			EDGAR CO. FAP 749 IL 133 RURAL 2LN	EDGAR CO. FAP 749 IL 133 RURAL 2LN	EDGAR CO. FAP 749 IL 133 RURAL 2LN	EDGAR CO. FAP 749 IL 133 RURAL 2LN	EDGAR CO. FAP 749 IL 133 RURAL 2LN
FUNDING BREAKOUT:			80% FED. / 20% STATE	80% FED. / 20% STATE	80% FED. / 20% STATE	80% FED. / 20% STATE	80% FED. / 20% STATE
CONSTRUCTION TYPE CODE:			TOTAL	0011	0040	0040	0040
			QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY
20200100	EARTH EXCAVATION	CU YD	2,348.0	2,015.0	86.0	171.0	76.0
20300100	CHANNEL EXCAVATION	CU YD	1,020.0	1,020.0			
20400800	FURNISHED EXCAVATION	CU YD	1,521.0	1,301.0		154.0	66.0
20700220	POROUS GRANULAR EMBANKMENT	CU YD	164.0		55.0	58.0	51.0
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	615.0	615.0			
21301052	EXPLORATION TRENCH 52" DEPTH	FOOT	600.0		200.0	200.0	200.0
* 25000210	SEEDING, CLASS 2A	ACRE	2.25	1.25	0.25	0.50	0.25
* 25000350	SEEDING, CLASS 7	ACRE	0.5	0.5			
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	200.0	110.0	22.5	45.0	22.5
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	200.0	110.0	22.5	45.0	22.5
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	200.0	110.0	22.5	45.0	22.5
* 25100115	MULCH, METHOD 2	ACRE	0.75	0.75			
* 25100630	EROSION CONTROL BLANKET	SQ YD	6,682.0	2,355.0	1,169.0	2,109.0	1,049.0
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	225.0	125.0	25.0	50.0	25.0
28000305	TEMPORARY DITCH CHECKS	FOOT	611.0	182.0	182.0	156.0	91.0
28000400	PERIMETER EROSION BARRIER	FOOT	2,810.0		810.0	1,000.0	1,000.0
28000500	INLET AND PIPE PROTECTION	EACH	2.0		1.0		1.0
28100107	STONE RIPRAP, CLASS A4	SQ YD	936.0	936.0			
28100201	STONE RIPRAP, CLASS A1	TON	126.0		27.0	60.0	39.0
28200200	FILTER FABRIC	SQ YD	936.0	936.0			
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	161.0	84.0		39.0	38.0
40600300	AGGREGATE (PRIME COAT)	TON	2.0			1.0	1.0
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	79.0	79.0			

*SPECIALTY ITEMS

FILE NAME =	USER NAME = keyserb	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
cr:\pw\work\pwidot\keyserb\0104347\05706	8-sh1-S00.dgn	DRAWN -	REVISED -		749	148R,14CR,123CR	EDGAR	115	4			
	PLOT SCALE = 40.0000' / in.	CHECKED -	REVISED -		SCALE: SHEET NO. 1 OF 5 SHEETS STA. TO STA.			CONTRACT NO. 70618				
	PLOT DATE = 8/25/2011	DATE -	REVISED -		[ILLINOIS] FED. AID PROJECT							