

SUMMARY OF QUANTITIES

**LICE
ACBRF**

**L25E
ACF**

CODE NO.	DESCRIPTION	UNII	LOCATION OF WORK:				
			EDGAR CO. FAP 749 IL 133 RURAL 2LN	EDGAR CO. FAP 749 IL 133 RURAL 2LN S.N. 023-0034	EDGAR CO. FAP 749 IL 133 RURAL 2LN S.N. 023-8064	EDGAR CO. FAP 749 IL 133 RURAL 2LN S.N. 023-2018	EDGAR CO. FAP 749 IL 133 RURAL 2LN S.N. 023-8065
CONSTRUCTION TYPE CODE:			FUNDING BREAKOUT:				
			80% FED. / 20% STATE	80% FED. / 20% STATE	80% FED. / 20% STATE	80% FED. / 20% STATE	80% FED. / 20% STATE
			TOTAL QUANTITY	0011 QUANTITY	0040 QUANTITY	0040 QUANTITY	0040 QUANTITY
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	796.0	128.0		334.0	334.0
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	116.0	51.0		33.0	32.0
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1.0	1.0			
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	2.0	2.0			
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	47.0	47.0			
44000100	PAVEMENT REMOVAL	SQ YD	1,343.0	1,343.0			
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	10.0	10.0			
44004250	PAVED SHOULDER REMOVAL	SQ YD	39.0	39.0			
44201335	CLASS C PATCHES, TYPE IV, 8 INCH	SQ YD	187.0			112.0	75.0
44201347	CLASS C PATCHES, TYPE IV, 9 INCH	SQ YD	75.0		75.0		
44213100	PAVEMENT FABRIC	SQ YD	262.0		75.0	112.0	75.0
44213204	TIE BARS 3/4"	EACH	47.0		13.0	20.0	14.0
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	1,127.0	727.0	133.3	133.3	133.4
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	22.0	22.0			
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1.0	1.0			
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1.0		1.0		
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1.0			1.0	
50100500	REMOVAL OF EXISTING STRUCTURES NO. 3	EACH	1.0				1.0
50102400	CONCRETE REMOVAL	CU YD	8.8	8.8			
50105220	PIPE CULVERT REMOVAL	FOOT	50.0	50.0			
50200100	STRUCTURE EXCAVATION	CU YD	216.0	216.0			
50300100	FLOOR DRAINS	EACH	8.0	8.0			
50300225	CONCRETE STRUCTURES	CU YD	55.5	55.5			

*SPECIALTY ITEMS

FILE NAME :	USER NAME : keysrb	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwwork\pwwork\keysrb\0104347\05706	8-shr-500.dgn	DRAWN -	REVISED -		749	14BR,14CR,123CR	EDGAR	115	5			
	PLOT SCALE : 40.0000 ' / in.	CHECKED -	REVISED -		SCALE: SHEET NO. 2 OF 5 SHEETS STA. TO STA.			CONTRACT NO. 70618				
	PLOT DATE : 8/25/2011	DATE -	REVISED -		ILLINOIS FED. AID PROJECT							