

SCHEDULE OF QUANTITIES

SHORT TERM PAVEMENT MARKING (70300100)

O/S	STATION	TO	STATION	# OF APPS.	LENGTH (FT)
CL-SKIP DASH	126+42.04		126+67.96	1	4.0
CL-SKIP DASH	231+29.85		232+70.15	3	48.0
CL-SKIP DASH	412+19.00		413+69.00	1	16.0
CL-SKIP DASH	416+30.00		419+90.00	1	36.0
CL-SKIP DASH	423+18.00		424+68.00	1	16.0
CL-SKIP DASH	513+12.00		514+48.00	3	48.0
TOTAL =					168.0

LONG SPAN GUARDRAIL OVER CULVERT, 18FT 9IN SPAN (63000360)

O/S	STATION	TO	STATION	LENGTH (FT)
RT	125+70.63		127+39.38	168.8
TOTAL =				168.8

LONG SPAN GUARDRAIL OVER CULVERT, 25FT SPAN (63000370)

O/S	STATION	TO	STATION	LENGTH (FT)
LT	512+92.50		514+67.50	175.0
RT	512+92.50		514+67.50	175.0
TOTAL =				350.0

TRAFFIC BARRIER TERMINAL, TYPE 6 (63100085)

O/S	STATION	TO	STATION	EACH
RT	417+15.52		417+61.17	1.0
LT	417+27.26		417+72.91	1.0
RT	418+57.37		419+03.02	1.0
LT	418+69.00		419+14.65	1.0
TOTAL =				4.0

TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT) (63100167)

O/S	STATION	TO	STATION	EACH
RT	123+70.63		124+20.63	1.0
LT	125+67.50		126+17.50	1.0
LT	127+05.00		127+55.00	1.0
RT	127+39.38		127+89.38	1.0
SUB-TOTAL =				4.0
RT	229+12.50		229+62.50	1.0
LT	231+12.50		231+62.50	1.0
RT	232+37.50		232+87.50	1.0
LT	234+37.50		234+87.50	1.0
SUB-TOTAL =				4.0
RT	510+92.50		511+42.50	1.0
LT	512+42.50		512+92.50	1.0
RT	514+67.50		515+17.50	1.0
LT	516+17.50		516+67.50	1.0
SUB-TOTAL =				4.0
RT	414+78.02		415+28.02	1.0
LT	416+77.26		417+27.26	1.0
RT	419+03.02		419+53.02	1.0
LT	420+77.15		421+27.15	1.0
SUB-TOTAL =				4.0
TOTAL =				16.0

GUARDRAIL REMOVAL (63200310)

O/S	STATION	TO	STATION	LENGTH (FT)
RT	124+14.00		128+01.50	387.5
LT	125+06.60		127+69.10	262.5
RT	415+07.90		420+57.90	550.0
LT	415+94.10		421+44.10	550.0
TOTAL =				1750.0

TEMPORARY PAVEMENT MARKING - LINE 4" (70300220)

WHITE -

STATION	TO	STATION	LOCATION	FEET
126+42.04		126+67.96	12.0' LT	25.9
126+42.04		126+67.96	12.0' RT	25.9
231+29.85		232+70.15	11.0' LT	140.3
231+29.85		232+70.15	11.0' RT	140.3
413+00.00		414+35.00	11.0' LT	135.0
416+30.00		419+90.00	11.0' LT	360.0
416+30.00		419+90.00	11.0' RT	360.0
422+75.00		423+85.00	11.0' LT	110.0
513+12.00		514+48.00	11.0' LT	136.0
513+12.00		514+48.00	11.0' RT	136.0
SUB-TOTAL =				1570.0

YELLOW -

STATION	TO	STATION	LOCATION	FEET
126+42.04		126+67.96	SKIP-DASH	10.0
231+29.85		232+70.15	SKIP-DASH	40.0
412+19.00		413+69.00	SKIP-DASH	40.0
423+18.00		424+68.00	SKIP-DASH	40.0
416+30.00		419+90.00	SKIP-DASH	90.0
513+12.00		514+48.00	SKIP-DASH	40.0
SUB-TOTAL =				260.0
TOTAL =				1830.0

WORK ZONE PAVEMENT MARKING REMOVAL (70301000)

SHORT TERM

O/S	STATION	TO	STATION	LENGTH (FT)	WIDTH (FT)	SQ FT
CL-SKIP DASH	126+42.04		126+67.96	4.0	0.33	1.3
CL-SKIP DASH	231+29.85		232+70.15	16.0	0.33	5.3
CL-SKIP DASH	412+19.00		413+69.00	16.0	0.33	5.3
CL-SKIP DASH	416+30.00		419+90.00	36.0	0.33	12.0
CL-SKIP DASH	423+18.00		424+68.00	16.0	0.33	5.3
CL-SKIP DASH	513+12.00		514+48.00	16.0	0.33	5.3
SUB-TOTAL =						34.5

TEMPORARY RUNAROUND

RT-STOP BAR	412+19.00			12.0	2.0	24.0
LT-STOP BAR	424+68.00			12.0	2.0	24.0
RT-EDGE LINE	10+00.00		11+50.00	150.0	0.33	49.5
LT-EDGE LINE	10+00.00		10+50.00	50.0	0.33	16.5
RT-EDGE LINE	19+89.46		21+39.46	150.0	0.33	49.5
LT-EDGE LINE	20+89.46		21+39.46	50.0	0.33	16.5
SUB-TOTAL =						180.0

TEMPORARY PAVEMENT MARKINGS

SEE SCHEDULE FOR 70300220	1830.0	0.33	604.0
SUB-TOTAL =			604.0
TOTAL =			818.5
USE =			819.0

CATCH BASINS TO BE ADJUSTED (60250200)

STATION	OFFSET	EACH
126+54.00	35.0' RT	1.0
513+82.00	32.0' RT	1.0
TOTAL =		2.0

STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS (63000001)

O/S	STATION	TO	STATION	LENGTH (FT)
RT	124+20.63		125+70.63	150.0
LT	126+92.50		127+05.00	12.5
RT	229+62.50		231+62.50	200.0
LT	232+37.50		234+37.50	200.0
RT	511+42.50		512+42.50	150.0
LT	514+67.50		516+17.50	150.0
RT	415+28.02		417+15.52	187.5
LT	419+14.65		420+77.15	162.5
TOTAL =				1212.5

STEEL PLATE BEAM GUARDRAIL, TYPE B (63000005)

O/S	STATION	TO	STATION	LENGTH (FT)
LT	126+17.50		126+42.50	25.0
LT	126+67.50		126+92.50	25.0
RT	231+62.50		231+87.50	25.0
LT	231+62.50		231+87.50	25.0
RT	232+12.50		232+37.50	25.0
LT	232+12.50		232+37.50	25.0
TOTAL =				150.0

STEEL PLATE BEAM GUARDRAIL ATTACHED TO STRUCTURE (63000025)

O/S	STATION	TO	STATION	LENGTH (FT)
LT	126+42.50		126+67.50	25.0
LT	231+87.50		232+12.50	25.0
RT	231+87.50		232+12.50	25.0
TOTAL =				75.0