

# SCHEDULE OF QUANTITIES

**NOTE:**  
SEVERAL PAY ITEMS APPEAR AT MULTIPLE LOCATIONS THROUGHOUT THE PLANS.  
FOR GRAND TOTALS, SEE ALL SCHEDULES, PLAN SHEETS AND DETAILS.

## CLASS A PATCHING SCHEDULE, 8"

LOCATION	STATION	LENGTH (FT)	WIDTH (FT)	44200529 TYPE II, 8" (SQ YD)	44200533 TYPE III, 8" (SQ YD)	44200535 TYPE IV, 8" (SQ YD)	44213200 SAW CUTS (FT)	44213204 TIE BARS 3/4" (EACH)	44213000 PATCHING REINFORCEMENT (SQ YD)
E.B. D.L.	1121+43.00	20.00	12.00			26.66	88.00	10.00	26.66
E.B. D.L.	1124+17.00	6.00	12.00	8.00			60.00		8.00
E.B. D.L.	1125+56.00	6.00	12.00	8.00			60.00		8.00
E.B. D.L.	1128+33.00	30.00	12.00			40.00	108.00	15.00	40.00
E.B. D.L.	1128+60.00	12.00	12.00		16.00		72.00		16.00
E.B. D.L.	1128+94.00	8.00	12.00	10.67			64.00		10.67
E.B. D.L.	1132+50.00	15.00	12.00		20.00		78.00		20.00
E.B. D.L.	1196+00.00	40.00	12.00			53.33	128.00	20.00	53.33
E.B. D.L.	1196+70.00	8.00	12.00	10.67			64.00		10.67
E.B. D.L.	1201+24.00	6.00	12.00	8.00			60.00		8.00
E.B. D.L.	1202+77.00	6.00	12.00	8.00			60.00		8.00
E.B. D.L.	1207+70.00	8.00	12.00	10.67			64.00		10.67
E.B. D.L.	1211+06.00	20.00	12.00			26.66	88.00	10.00	26.66
E.B. D.L.	1218+34.00	6.00	12.00	8.00			60.00		8.00
E.B. D.L.	1226+30.00	40.00	12.00			53.33	128.00	20.00	53.33
E.B. D.L.	1227+25.00	30.00	12.00			40.00	108.00	15.00	40.00
E.B. D.L.	1229+85.00	6.00	12.00	8.00			60.00		8.00
E.B. D.L.	1232+80.00	10.00	12.00	13.33			68.00		13.33
E.B. D.L.	1238+80.00	12.00	12.00		16.00		72.00		16.00
E.B. D.L.	1239+70.00	6.00	12.00	8.00			60.00		8.00
E.B. D.L.	1240+28.00	6.00	12.00	8.00			60.00		8.00
E.B. D.L.	1240+50.00	30.00	12.00			40.00	108.00	15.00	40.00
E.B. D.L.	1241+00.00	10.00	12.00	13.33			68.00		13.33
E.B. D.L.	MISC.	6.00	12.00	8.00			60.00		8.00
E.B. D.L.	MISC.	6.00	12.00	8.00			60.00		8.00
E.B. D.L.	MISC.	6.00	12.00	8.00			60.00		8.00
W.B. D.L.	1151+00.00	6.00	12.00	8.00			60.00		8.00
W.B. D.L.	1201+00.00	10.00	12.00	13.33			68.00		13.33
W.B. D.L.	12+30.00	8.00	12.00	10.67			64.00		10.67
W.B. D.L.	MISC.	6.00	12.00	8.00			60.00		8.00
W.B. D.L.	MISC.	6.00	12.00	8.00			60.00		8.00
W.B. D.L.	MISC.	6.00	12.00	8.00			60.00		8.00
<b>TOTAL =</b>				202.67	52.00	279.98	2338.00	105.00	534.65
<b>USE =</b>				203.00	52.00	280.00	2338.00	105.00	535.00
				(SQ YD)	(SQ YD)	(SQ YD)	(FT)	(EACH)	(SQ YD)
<b>URBAN =</b>				35.00	36.00	67.00	590.00	25.00	138.00
<b>RURAL =</b>				168.00	16.00	213.00	1748.00	80.00	397.00
				(SQ YD)	(SQ YD)	(SQ YD)	(FT)	(EACH)	(SQ YD)

**NOTES:**

THE STATIONS LISTED FOR THE PATCHES ARE APPROXIMATE LOCATIONS.  
THE ACTUAL LOCATION AND SIZE SHALL BE FIELD VERIFIED AS SPECIFIED  
IN G.N.-442B.

THE LOCATION OF THE 8" PATCHES OCCUR IN THE SECTION OF PAVEMENT  
WHERE THE HOT-MIX ASPHALT RESURFACING WILL BE MILLED TO BARE  
CONCRETE. THE PATCHING OPERATIONS IN THESE AREAS SHALL NOT BE  
COMPLETED UNTIL AFTER THE EXISTING HOT-MIX ASPHALT MATERIAL IS  
REMOVED.

## CLASS A PATCHING SCHEDULE, 14"

LOCATION	STATION	LENGTH (FT)	WIDTH (FT)	44200620 TYPE II, 14" (SQ YD)	44200624 TYPE III, 14" (SQ YD)	44200628 TYPE IV, 14" (SQ YD)	44213200 SAW CUTS (FT)	44213204 TIE BARS 3/4" (EACH)	44213000 PATCHING REINFORCEMENT (SQ YD)
E.B. P.L.	1196+00.00	40.00	12.00			53.33	128.00	20.00	53.33
E.B. P.L.	1201+24.00	6.00	12.00	8.00			60.00		8.00
E.B. P.L.	1202+77.00	6.00	12.00	8.00			60.00		8.00
E.B. D.L.	246+58.00	6.00	12.00	8.00			60.00		8.00
E.B. D.L.	375+36.00	6.00	12.00	8.00			60.00		8.00
E.B. P.L.	375+70.00	6.00	12.00	8.00			60.00		8.00
E.B. P.L.	MISC.	6.00	12.00	8.00			60.00		8.00
E.B. P.L.	MISC.	12.00	12.00		16.00		72.00		16.00
E.B. P.L.	MISC.	20.00	12.00			26.67	88.00	10.00	26.67
W.B. P.L.	1133+32.00	6.00	12.00	8.00			60.00		8.00
W.B. P.L.	1201+00.00	20.00	12.00			26.67	88.00	10.00	26.67
W.B. P.L.	375+50.00	6.00	12.00	8.00			60.00		8.00
W.B. P.L.	MISC.	6.00	12.00	8.00			60.00		8.00
W.B. P.L.	MISC.	6.00	12.00	8.00			60.00		8.00
W.B. P.L.	MISC.	12.00	12.00		16.00		72.00		16.00
RAMP CB	MISC	6.00	16.00		10.67		76.00		10.67
RAMP CB	MISC	6.00	16.00		10.67		76.00		10.67
RAMP BD	MISC	6.00	16.00		10.67		76.00		10.67
RAMP BD	MISC	6.00	16.00		10.67		76.00		10.67
RAMP AC	MISC	6.00	16.00		10.67		76.00		10.67
RAMP AC	MISC	6.00	16.00		10.67		76.00		10.67
RAMP DA	MISC	6.00	16.00		10.67		76.00		10.67
RAMP DA	MISC	6.00	16.00		10.67		76.00		10.67
<b>TOTAL =</b>				80.00	117.36	106.67	1656.00	40.00	304.03
<b>USE =</b>				80.00	117.00	107.00	1656.00	40.00	304.00
				(SQ YD)	(SQ YD)	(SQ YD)	(FT)	(EACH)	(SQ YD)
<b>URBAN =</b>				8.00			60.00		8.00
<b>RURAL =</b>				72.00	117.00	107.00	1596.00	40.00	296.00
				(SQ YD)	(SQ YD)	(SQ YD)	(FT)	(EACH)	(SQ YD)

**NOTES:**

THE STATIONS LISTED FOR THE PATCHES ARE APPROXIMATE LOCATIONS.  
THE ACTUAL LOCATION AND SIZE SHALL BE FIELD VERIFIED AS SPECIFIED  
IN G.N.-442B

THE LOCATION OF THE 14" PATCHES OCCUR IN THE SECTION OF PAVEMENT  
WHERE THERE IS NO MILLING IN THE DRIVING LANE OR RAMPS, AND ONLY  
2" MILLING IN THE PASSING LANE. THE PATCHING OPERATIONS IN THESE  
AREAS SHALL BE COMPLETED PRIOR TO ANY MILLING OR RESURFACING  
OPERATIONS.