

SUMMARY OF QUANTITIES

FAP326 (IL47)
 CHAMPAIGN
 COUNTY
 RURAL
 TWO LANE
 FUNDING BREAKOUT: 80 % FEDERAL
 20% STATE
 CONSTRUCTION CODE: 0005

FAP326 (IL47)
 CHAMPAIGN
 COUNTY
 RURAL
 TWO LANE
 FUNDING BREAKOUT: 80 % FEDERAL
 20% STATE
 CONSTRUCTION CODE: 0005

CODE NO	ITEM	UNIT	QUANTITY
20800150	TRENCH BACKFILL	CU YD	3.00
*25000200	SEEDING, CLASS 2	ACRE	0.25
*25000400	NITROGEN FERTILIZER NUTRIENT	POUND	23.0
*25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	23.0
*25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	23.0
*25100630	EROSION CONTROL BLANKET	SQ YD	570.00
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	25.00
28100205	STONE RIPRAP CLASS A3	TON	15.0
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	10,402.0
40600300	AGGREGATE (PRIME COAT)	TON	208.0
40600895	CONSTRUCTING TEST STRIP	EACH	2.0
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	3,896.0
40600990	TEMPORARY RAMP	SQ YD	380.0
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	8,738.0
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	390.0
40800030	AGGREGATE (PRIME COAT)	TON	9.0
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	366.0
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	103,752.0
44201729	CLASS D PATCHES, TYPE II, 7 INCH	SQ YD	447.0
44201733	CLASS D PATCHES, TYPE III, 7 INCH	SQ YD	364.0
44201735	CLASS D PATCHES, TYPE IV, 7 INCH	SQ YD	1,320.0
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1,594.0
542A1093	PIPE CULVERTS, CLASS A, TYPE II, 48 INCH	FOOT	8.0
*63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	1,263.0
*63000003	STEEL PLATE BEAM GUARDRAIL, TYPE A, 9 FOOT POSTS	FOOT	1,738.0

CODE NO	ITEM	UNIT	QUANTITY
*63000005	STEEL PLATE BEAM GUARDRAIL, TYPE B	FOOT	300.0
*63000025	STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURES	FOOT	126.0
*63100167	TRAFFIC BARRIER TERMINAL, TYPE 1(SPECIAL) TANGENT	EACH	12.0
*63100169	TRAFFIC BARRIER TERMINAL, TYPE 1(SPECIAL) FLARED	EACH	4.0
63200310	GUARDRAIL REMOVAL	FOOT	3,668.0
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	3.0
67100100	MOBILIZATION	L SUM	1.0
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1.0
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1.0
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	8,570.0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	952.0
*78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	73,364.0
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	424.0
*78200420	GUARDRAIL MARKERS, TYPE B	EACH	48.0
*78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	16.0
*78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	424.0
X4060637	LEVELING BINDER (MACHINE METHOD), IL9.5 FG, N70	TON	4,369.0
X4820110	HOT-MIX ASPHALT SHOULDER REMOVAL & REPLACEMENT (SPECIAL)	SQ YD	530.0
X5427600	REMOVE & RELOCATE END SECTION	EACH	1.0
XZ193300	SURVEY MARKER, TYPE 1(SPECIAL)	EACH	10.0
Z0070202	SURVEY MARKER VAULT	EACH	2.0

* SPECIALTY ITEM

FILE NAME =	USER NAME = bucklesj	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\puidet\bucksj\0180660\052706-shr-500.dgn	DRAWN -	REVISED -	326					129RS-3	Champaign	24	3	
PLOT SCALE = 40.0000' / 1"	CHECKED -	REVISED -	CONTRACT NO. 70706									
PLOT DATE = 8/15/2011	DATE -	REVISED -	ILLINOIS FED. AID PROJECT									