

SUMMARY OF QUANTITIES

CODENO.	ITEM	UNITS	TOTAL	CONSTRUCTION TYPE CODE	
				20% STATE / 80% FEDERAL	
				ROADWAY	BRIDGE
				0004	0011
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	133		133
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	3298	3298	
* X7200201	WIDTH RESTRICTION SIGNING	L SUM	1	1	
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	30		30
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
* Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	2	2	
* Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	112		112
Z0073002	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	370		370
Z0100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	6	6	
Z0200100	EARTH EXCAVATION	CU YD	76	76	
Z0300100	CHANNEL EXCAVATION	CU YD	971	971	
Z8100107	STONE RIP RAP, CLASS A4	SQ YD	990		990
Z8200200	FILTER FABRIC	SQ YD	990		990
Z35101400	AGGREGATE BASE COURSE, TYPE B	TON	48	48	
Z35501324	HOT-MIX ASPHALT BASE COURSE, 10"	SQ YD	861	861	
Z40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	25	25	
Z40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	4	4	
Z40600300	AGGREGATE (PRIME COAT)	TON	11	11	
Z40600682	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	155	155	
Z40800090	TEMPORARY RAMP	SQ YD	155	155	
Z40803310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	243	243	
Z40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	25	25	
Z42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	48	48	
Z44000100	PAVEMENT REMOVAL	SQ YD	278	278	
Z44004250	PAVED SHOULDER REMOVAL	SQ YD	1272	1272	
Z48101200	AGGREGATE SHOULDERS, TYPE B	TON	206	206	
Z48203100	HOT-MIX ASPHALT SHOULDERS	TON	126	126	
Z50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1
Z50200100	STRUCTURE EXCAVATION	CU YD	228		228
Z50300100	FLOOR DRAINS	EACH	8		8
Z50300225	CONCRETE STRUCTURES	CU YD	56.4		56.4
Z50300255	CONCRETE SUPERSTRUCTURE	CU YD	234.8		234.8
Z50300260	BRIDGE DECK GROOVING	SQ YD	510		510
Z50300280	CONCRETE ENCASMENT	CU YD	6.6		6.6
Z50300300	PROTECTIVE COAT	SQ YD	636		636
Z50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1
Z50500505	STUD SHEAR CONNECTORS	EACH	1890		1890
Z50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	58410		58410
Z50800515	BAR SPLICERS	EACH	567		567
Z51201800	FURNISHING STEEL PILES HP14 X 73	FOOT	490		490
Z51202305	DRIVING PILES	FOOT	490		490
Z51203800	TEST PILE STEEL HP14 X 73	EACH	2		2
Z51500100	NAME PLATES	EACH	1		1
Z52100520	ANCHOR BOLTS, 1"	EACH	24		24
Z59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	87		87
* Z63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	262.5	262.5	

\*SPECIALTY ITEM

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNITS	TOTAL	CONSTRUCTION TYPE CODE	
				20% STATE / 80% FEDERAL	
				ROADWAY	BRIDGE
				0004	0011
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4		4
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)	EACH	4		4
63200310	GUARDRAIL REMOVAL	FOOT	708		708
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8		8
67100100	MOBILIZATION	L SUM	1		1
70100405	TRAFFIC CONTROL AND PROTECTION STANDARD, 701321	EACH	1		1
70100460	TRAFFIC CONTROL AND PROTECTION STANDARD, 701306	L SUM	1		1.0
70100600	TRAFFIC CONTROL AND PROTECTION STANDARD, 701326	L SUM	1		1.0
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5		5
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1		1
70300100	SHORT TERM PAVEMENT MARKING	FOOT	176		176
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	2140		2140
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	30		30
70400100	TEMPORARY CONCRETE BARRIER	FOOT	425		425
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	425		425
* 78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	2140		2140
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	12		12
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	10		10
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4		4
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1749		1749
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	12		12

FILE NAME =	USER NAME = sparksgv	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 40.0001' / in.	CHECKED -	REVISED -
	PLOT DATE = Sep-09-2011 11:34:29AM	DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE:	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
				42	105B-1	MONTGOMERY	63	3
				CONTRACT NO. 72B66				
				FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				