

EARTHWORK SCHEDULE		STAGE	EARTH EXCAVATION	EMBANKMENT ADJUSTED FOR SHRINKAGE	SHRINKAGE FACTOR	EMBANKMENT (NOT A PAY ITEM)	EARTHWORK BALANCE	CHANNEL EXCAVATION
STATION TO	STATION		CU YD	CU YD		CU YD	CU YD	CU YD
306+50.00	TO 311+17.50	RT I	19.28	12.96	25%	10.37	6.3	
306+50.00	TO 311+17.50	LT II	16.72	12.02	25%	9.62	4.7	
311+17.50	TO 312+22.50	LT & RT I/II						971
311+92.50	TO 316+00.00	RT I	20.93	15.66	25%	12.53	5.3	
311+92.50	TO 316+00.00	LT II	18.77	16.64	25%	13.31	2.1	
TOTAL			75.70	57.28		45.83	18.4	971

SHOULDER SCHEDULE		HMA SHOULDER	AGGREGATE SHOULDERS, TYPE B	EARTH EXCAVATION	NOTES
STATION TO	STATION	TON	TON	CU YD	
STAGE 1 CONSTRUCTION					
STA 308+97.25	TO 310+87.50	RT	46.8	8.8	
STA 312+22.50	TO 314+75.00	RT	63.9	10.8	
STAGE 2 CONSTRUCTION					
STA 309+40.00	TO 310+87.50	LT	37.3	6.8	
STA 312+22.50	TO 314+75.00	LT	58.2	9.7	
FINAL STAGE CONSTRUCTION					
STA 306+50.00	TO 310+87.50	LT	36.3		
STA 306+50.00	TO 310+87.50	RT	41.3		
STA 312+22.50	TO 316+00.00	LT	24.0		
STA 312+22.50	TO 316+00.00	RT	24.0		
TOTAL			125.6	206.3	36.1

PAVEMENT REMOVAL SCHEDULE		HMA SURFACE REMOVAL - BUTT JOINT	PAVEMENT REMOVAL	HMA REMOVAL (VARIABLE DEPTH)	PAVED SHOULDER REMOVAL	TEMPORARY RAMP	NOTES
STATION TO	STATION	SO YD	SO YD	SO YD	SO YD	SO YD	
PRE-STAGE 1 CONSTRUCTION							
STA 309+18.00	TO 311+33.70	LT			143.8		
STA 311+76.30	TO 314+75.00	LT			196.4		
STAGE 1 CONSTRUCTION							
STA 308+55.00	TO 311+33.70	RT			356.1		
STA 311+76.30	TO 314+75.00	RT			309.2		
STA 310+81.50	TO 311+33.70	RT	69.6				
STA 311+76.30	TO 312+28.50	RT	69.6				
STAGE 2 CONSTRUCTION							
STA 309+18.00	TO 311+33.70	LT			131.8		
STA 310+81.50	TO 311+33.70	LT	69.6				
STA 311+76.30	TO 314+75.00	LT			135.1		
STA 311+76.30	TO 312+28.50	LT	69.6				
FINAL STAGE CONSTRUCTION							
STA 306+50.00	TO 306+60.00	LT/RT	40.6			40.6	
STA 306+50.00	TO 310+87.50	LT/RT		1860.2			
STA 310+77.50	TO 310+87.50	LT/RT	40.0			40.0	
STA 312+22.50	TO 316+00.00	LT/RT		1435.0			
STA 312+22.50	TO 312+32.50	LT/RT	40.0			40.0	
STA 315+90.00	TO 316+00.00	LT/RT	34.4			34.4	
TOTAL			155.0	278.4	3,298.2	1,272.4	155.0

ENTRANCE SCHEDULE		INCIDENTAL HMA SURFACING	AGGREGATE BASE COURSE TYPE B	AGGREGATE SURFACE COURSE TYPE B	BIT. MAT PRIME COAT	AGGREGATE PRIME COAT	NOTES
TYPE	STATION	TON	TON	TON	TON	TON	
PE + MAILBOX TURNOUT	STA 308+67.50	10.4	26.4		0.08	0.11	
FE	STA 309+31.51	3.8	11.3		0.03	0.04	
FE	STA 314+17.56	3.3	9.5		0.02	0.03	
ENGINEER DISCRETION		7.5		25			
TOTAL		25	47.2	25	0.13	0.18	

GUARDRAIL REMOVAL SCHEDULE		GUARDRAIL REMOVAL	NOTES
STATION TO	STATION	FOOT	
STAGE 1 CONSTRUCTION			
STA 309+37.80	TO 311+33.80	RT	196.0
STA 311+76.30	TO 313+09.80	RT	133.5
STAGE 2 CONSTRUCTION			
STA 309+50.70	TO 311+33.70	LT	183.0
STA 311+76.30	TO 313+71.90	LT	195.6
TOTAL			708.1

TEMPORARY CONCRETE BARRIER SCHEDULE		TEMPORARY CONCRETE BARRIER	NOTES
STATION TO	STATION	FOOT	
STAGE 1 CONSTRUCTION			
STA 309+45.00	TO 313+65.00	LT	425.0
TOTAL		425.0	

RELOCATE TEMPORARY CONCRETE BARRIER SCHEDULE		RELOCATE TEMPORARY CONCRETE BARRIER	NOTES
STATION TO	STATION	FOOT	
STAGE 2 CONSTRUCTION			
STA 309+45.00	TO STA 313+65.00	RT	425.0
TOTAL		425.0	