

IMPACT ATTENUATORS SCHEDULE		IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE) NARROW, TEST LEVEL 3 EACH	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE) NARROW, TEST LEVEL 3 EACH	NOTES
STATION				
STAGE 1 CONSTRUCTION				
STA 309+45.00	LT	1		
STA 313+65.00	LT	1		
STAGE 2 CONSTRUCTION				
STA 309+45.00	RT		1	
STA 313+65.00	RT		1	
TOTAL		2	2	

GUARDRAIL SCHEDULE	TRAFFIC BARRIER TERMINAL, TYPE 6 EACH	TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL (TANGENT) EACH	STEEL PLATE BEAM GUARDRAIL TYPE A 6' POSTS FOOT	TERMINAL MARKER DIRECT APPLIED EACH	GUARDRAIL MARKERS, TYPE A EACH	NOTES
STATION TO STATION						
STAGE 1 CONSTRUCTION						
STA 309+21.85 TO 310+71.85	RT	1		1		
STA 309+71.85 TO 313+25.65	RT				5	
STA 309+71.85 TO 310+59.35	RT		87.5			
STA 310+59.35 TO 311+03.10	RT	1				
STA 312+06.90 TO 312+50.65	RT	1				
STA 312+50.65 TO 312+75.65	RT		25.0			
STA 312+75.65 TO 313+25.65	RT	1		1		
STAGE 2 CONSTRUCTION						
STA 309+59.35 TO 310+09.35	LT	1		1		
STA 309+59.35 TO 313+50.65	LT				5	
STA 310+09.35 TO 310+59.35	LT		50.0			
STA 310+59.35 TO 311+03.10	LT	1				
STA 312+06.90 TO 312+50.65	LT	1				
STA 312+50.65 TO 313+50.65	LT		100.0			
STA 313+50.65 TO 314+00.65	LT	1		1		
TOTAL		4	4	4	10	

PAVEMENT SCHEDULE	BITUMIONOUS MATERIALS (PRIME COAT) TON	AGGREGATE PRIME COAT TON	HMA SURFACE COURSE MIX "C", N50 TON	HMA BASE COURSE 10" SY	NOTES
STATION TO STATION					
PRE-STAGE 1 CONSTRUCTION					
STA 309+18.00 TO 311+33.70	LT	0.21		143.8	
STA 311+76.30 TO 314+75.00	LT	0.28		196.4	
STAGE 1 CONSTRUCTION					
STA 308+55.00 TO 310+87.50	RT	0.22		155.0	
STA 312+22.50 TO 314+75.00	RT	0.24		165.6	
FINAL STAGE CONSTRUCTION					
STA 306+50.00 TO 310+87.50	LT/RT	1.73	5.87	130.7	
STA 312+22.50 TO 316+00.00	LT/RT	1.18	4.60	112.7	
TOTAL		3.86	10.47	243.4	660.7

PAVEMENT MARKING SCHEDULE	SHORT TERM PAVEMENT MARKING FOOT	TEMPORARY PAVEMENT MARKING-LINE 5" (YELLOW-SKIP) FOOT	TEMPORARY PAVEMENT MARKING-LINE 5" (WHITE-SOLID) FOOT	PAINT PAVEMENT MARKING-LINE 5" (YELLOW - SKIP) FOOT	PAINT PAVEMENT MARKING-LINE 5" (WHITE-SOLID) FOOT	PAVEMENT MARKING REMOVAL SQ FT	WORK ZONE PAVEMENT MARKING REMOVAL SQ FT	RAISED REFLECTIVE PAVEMENT MARKER EACH
STATION TO STATION								
STAGE 1 CONSTRUCTION								
STA 307+35.00 TO 309+11.65	CL					18.4		
STA 308+55.00 TO 314+55.00	LT					250.0		
STA 313+82.55 TO 315+85.00	CL					21.1		
STAGE 2 CONSTRUCTION								
STA 307+35.00 TO 315+85.00	LT					334.2		
STA 308+55.00 TO 314+55.00	LT					250.0		
STA 309+11.65 TO 309+44.35	CL					3.4		
STA 308+55.00 TO 314+55.00	RT					250.0		
FINAL STAGE CONSTRUCTION								
STA 307+35.00 STOP BAR						24.0		
STA 307+35.00 TO 315+85.00	RT					324.2		
STA 308+55.00 TO 314+55.00	RT					250.0		
STA 315+85.00 STOP BAR						24.0		
STA 306+50.00 TO 318+00.00	LT/RT/CL	176	240	1,900	240	1,900	30	12
TOTAL		176	240	1,900	240	1,749.3	30	12

BRIDGE APPROACH PAVEMENT CONNECTOR SCHEDULE	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE) SQ YD	NOTES
STATION TO STATION		
STAGE 1 CONSTRUCTION		
STA 310+81.50 TO 310+87.50	RT	12.0
STA 312+22.50 TO 312+28.50	RT	12.0
STAGE 2 CONSTRUCTION		
STA 310+81.50 TO 310+87.50	LT	12.0
STA 312+22.50 TO 312+28.50	LT	12.0
TOTAL		48.0