

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES				90% FEDERAL 10% STATE	SUMMARY OF QUANTITIES				90% FEDERAL 10% STATE
SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE	SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE
CODE NO.	ITEM	UNIT	TOT. QUAN.	0005	CODE NO.	ITEM	UNIT	TOT. QUAN.	0005
X0301183	GEOMETRICALLY PROGRAMMED LOUVER	EACH	4	4	60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	33	33
X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - VARIABLE DEPTH	SO YD	102	102	60610400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	FOOT	97	97
X4402020	CONCRETE MEDIAN SURFACE REMOVAL	SO FT	687	687	60618300	CONCRETE MEDIAN SURFACE 4"	SO FT	1,062	1,062
Z0010688	CAMERA MOUNTING ASSEMBLY	EACH	3	3	60625900	PCC RAMPED MEDIAN TERMINAL	EACH	3	3
Z0033072	VIDEO VEHICLE DETECTION SYSTEM	EACH	1	1	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	35	35	67100100	MOBILIZATION	L SUM	1	1
21400100	GRADING AND SHAPING DITCHES	FOOT	955	955	70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1
28100107	STONE RIPRAP, CLASS A4	SO YD	96	96	70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1
28200200	FILTER FABRIC	SO YD	96	96	70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
31100700	SUBBASE GRANULAR MATERIAL, TYPE A 8"	SO YD	197	197	70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1
35101400	AGGREGATE BASE COURSE, TYPE B	TON	7	7	70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1
35400400	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 9"	SO YD	8	8	70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
35501320	HOT-MIX ASPHALT BASE COURSE, 9"	SO YD	84	84	70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	10
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	7	7	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	507	507
40600300	AGGREGATE (PRIME COAT)	TON	24	24	70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	125	125
40600895	CONSTRUCTING TEST STRIP	EACH	1	1	70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	8,091	8,091
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	149	149	70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	732	732
40600990	TEMPORARY RAMP	SO YD	75	75	70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	525	525
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	982	982	70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	507	507
44000100	PAVEMENT REMOVAL	SO YD	77	77	70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	95	95
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO YD	9,866	9,866	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	85	85
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	172	172	72000100	SIGN PANEL -TYPE 1	SO FT	24	24
44004250	PAVED SHOULDER REMOVAL	SO YD	1,083	1,083	78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	7,948	7,948
44200144	PAVEMENT PATCHING, TYPE II, 12 INCH	SO YD	50	50	78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	525	525
44200148	PAVEMENT PATCHING, TYPE III, 12 INCH	SO YD	50	50	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	507	507
44200150	PAVEMENT PATCHING, TYPE IV, 12 INCH	SO YD	50	50	78004200	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LETTERS AND SYMBOLS	SO FT	125	125
48101200	AGGREGATE SHOULDERS, TYPE B	TON	158	158	78004220	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 5"	FOOT	143	143
48203023	HOT-MIX ASPHALT SHOULDERS 6 1/2"	SO YD	1,946	1,946	78004230	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 6"	FOOT	732	732
50105220	PIPE CULVERT REMOVAL	FOOT	25	25	78004280	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 24"	FOOT	95	95
54215559	METAL END SECTIONS 24"	EACH	4	4	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	102	102
54200229	PIPE CULVERTS, CLASS D, TYPE 1 24"	FOOT	52	52					
60603500	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.06	FOOT	51	51					