

SCHEDULE OF QUANTITIES

HOT-MIX ASPHALT SURFACE REMOVAL

TYP. SEC. #	LOCATION		QUANTITY	
			BUTT JOINT	1.5"
			(SQ YD)	(SQ YD)
	[F. A. U. 8159 (OLD US 66/PALM RD)]			
(1)	STA. 188+97.00	TO STA. 189+07.00	27.78	
(1)	STA. 189+07.00	TO STA. 191+00.00		536.11
(2)	STA. 191+00.00	TO STA. 194+90.00		1,702.65
	[F. A. U. 8159 (OLD US 66/E. LAKE SHORE DR NB)]			
(3)	STA. 194+90.00	TO STA. 196+84.00		587.39
(3-6)	STA. 196+84.00	TO STA. 205+90.00		2,466.33
(6)	STA. 205+90.00	TO STA. 206+00.00	27.22	
	[F. A. U. 8159 (OLD US 66/E. LAKE SHORE DR SB)]			
(3)	STA. 194+90.00	TO STA. 197+65.00		704.03
(4)	STA. 197+65.00	TO STA. 198+52.80		247.14
(4)	STA. 198+52.80	TO STA. 199+64.10		329.79
(5)	STA. 199+64.10	TO STA. 201+04.47		402.91
	REMAINING INTERSECTION AREA BETWEEN EXISTING MEDIANS (MEASURED USING CADD)			170.16
(6)	STA. 201+04.47	TO STA. 205+90.00		1,321.72
(6)	STA. 205+90.00	TO STA. 206+00.00	27.22	
	[F. A. U. 7998 (CHATHAM RD EB)]			
(7)	STA. 96+72.00	TO STA. 96+82.00	30.56	
(7)	STA. 96+72.00	TO STA. 97+35.52		176.44
(7)	STA. 97+35.52	TO STA. 98+35.00		269.89
	EB RIGHT TURN LANE ONTO SB PALM RD. (MEASURED USING CADD)			277.36
	FRONT OF MEDIAN ON CHATHAM RD. (MEASURED USING CADD)			20.87
	[F. A. U. 7998 (CHATHAM RD WB)]			
(7)	STA. 96+72.00	TO STA. 96+82.00	36.11	
(7)	STA. 96+72.00	TO STA. 98+35.00		365.25
(7)	STA. 96+82.00	TO STA. 97+35.52		47.57
	RT TURN LANE ON SB E. LAKE SHORE DR. ONTO WB CHATHAM RD. (MEASURED USING CADD)			240.30
PROJECT TOTAL			149	9,866

PORTLAND CEMENT CONCRETE SURFACE REMOVAL - VARIABLE DEPTH

TYP. SEC. #	LOCATION	QUANTITY (SQ YD)
	[F. A. U. 8159 (OLD US 66/PALM RD.)]	
(2)	STA. 193+63.00 TO STA. 194+90.00	70.56
(3)	STA. 194+90.00 TO STA. 195+84.00	31.33
PROJECT TOTAL		102

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL

LOCATION	QUANTITY (EACH)	
COUNTED IN FIELD		
[F. A. U. 8159 (OLD US 66/PALM RD)] NB	23	
[F. A. U. 8159 (OLD US 66/PALM RD)] SB	46	
[F. A. U. 7998 (CHATHAM RD)] EB	6	
[F. A. U. 7998 (CHATHAM RD)] WB	3	
PROJECT TOTAL		78

CONCRETE MEDIAN SURFACE REMOVAL

TYP. SEC. #	LOCATION	QUANTITY (SQ FT)
	[F. A. U. 8159 (PALM RD/E. LAKE SHORE DR)] (MEASURED USING CADD)	
(4-5)	STA. 198+80.00 TO STA. 199+50.00	
(5)	STA. 200+46.00 TO STA. 200+62.00	
	[F. A. U. 7998 (CHATHAM RD)] WB (MEASURED USING CADD)	
	STA. 97+75.00 TO STA. 97+79.00	
TOTAL TRAFFIC QUANTITIES=		564
(7)	STA 98+21 46.53' RT	122.4
PROJECT TOTAL		687