

PAVED SHOULDER REMOVAL

PALM RD/ E. LAKE SHORE DR.

STATION	TO	STATION		AVG WIDTH	AVG WIDTH	QUANTITY (SQ YD)		TOTAL (SQ YD)	STATION	TO	STATION		AVG WIDTH NB	AVG WIDTH SB	QUANTITY (SQ YD)		TOTAL (SQ YD)
						NB	SB								NB	SB	
205+00.00		205+25.00	RT	3.31		9.19		9.19									
205+25.00		205+50.00	LT		3.30		9.17	9.17									
205+25.00		205+50.00	RT		3.13		8.69	8.69									
205+25.00		205+50.00	LT	3.22		8.94		8.94									
205+25.00		205+50.00	RT	3.38		9.38		9.38									
205+50.00		205+75.00	LT		3.28		9.10	9.10									
205+50.00		205+75.00	RT		3.11		8.64	8.64									
205+50.00		205+75.00	LT	3.27		9.08		9.08									
205+50.00		205+75.00	RT	3.37		9.36		9.36									
205+75.00		206+00.00	LT		3.23		8.97	8.97									
205+75.00		206+00.00	RT		3.04		8.44	8.44									
205+75.00		206+00.00	LT	3.24		8.99		8.99									
205+75.00		206+00.00	RT	3.31		9.19		9.19									
PROJECT SUB-TOTAL (SQ YD) PG 3								117.16									0.00

PROJECT TOTAL (SQ YD)																	1,083
-----------------------	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	-------

EXCAVATING AND GRADING EXISTING SHOULDERS

TYP. SEC. #	LOCATION				QUANTITY (UNIT)
	(UNIT = 100 ft)				
	[ F. A. U. 8159 (OLD US 66)]				
(1-4)	STA. 188+97.00	TO	STA. 198+54.00	LT & RT	19.14
(4-5)	STA. 198+54.00	TO	STA. 201+04.47	RT	2.50
(6)	STA. 201+04.47	TO	STA. 206+00.00	LT & RT	9.91
	[ F. A. U. 7998 (CHATHAM RD)]				
(7)	STA. 96+72.00	TO	STA. 98+35.00	LT & RT	3.26
PROJECT TOTAL					36

TEMPORARY RAMP

TYP. SEC. #	LOCATION		QUANTITY (SQ YD)
	[ F. A. U. 8159 (OLD US 66/PALM RD)]		
(1)	STA. 188+97.00	TO STA. 189+02.00	13.89
	[ F. A. U. 8159 (OLD US 66/E. LAKE SHORE DR NB)]		
(6)	STA. 205+95.00	TO STA. 206+00.00	13.61
	[ F. A. U. 8159 (OLD US 66/E. LAKE SHORE DR SB)]		
(6)	STA. 205+95.00	TO STA. 206+00.00	13.61
	[ F. A. U. 7998 (CHATHAM RD WB)]		
(7)	STA. 96+77.00	TO STA. 96+82.00	15.28
	[ F. A. U. 7998 (CHATHAM RD EB)]		
(7)	STA. 96+77.00	TO STA. 96+82.00	18.06
PROJECT TOTAL			75

FILE NAME =	USER NAME = sparksgw	DESIGNED - JWC	REVISED -
c:\pw\work\p\dot\sparksgw\0221228\d672087-sht-schedule.dgn		DRAWN - JWC	REVISED -
	PLOT SCALE = 100.0000' / 1in.	CHECKED - RSC	REVISED -
	PLOT DATE = Sep-01-2011 12:34:44PM	DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: 50 SHEET NO. 5 OF 11 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
7998	110TS,NL	SANGAMON	95	15
CONTRACT NO. 72C87			ILLINOIS FED. AID PROJECT	