

SCHEDULE OF QUANTITIES

HOT-MIX ASPHALT SHOULDERS 6 1/2"

TYP. SEC. #	LOCATION	QUANTITY (SQ YD)
	[F. A. U. 8159 (OLD US 66/PALM RD)]	
(1-2)	STA. 188+97.00 TO STA. 191+38.00	214.22
	[F. A. U. 8159 (PALM RD/E. LAKE SHORE DR)] NB	
(2-6)	STA. 191+38.00 TO STA. 201+05.00 RT	429.78
(6)	STA. 201+05.00 TO STA. 206+00.00	440.00
	[F. A. U. 8159 (PALM RD.)] SB	
(2-4)	STA. 191+38.00 TO STA. 198+54.00 LT	318.22
	(No HMA Shoulder fr. 198+54.00 to 201+12.00 LT)	
(6)	STA. 201+05.00 TO STA. 201+12.00 RT	3.11
(6)	STA. 201+12.00 TO STA. 206+00.00	433.78
	[F. A. U. 7998 (CHATHAM RD)] WB	
(7)	STA. 96+82.00 TO STA. 97+14.00	28.44
(7)	STA. 97+14.00 TO STA. 97+40.50	18.67
(7)	(NW Quadrant of Turning Shoulder)	59.24
PROJECT TOTAL		1,946

AGGREGATE SHOULDER, TYPE B

TYP. SEC. #	LOCATION	QUANTITY (TON)
	[F. A. U. 8159 (OLD US 66/PALM RD)]	
(1-2)	STA. 188+97.00 TO STA. 191+38.00	18.30
	[F. A. U. 8159 (PALM RD./E. LAKE SHORE DR)] NB	
(2-6)	STA. 191+38.00 TO STA. 201+05.00 RT	36.71
(6)	STA. 201+05.00 TO STA. 206+00.00	37.58
	[F. A. U. 8159 (PALM RD.)] SB	
(2-4)	STA. 191+38.00 TO STA. 198+70.00 LT	27.79
	(No Aggregate Shoulder fr. 198+70.00 to 201+12.00 LT)	
(6)	STA. 201+05.00 TO STA. 201+23.00 RT	0.68
(6)	STA. 201+12.00 TO STA. 201+23.00 LT	0.42
(6)	STA. 201+23.00 TO STA. 206+00.00	36.22
PROJECT TOTAL		158

CONCRETE MEDIAN SURFACE 4"

TYP. SEC. #	LOCATION	QUANTITY (SQ FT)
	[F. A. U. 8159 (PALM RD/E. LAKE SHORE DR)] (MEASURED USING CADD)	
(4-5)	STA. 198+80.00 TO STA. 199+50.00	
(5)	STA. 200+46.00 TO STA. 200+62.00	
	[F. A. U. 7998 (CHATHAM RD)] WB	
	STA. 97+75.00 TO STA. 97+79.00	
	TOTAL OF TRAFFIC QUANTITIES=	538
	(NW QUADRANT OF INTERSECTION) (CONCRETE ISLAND) (MEASURED USING CADD)	
	CL of Concrete Island Sta. 98+26.00 32.52' LT	156.48
	[F. A. U. 7998 (CHATHAM RD)] EB (SW QUADRANT OF INTERSECTION) (CONCRETE ISLAND) (MEASURED USING CADD)	
	CL of Concrete Island Sta. 98+22.00 43.51' RT	367.14
PROJECT TOTAL		1,062