

IL. RTE. 127
F.A.P. 42
RURAL

IL. RTE. 16
F.A.P. 325
URBAN

SUMMARY OF QUANTITIES				07COL				
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	L25EC	L2SEC	TOTAL BREAKOUTS		L2SEL
				80% FEDERAL	80% FEDERAL	50% STATE	80% FEDERAL	80% FEDERAL
				20% STATE	20% STATE	50% LOCAL (PARKING LANE)	10% STATE	20% LOCAL
				CODE 0005	CODE 0021	CODE 0005	CODE 0021	CODE 0021
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	150	150				
35300720	PORTLAND CEMENT CONCRETE BASE COURSE 13"	SQ YD	1					1
35800100	PREPARATION OF BASE	SQ YD	25	25				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	44.1	44.0		0.1		
40600300	AGGREGATE (PRIME COAT)	TON	232	231		1		
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	3,871	3,871				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	5,320	5,320				
40600990	TEMPORARY RAMP	SQ YD	1,311	1,311				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	12,613	12,576		37		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	385	385				
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4"	SQ FT	23.5					23.5
42400800	DETECTABLE WARNINGS	SQ FT	81.4					81.4
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	19,926	19,599		327		
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	8,050	8,050				
44000300	CURB REMOVAL	FOOT	12.0					12
44000600	SIDEWALK REMOVAL	SQ FT	44.0					44.0
44200144	PAVEMENT PATCHING, TYPE II, 12 INCH	SQ YD	568	568				
44200148	PAVEMENT PATCHING, TYPE III, 12 INCH	SQ YD	231	231				
44200150	PAVEMENT PATCHING, TYPE IV, 12 INCH	SQ YD	591	591				

325, 42
15, 21RS-7, 22RS-4, 24RS-8

FILE NAME =	USER NAME = sparksgv	DESIGNED - RTS	REVISED -
at:\pwork\p\idat\sparksgv\d0222005\0672067-sht-S00.dgn		DRAWN - RTS	REVISED -
	PLOT SCALE = 36.0000 / 1"	CHECKED -	REVISED -
	PLOT DATE = Aug-25-2011 10:05:53AM	DATE - 06-16-11	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO. 1 OF 4 SHEETS	STA.	TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
.	..	MONTGOMERY	80	3
CONTRACT NO.				
ILLINOIS FED. AID PROJECT				