

HOT-MIX ASPHALT SHOULDER REMOVAL, LEFT SIDE								
LOCATION		SHOULDER WIDTH OF REMOVAL, LEFT	DISTANCE OF RUN	SHOULDER AREA	PAVED SHOULDER REMOVAL SPECIAL, 6"	PAVED SHOULDER REMOVAL SPECIAL, 8"	HMA SURFACE REMOVAL VARIABLE DEPTH	
		(FOOT)	(FOOT)	(SQ FT)	(SQ YD)	(SQ YD)	(SQ YD)	
IL RTE.16 MAINLINE								
STA 100+99.00	TO	STA 102+19.50	7.0	120.50	843.50		93.72	
STA 102+19.50	TO	STA 104+06.00	8.0 TO 7.0	186.50	1,398.75		155.42	
STA 104+50.00	TO	STA 110+50.00	4.0	600.00	2,400.00	266.67		
STA 110+50.00	TO	STA 116+25.00	4.0	575.00	2,300.00	255.56		
STA 116+25.00	TO	STA 121+75.00	4.0	550.00	2,200.00	244.44		
STA 121+75.00	TO	STA 127+25.00	4.0	550.00	2,200.00	244.44		
STA 127+25.00	TO	STA 131+27.83	4.0	402.83	1,611.32	179.04		
STA EQUATION: 131+27.83 (BK.) = 131+19.80 (AHD.)								
STA 131+19.80	TO	STA 132+75.00	4.0	155.20	620.80	68.98		
STA 132+75.00	TO	STA 138+25.00	4.0	550.00	2,200.00	244.44		
STA 138+25.00	TO	STA 143+75.00	4.0	550.00	2,200.00	244.44		
STA 143+75.00	TO	STA 149+25.00	4.0	550.00	2,200.00	244.44		
STA 149+25.00	TO	STA 154+75.00	4.0	550.00	2,200.00	244.44		
STA 154+75.00	TO	STA 156+47.26	4.0	172.26	689.04	76.56		
STA 156+47.26	TO	STA 158+40.49	7.7	193.23	1,487.87		165.32	
WEST FORK OF SHOAL CREEK								
STA 160+67.70	TO	STA 162+60.32	7.7	192.62	1,483.17		164.80	
STA 162+60.32	TO	STA 165+75.00	4.0	314.68	1,258.72	139.86		
STA 165+75.00	TO	STA 176+75.00	4.0	1,100.00	4,400.00	488.89		
STA 176+75.00	TO	STA 187+75.00	4.0	1,100.00	4,400.00	488.89		
STA 187+75.00	TO	STA 198+75.00	4.0	1,100.00	4,400.00	488.89		
STA 198+75.00	TO	STA 209+75.00	4.0	1,100.00	4,400.00	488.89		
STA 209+75.00	TO	STA 215+77.50	4.0	602.50	2,410.00	267.78		
STA 217+35.00	TO	STA 220+75.00	4.0	340.00	1,360.00	151.11		
STA 220+75.00	TO	STA 231+75.00	4.0	1,100.00	4,400.00	488.89		
STA 231+75.00	TO	STA 242+75.00	4.0	1,100.00	4,400.00	488.89		
STA 242+75.00	TO	STA 242+93.00	4.0	18.00	72.00	8.00		
STA 243+32.00	TO	STA 253+75.00	4.0	1,043.00	4,172.00	463.56		
STA 253+75.00	TO	STA 264+75.00	4.0	1,100.00	4,400.00	488.89		
STA 264+75.00	TO	STA 275+25.00	4.0	1,050.00	4,200.00	466.67		
STA 275+25.00	TO	STA 277+25.00	4.0	200.00	800.00	88.89		
BRUSH CREEK								
STA 280+06.00	TO	STA 282+20.00	4.0	214.00	856.00	95.11		
STA 282+20.00	TO	STA 295+41.50	4.0	1,321.50	5,286.00	587.33		
STA 296+07.50	TO	STA 297+75.00	4.0	167.50	670.00	74.44		
STA 297+75.00	TO	STA 308+75.00	4.0	1,100.00	4,400.00	488.89		
STA 308+75.00	TO	STA 319+75.00	4.0	1,100.00	4,400.00	488.89		
STA 319+75.00	TO	STA 330+75.00	4.0	1,100.00	4,400.00	488.89		
STA 330+75.00	TO	STA 336+00.00	4.0	525.00	2,100.00	233.33		
STA 336+00.00	TO	STA 338+00.08	4.0	200.08	800.32	88.92		
STA 338+00.08	TO	STA 347+06.35	4.0	906.27	3,625.08		402.79	
IL RTE.16 / IL RTE. 127 INTERSECTION								
STA 350+18.17	TO	STA 352+25.00	4.0	206.83	827.32		91.92	
STA 352+25.00	TO	STA 355+64.76	4.0	339.76	1,359.04		151.00	
STA 437+70.00	TO	STA 441+25.00	8.0	355.00	2,840.00		315.56	
TOTALS:				24,702.26	102,670.94	9,867.37	645.71	894.82

HOT-MIX ASPHALT SHOULDER REMOVAL, RIGHT SIDE								
LOCATION		SHOULDER WIDTH OF REMOVAL, RIGHT	DISTANCE OF RUN	SHOULDER AREA	PAVED SHOULDER REMOVAL SPECIAL, 6"	PAVED SHOULDER REMOVAL SPECIAL, 8"	HMA SURFACE REMOVAL VARIABLE DEPTH	
		(FOOT)	(FOOT)	(SQ FT)	(SQ YD)	(SQ YD)	(SQ YD)	
IL RTE.16 MAINLINE								
STA 100+99.00	TO	STA 102+19.50	11.3 TO 9.7	120.50	1,265.25		140.58	
STA 102+19.50	TO	STA 105+02.40	9.7 TO 4.0	282.90	2,210.00		245.56	
STA 105+02.40	TO	STA 110+50.00	4.0	547.60	2,190.40	243.38		
STA 110+50.00	TO	STA 116+25.00	4.0	575.00	2,300.00	255.56		
STA 116+25.00	TO	STA 121+75.00	4.0	550.00	2,200.00	244.44		
STA 121+75.00	TO	STA 122+10.00	4.0	35.00	140.00	15.56		
STA 122+50.00	TO	STA 127+25.00	4.0	475.00	1,900.00	211.11		
STA 127+25.00	TO	STA 131+27.83	4.0	402.83	1,611.32	179.04		
STA EQUATION: 131+27.83 (BK.) = 131+19.80 (AHD.)								
STA 131+19.80	TO	STA 132+75.00	4.0	155.20	620.80	68.98		
STA 132+75.00	TO	STA 143+75.00	4.0	1,100.00	4,400.00	488.89		
STA 143+75.00	TO	STA 154+75.00	4.0	1,100.00	4,400.00	488.89		
STA 154+75.00	TO	STA 156+47.26	4.0	172.26	689.04	76.56		
STA 156+47.26	TO	STA 158+40.49	7.7	193.23	1,487.87		165.32	
WEST FORK OF SHOAL CREEK								
STA 160+67.70	TO	STA 162+60.32	7.7	192.62	1,483.17		164.80	
STA 162+60.32	TO	STA 165+75.00	4.0	314.68	1,258.72	139.86		
STA 165+75.00	TO	STA 176+75.00	4.0	1,100.00	4,400.00	488.89		
STA 176+75.00	TO	STA 179+25.50	4.0	250.50	1,002.00	111.33		
STA 180+12.00	TO	STA 187+75.00	4.0	763.00	3,052.00	339.11		
STA 187+75.00	TO	STA 198+75.00	4.0	1,100.00	4,400.00	488.89		
STA 198+75.00	TO	STA 205+00.00	4.0	625.00	2,500.00	277.78		
STA 206+14.00	TO	STA 209+75.00	4.0	361.00	1,444.00	160.44		
STA 209+75.00	TO	STA 220+75.00	4.0	1,100.00	4,400.00	488.89		
STA 220+75.00	TO	STA 229+54.00	4.0	879.00	3,516.00	390.67		
STA 230+39.00	TO	STA 231+75.00	4.0	136.00	544.00	60.44		
STA 231+75.00	TO	STA 242+75.00	4.0	1,100.00	4,400.00	488.89		
STA 242+75.00	TO	STA 253+75.00	4.0	1,100.00	4,400.00	488.89		
STA 253+75.00	TO	STA 264+75.00	4.0	1,100.00	4,400.00	488.89		
STA 264+75.00	TO	STA 275+25.00	4.0	1,050.00	4,200.00	466.67		
STA 275+25.00	TO	STA 277+25.00	4.0	200.00	800.00	88.89		
BRUSH CREEK								
STA 280+06.00	TO	STA 282+20.00	4.0	214.00	856.00	95.11		
STA 282+20.00	TO	STA 297+75.00	4.0	1,555.00	6,220.00	691.11		
STA 297+75.00	TO	STA 308+75.00	4.0	1,100.00	4,400.00	488.89		
STA 308+75.00	TO	STA 310+55.00	4.0	180.00	720.00	80.00		
STA 311+49.50	TO	STA 319+75.00	4.0	825.50	3,302.00	366.89		
STA 319+75.00	TO	STA 330+75.00	4.0	1,100.00	4,400.00	488.89		
STA 330+75.00	TO	STA 336+00.00	4.0	525.00	2,100.00	233.33		
STA 336+00.00	TO	STA 338+00.08	4.0	200.08	800.32	88.92		
STA 338+00.08	TO	STA 346+75.00	4.0	874.92	3,499.68		388.85	
IL RTE.16 / IL RTE. 127 INTERSECTION								
STA 346+75.00	TO	STA 352+25.00	4.0	550.00	2,200.00		244.44	
STA 352+25.00	TO	STA 355+64.76	4.0	339.76	1,359.04		151.00	
STA 437+70.00	TO	STA 441+25.00	8.0	355.00	2,840.00		315.56	
TOTALS:				24,900.58	104,312.27	9,774.09	784.29	941.68

-- (15, 21)RS-7, 22RS-4, 24RS-8  
 -- 42, 325

FILE NAME =	USER NAME = sparksgw	DESIGNED - RTS	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULES OF QUANTITIES</b>			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\pwork\sparksgw\100222005\0672067-sht-schedule.dgn	DRAWN - RTS	REVISED -	..					.	MONTGOMERY	80	19	
PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -	SCALE: SHEET NO. 2 OF 18 SHEETS STA. TO STA.				CONTRACT NO. 72D67					
PLOT DATE = Aug-25-2011 10:41:28AM	DATE - 04-26-11	REVISED -	ILLINOIS FED. AID PROJECT									