

**HOT-MIX ASPHALT SURFACE COURSE, MAINLINE PAVEMENT**

LOCATION			PAVEMENT WIDTH	DISTANCE OF RUN	PAVEMENT AREA	PAVEMENT AREA	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	HMA LEVELING BINDER, (MM), N70, 3/4"	HMA SURFACE COURSE, MIX "D", N70, 1 1/2"	HMA SURFACE COURSE, MIX "D", N70, 2"
			(FOOT)	(FOOT)	(SQ FT)	(SQ YD)	(TON)	(TON)	(TON)	(TON)	(TON)
IL RTE. 16 IN LITCHFIELD											
STA 923+67.05	TO	STA 928+00.00	VARIABLE	432.95	44,235.00	4,915.00	1.87	9.83			550.48
STA 928+00.00	TO	STA 933+75.00	VARIABLE	575.00	29,421.00	3,269.00	1.24	6.54			366.13
STA 933+75.00	TO	STA 938+00.00	VARIABLE	425.00	15,206.52	1,689.62	0.64	3.38			189.24
STA 938+00.00	TO	STA 942+12.70 BK	VARIABLE	412.70	14,770.07	1,641.12	0.62	3.28			183.81
STA. EQUATION: 942+12.70 (BK.) = 0+00.00 (AHD.)											
STA 0+00.00 AH	TO	STA 0+13.85	VARIABLE	13.85	502.00	55.78	0.02	0.11			6.25
STA 0+22.42	TO	STA 1+50.00	VARIABLE	127.58	4,740.06	526.67	0.20	1.05			58.99
STA 1+50.00	TO	STA 2+85.00	VARIABLE	135.53	4,964.98	551.67	0.21	1.10			61.79
STA 3+16.12	TO	STA 7+15.00	VARIABLE	398.88	14,960.12	1,662.23	0.63	3.32			186.17
STA 7+15.00	TO	STA 12+40.00	VARIABLE	525.00	19,124.04	2,124.89	0.81	4.25			237.99
STA 12+40.00	TO	STA 18+00.00	VARIABLE	560.00	23,255.50	2,583.95	0.98	5.17			289.40
STA 18+00.00	TO	STA 19+97.28	VARIABLE	197.28	9,930.22	1,103.36	0.42	2.21			123.58
IL RTE. 16 MAINLINE											
STA 100+64.00	TO	STA 102+19.50	29 TO 30.5	155.50	4,626.13	514.01	0.20	1.03	21.59	43.18	
STA 102+19.50	TO	STA 104+50.00	30	230.50	6,915.00	768.33	0.29	1.54	32.27	64.54	
STA 104+50.00	TO	STA 110+50.00	30	600.00	18,000.00	2,000.00	0.76	4.00	84.00	168.00	
STA 110+50.00	TO	STA 116+25.00	24	575.00	13,800.00	1,533.33	0.58	3.07	64.40	128.80	
STA 116+25.00	TO	STA 121+75.00	24	550.00	13,200.00	1,466.67	0.56	2.93	61.60	123.20	
STA 121+75.00	TO	STA 127+50.00	24	575.00	13,800.00	1,533.33	0.58	3.07	64.40	128.80	
STA 127+50.00	TO	STA 131+27.83	24	377.83	9,067.92	1,007.55	0.38	2.02	42.32	84.63	
STA. EQUATION: 131+27.83 (BK.) = 131+19.80 (AHD.)											
STA 131+19.80	TO	STA 132+75.00	24	155.20	3,724.80	413.87	0.16	0.83	17.38	34.76	
STA 132+75.00	TO	STA 138+25.00	24	550.00	13,200.00	1,466.67	0.56	2.93	61.60	123.20	
STA 138+25.00	TO	STA 143+75.00	24	550.00	13,200.00	1,466.67	0.56	2.93	61.60	123.20	
STA 143+75.00	TO	STA 149+25.00	24	550.00	13,200.00	1,466.67	0.56	2.93	61.60	123.20	
STA 149+25.00	TO	STA 154+75.00	24	550.00	13,200.00	1,466.67	0.56	2.93	61.60	123.20	
STA 154+75.00	TO	STA 155+12.71	24	37.71	905.04	100.56	0.04	0.20	4.22	8.45	
STA 155+12.71	TO	STA 156+47.26	24	134.55	3,229.20	358.80	0.14	0.72	15.07	30.14	
STA 156+47.26	TO	STA 158+40.49	24	193.23	4,637.52	515.28	0.20	1.03	21.64	43.28	
WEST FORK OF SHOAL CREEK											
STA 160+67.70	TO	STA 165+75.00	24	507.30	12,175.20	1,352.77	0.51	2.71	56.82	113.63	
STA 165+75.00	TO	STA 176+75.00	24	1,100.00	26,400.00	2,933.33	1.11	5.87	123.20	246.40	
STA 176+75.00	TO	STA 187+75.00	24	1,100.00	26,400.00	2,933.33	1.11	5.87	123.20	246.40	
STA 187+75.00	TO	STA 198+75.00	24	1,100.00	26,400.00	2,933.33	1.11	5.87	123.20	246.40	
STA 198+75.00	TO	STA 209+75.00	24	1,100.00	26,400.00	2,933.33	1.11	5.87	123.20	246.40	
STA 209+75.00	TO	STA 220+75.00	24	1,100.00	26,400.00	2,933.33	1.11	5.87	123.20	246.40	
STA 220+75.00	TO	STA 231+75.00	24	1,100.00	26,400.00	2,933.33	1.11	5.87	123.20	246.40	
STA 231+75.00	TO	STA 242+75.00	24	1,100.00	26,400.00	2,933.33	1.11	5.87	123.20	246.40	
STA 242+75.00	TO	STA 253+75.00	24	1,100.00	26,400.00	2,933.33	1.11	5.87	123.20	246.40	
STA 253+75.00	TO	STA 264+75.00	24	1,100.00	26,400.00	2,933.33	1.11	5.87	123.20	246.40	
STA 264+75.00	TO	STA 275+75.00	24	1,100.00	26,400.00	2,933.33	1.11	5.87	123.20	246.40	
STA 275+75.00	TO	STA 277+25.00	24	150.00	3,600.00	400.00	0.15	0.80	16.80	33.60	

SCHEDULE CONTINUED, NEXT SHEET →

-- (15, 21)RS-7, 22RS-4, 24RS-8  
 -- 42, 325

FILE NAME =	USER NAME = sparksgw	DESIGNED - RTS	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULES OF QUANTITIES</b>			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ci:\pw\work\p\idot\sparksgw\10222005\0672067-sht-schedule.dgn	DRAWN - RTS	REVISED -	..					.	MONTGOMERY	80	20	
PLOT SCALE = 100.0000' / 1in.	CHECKED -	REVISED -	CONTRACT NO. 72D67									
PLOT DATE = Aug-25-2011 10:14:29AM	DATE - 04-26-11	REVISED -	SCALE:		SHEET NO. 3 OF 18 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT				