

HOT-MIX ASPHALT SHOULDER TREATMENT, LEFT SIDE (CONTINUED)

LOCATION	DISTANCE OF RUN	SHOULDER WIDTH	HMA SHOULDERS, 6 1/4" DEPTH	HMA SHOULDERS, 6 1/2" DEPTH	HMA SURFACE COURSE, 2 1/4" AVG. DEPTH	HMA SURFACE COURSE, 1 1/2" DEPTH
	(FOOT)	(FOOT)	(SQ YD)	(SQ YD)	(TON)	(TON)
IL RTE. 16 / IL RTE. 127 INTERSECTION						
STA 350+18.17 TO STA 356+14.76	596.59	4.00		265.15		22.27
STA 356+14.76 TO STA 358+15.00	200.24	4.00		89.00		7.48
STA 358+15.00 TO STA 365+00.00	685.00	4.00		304.44		25.57
STA 365+00.00 TO STA 376+00.00	1,100.00	4.00		488.89		41.07
STA 376+00.00 TO STA 377+81.00	181.00	4.00		80.44		6.76
STA 378+53.00 TO STA 398+00.00	1,947.00	4.00		865.33		72.69
STA 398+00.00 TO STA 409+00.00	1,100.00	4.00		488.89		41.07
STA 409+00.00 TO STA 420+00.00	1,100.00	4.00		488.89		41.07
STA 420+00.00 TO STA 422+12.00	212.00	4.00		94.22		7.91
STA 422+97.00 TO STA 428+69.55	572.55	4.00		254.47		21.38
STATION EQUATION: 428+69.55 (BK.) = 433+70.11 (AHD.)						
STA 433+70.11 TO STA 437+70.00	399.89	4.00		177.73		14.93
STA 437+70.00 TO STA 440+75.00	305.00	8.00			34.16	
TOTALS:	32,334.94		10,091.48	3,978.02	110.57	1,181.85

•- (15, 21)RS-7, 22RS-4, 24RS-8
••- 42, 325

FILE NAME =	USER NAME = sparksgw	DESIGNED - RTS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\pwork\sparksgw\10222005\0672067-sht-schedule.dgn	DRAWN - RTS	REVISED -	••					•	MONTGOMERY	80	24	
PLOT SCALE = 100.0000' / 1in.	CHECKED -	REVISED -	CONTRACT NO. 72D67									
PLOT DATE = Aug-25-2011 10:14:31AM	DATE - 04-26-11	REVISED -	SCALE:		SHEET NO. 7 OF 18 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT				