

HOT-MIX ASPHALT SHOULDER TREATMENT, RIGHT SIDE						
LOCATION	DISTANCE	SHOULDER	HMA	HMA	HMA SURFACE	HMA SURFACE
	OF RUN	WIDTH	SHOULDERS, 6 1/4" DEPTH	SHOULDERS, 6 1/2" DEPTH	COURSE, 2 1/4" AVG. DEPTH	COURSE, 1 1/2" DEPTH
	(FOOT)	(FOOT)	(SQ YD)	(SQ YD)	(TON)	(TON)
IL RTE.16 MAINLINE						
STA 100+64.00	TO	STA 104+64.16	400.16	11.3 TO 9.7		58.82
STA 104+64.16	TO	STA 105+36.70	72.54	9.7 TO 4		6.96
STA 105+36.70	TO	STA 110+50.00	513.30	4.00	228.13	19.16
STA 110+50.00	TO	STA 121+75.00	1,125.00	4.00	500.00	42.00
STA 121+75.00	TO	STA 122+10.00	35.00	4.00	15.56	1.31
STA 122+50.00	TO	STA 127+25.00	475.00	4.00	211.11	17.73
STA 127+25.00	TO	STA 131+27.83	402.83	4.00	179.04	15.04
STA. EQUATION: 131+27.83 (BK.) = 131+19.80 (AHD.)						
STA 131+19.80	TO	STA 132+75.00	155.20	4.00	68.98	5.79
STA 132+75.00	TO	STA 143+75.00	1,100.00	4.00	488.89	41.07
STA 143+75.00	TO	STA 154+75.00	1,100.00	4.00	488.89	41.07
STA 154+75.00	TO	STA 156+47.26	172.26	4.00	76.56	6.43
STA 156+47.26	TO	STA 158+40.49	193.23	7.70		20.83
WEST FORK SHOAL CREEK						
STA 160+67.70	TO	STA 162+60.32	192.62	7.70		20.76
STA 162+60.32	TO	STA 165+75.00	314.68	4.00	139.86	11.75
STA 165+75.00	TO	STA 176+75.00	1,100.00	4.00	488.89	41.07
STA 176+75.00	TO	STA 179+25.50	250.50	4.00	111.33	9.35
STA 180+12.00	TO	STA 187+75.00	763.00	4.00	339.11	28.49
STA 187+75.00	TO	STA 198+75.00	1,100.00	4.00	488.89	41.07
STA 198+75.00	TO	STA 205+00.00	625.00	4.00	277.78	23.33
STA 206+14.00	TO	STA 209+75.00	361.00	4.00	160.44	13.48
STA 209+75.00	TO	STA 220+75.00	1,100.00	4.00	488.89	41.07
STA 220+75.00	TO	STA 229+54.00	879.00	4.00	390.67	32.82
STA 230+39.00	TO	STA 231+75.00	136.00	4.00	60.44	5.08
STA 231+75.00	TO	STA 242+75.00	1,100.00	4.00	488.89	41.07
STA 242+75.00	TO	STA 253+75.00	1,100.00	4.00	488.89	41.07
STA 253+75.00	TO	STA 264+75.00	1,100.00	4.00	488.89	41.07
STA 264+75.00	TO	STA 275+25.00	1,050.00	4.00	466.67	39.20
STA 275+25.00	TO	STA 277+75.00	250.00	VARIABLE	175.22	14.72
BRUSH CREEK						
STA 279+56.00	TO	STA 282+20.00	264.00	VARIABLE	187.83	15.78
STA 282+20.00	TO	STA 297+75.00	1,555.00	4.00	691.11	58.05
STA 297+75.00	TO	STA 308+75.00	1,100.00	4.00	488.89	41.07
STA 308+75.00	TO	STA 310+55.00	180.00	4.00	80.00	6.72
STA 311+49.50	TO	STA 319+75.00	825.50	4.00	366.89	30.82
STA 319+75.00	TO	STA 330+75.00	1,100.00	4.00	488.89	41.07
STA 330+75.00	TO	STA 336+00.00	525.00	4.00	233.33	19.60
STA 336+00.00	TO	STA 338+50.08	250.08	4.00	111.15	9.34
STA 338+50.08	TO	STA 341+25.00	274.92	4.00		10.26
STA 341+25.00	TO	STA 346+75.00	550.00	4.00		20.53

SCHEDULE CONTINUED, NEXT SHEET →

-- (15, 21)RS-7, 22RS-4, 24RS-8
 -- 42, 325

FILE NAME =	USER NAME = sparksgw	DESIGNED - RTS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ci:\pw\work\p\dot\sparksgw\10222005\0672067-sht-schedule.dgn		DRAWN - RTS	REVISED -		SCALE:	SHEET NO. 8	OF 18 SHEETS	STA.	TO STA.	MONTGOMERY	80	25
	PLOT SCALE = 100.0000' / 1in.	CHECKED -	REVISED -		CONTRACT NO. 72D67							
	PLOT DATE = Aug-25-2011 10:14:32AM	DATE - 04-26-11	REVISED -		ILLINOIS FED. AID PROJECT							