

PREFORMED PLASTIC PAVEMENT, TYPE B - INLAID- LETTERS & SYMBOLS

LOCATION	MARKING TYPE	QUANTITY
		(SURFACE AREA) SQ FT
IL RTE. 16 (LITCHFIELD)		
STA 924+11.60	LEFT LANE TURN ARROW	15.60
STA 924+74.00	LEFT LANE TURN ARROW	15.60
STA 925+55.00	LEFT LANE TURN ARROW	15.60
STA 926+00.00	LEFT LANE TURN ARROW	15.60
STA 927+50.00	LEFT LANE TURN ARROW	15.60
STA 928+43.00	LEFT LANE TURN ARROW	15.60
STA 929+83.00	MEDIAN LEFT TURN ARROW	15.60
STA 930+15.00	MEDIAN LEFT TURN ARROW	15.60
STA 931+16.00	MEDIAN LEFT TURN ARROW	15.60
STA 931+48.00	MEDIAN LEFT TURN ARROW	15.60
STA 932+49.00	MEDIAN LEFT TURN ARROW	15.60
STA 932+81.00	MEDIAN LEFT TURN ARROW	15.60
STA 933+81.00	MEDIAN LEFT TURN ARROW	15.60
STA 934+13.00	MEDIAN LEFT TURN ARROW	15.60
STA 935+13.00	MEDIAN LEFT TURN ARROW	15.60
STA 935+45.00	MEDIAN LEFT TURN ARROW	15.60
STA 936+81.00	MEDIAN LEFT TURN ARROW	15.60
STA 937+13.00	MEDIAN LEFT TURN ARROW	15.60
STA 938+13.00	MEDIAN LEFT TURN ARROW	15.60
STA 938+45.00	MEDIAN LEFT TURN ARROW	15.60
STA 939+79.00	MEDIAN LEFT TURN ARROW	15.60
STA 940+11.00	MEDIAN LEFT TURN ARROW	15.60
STA 941+11.00	MEDIAN LEFT TURN ARROW	15.60
STA 941+43.00	MEDIAN LEFT TURN ARROW	15.60
STA 0+70.00	MEDIAN LEFT TURN ARROW	15.60
STA 1+02.00	MEDIAN LEFT TURN ARROW	15.60
STA 2+23.00	MEDIAN LEFT TURN ARROW	15.60
STA 2+55.00	MEDIAN LEFT TURN ARROW	15.60
STA 3+46.00	MEDIAN LEFT TURN ARROW	15.60
STA 3+78.00	MEDIAN LEFT TURN ARROW	15.60
STA 5+34.00	MEDIAN LEFT TURN ARROW	15.60
STA 5+66.00	MEDIAN LEFT TURN ARROW	15.60
STA 6+71.00	MEDIAN LEFT TURN ARROW	15.60
STA 7+03.00	MEDIAN LEFT TURN ARROW	15.60
STA 8+04.00	LEFT LANE TURN ARROW	15.60
STA 8+60.00	LEFT LANE TURN ARROW	15.60
STA 10+43.00	LEFT LANE TURN ARROW	15.60
STA 10+93.00	LEFT LANE TURN ARROW	15.60
STA 11+93.00	MEDIAN LEFT TURN ARROW	15.60
STA 12+25.00	MEDIAN LEFT TURN ARROW	15.60
STA 13+29.00	MEDIAN LEFT TURN ARROW	15.60
STA 13+61.00	MEDIAN LEFT TURN ARROW	15.60
STA 14+97.00	LEFT LANE TURN ARROW	15.60
STA 15+45.00	LEFT LANE TURN ARROW	15.60
STA 16+91.00	LEFT LANE TURN ARROW	15.60
STA 17+51.00	LEFT LANE TURN ARROW	15.60
IL RTE. 16 RAILROAD CROSSINGS (LITCHFIELD)		
STA 940+92.00	2 x R.R. CROSS-BUCK ("X" & "R")	122.40
STA 1+16.00	2 x R.R. CROSS-BUCK ("X" & "R")	122.40
STA 2+04.00	2 x R.R. CROSS-BUCK ("X" & "R")	122.40
STA 3+98.00	2 x R.R. CROSS-BUCK ("X" & "R")	122.40
IL RTE. 16/127 INTERSECTION		
STA 345+73.00	LEFT LANE TURN ARROW	15.60
STA 346+81.00	LEFT LANE TURN ARROW	15.60
STA 347+89.00	LEFT LANE TURN ARROW	15.60
STA 350+12.00	RIGHT LAND TURN ARROW	15.60
STA 351+08.00	RIGHT LAND TURN ARROW	15.60
STA 352+04.00	RIGHT LAND TURN ARROW	15.60
STA 353+00.00	RIGHT LAND TURN ARROW	15.60
TOTALS:		1332.00

RAISED REFLECTIVE PAVEMENT MARKERS

LOCATION			ONE-WAY CRYSTAL	ONE-WAY AMBER	TWO-WAY AMBER	MARKER SPACING
			(EACH)	(EACH)	(EACH)	(FOOT)
IL RTE. 16 IN LITCHFIELD						
STA 923+86.60	TO	STA 927+00.00	18		17	40
STA 927+00.00	TO	STA 930+00.00	16		14	40
STA 930+00.00	TO	STA 933+75.00			18	40
STA 933+75.00	TO	STA 938+00.00			16	40
STA 938+00.00	TO	STA 942+12.70			14	40
STATION EQUATION: 942+12.70 BK = 0+00.00 AH						
STA 0+00.00	TO	STA 1+50.00			4	40
STA 1+50.00	TO	STA 7+15.00			22	40
STA 7+15.00	TO	STA 9+00.00	3		10	40
STA 9+00.00	TO	STA 12+40.00	3		10	40
STA 12+40.00	TO	STA 18+00.00	6		24	40
STA 18+00.00	TO	STA 20+00.00			6	40
IL RTE. 16 MAINLINE						
STA 100+64.00	TO	STA 104+50.00			5	80
STA 104+50.00	TO	STA 110+50.00			7	80
STA 110+50.00	TO	STA 116+25.00			7	80
STA 116+25.00	TO	STA 121+75.00			7	80
STA 121+75.00	TO	STA 127+25.00			7	80
STA 127+25.00	TO	STA 132+75.00			7	80
STA 132+75.00	TO	STA 138+25.00			7	80
STA 138+25.00	TO	STA 143+75.00			7	80
STA 143+75.00	TO	STA 149+25.00			7	80
STA 149+25.00	TO	STA 154+75.00			7	80
STA 154+75.00	TO	STA 158+40.49			4	80
WEST FORK SHOAL CREEK						
STA 160+67.70	TO	STA 165+75.00			7	80
STA 165+75.00	TO	STA 176+75.00			14	80
STA 176+75.00	TO	STA 187+75.00			14	80
STA 187+75.00	TO	STA 198+75.00			14	80
STA 198+75.00	TO	STA 209+75.00			14	80
STA 209+75.00	TO	STA 220+75.00			14	80
STA 220+75.00	TO	STA 231+75.00			14	80
STA 231+75.00	TO	STA 242+75.00			14	80
STA 242+75.00	TO	STA 253+75.00			14	80
STA 253+75.00	TO	STA 264+75.00			14	80
STA 264+75.00	TO	STA 275+75.00			14	80
STA 275+75.00	TO	STA 278+00.00			3	80
BRUSH CREEK						
STA 279+00.00	TO	STA 286+75.00			9	80
STA 286+75.00	TO	STA 297+75.00			14	80
STA 297+75.00	TO	STA 308+75.00			14	80
STA 308+75.00	TO	STA 319+75.00			14	80
STA 319+75.00	TO	STA 330+75.00			14	80
STA 330+75.00	TO	STA 335+75.00			6	80
STA 335+75.00	TO	STA 336+50.00			1	80
STA 336+50.00	TO	STA 341+25.00			12	80
STA 341+25.00	TO	STA 345+68.60			16	40 / 80
STA 345+68.60	TO	STA 348+70.71	7		12	40
IL RTE. 16/IL RTE. 127						
RAISED CONCRETE ISLANDS @ INTERSECTION			12			
RAISED CONCRETE IMEDIAN ON IL 127				4		
STA 348+70.71	TO	STA 352+25.00	6		12	40 / 80
STA 352+25.00	TO	STA 353+05.00	3		2	40 / 80
STA 353+05.00	TO	STA 357+75.00			11	80
STA 357+75.00	TO	STA 365+00.00			8	80
STA 365+00.00	TO	STA 376+00.00			14	80
STA 376+00.00	TO	STA 387+00.00			14	80
STA 387+00.00	TO	STA 398+00.00			14	80
STA 398+00.00	TO	STA 409+00.00			14	80
STA 409+00.00	TO	STA 420+00.00			14	80
STA 420+00.00	TO	STA 428+69.55			11	80
STATION EQUATION: 428+69.55 BH=433+70.11 AH						
STA 433+70.11	TO	STA 436+50.00			4	80
STA 436+50.00	TO	STA 441+25.00			6	80
TOTALS =			74	4	613	

-- (15, 21)RS-7, 22RS-4, 24RS-8
 -- 42, 325

FILE NAME =	USER NAME = sparksgw	DESIGNED - TJA	REVISED -
et:\pw\work\p\idot\sparksgw\10222005\0672067-sht-schedule.dgn		DRAWN - TJA	REVISED -
	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -
	PLOT DATE = Aug-25-2011 10:15:48AM	DATE - 06-29-11	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULES OF QUANTITIES

SCALE: SHEET NO. 18 OF 18 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		MONTGOMERY	80	35
			CONTRACT NO. 72D67	
ILLINOIS FED. AID PROJECT				