



**NOTES:**  
 THE PROPOSED EDGE OF PAVEMENT STRIPES ARE NOT SHOWN ON THIS PLAN SHEET. SEE SCHEDULES FOR E.O.P. STRIPING AND OTHER PAVEMENT MARKING LOCATIONS.  
 WIDTH OF PROPOSED SHOULDER REMOVAL AND HMA SHOULDERS IS 4' UNLESS OTHERWISE STATED WITHIN THESE PLANS.  
 WIDTH OF PROPOSED AGGREGATE SHOULDER WEDGE, TYPE B IS 3'-0".  
 SEE SIDEROAD AND ENTRANCE SCHEDULES FOR THEIR PROPOSED IMPROVEMENT DETAILS.

EXIST. CURVE 232  
 PI STA. = 232+64.67  
 $\Delta = 1^\circ 49' 00''$  (RT)  
 D = 0° 15' 44"  
 R = 21,851.52'  
 T = 346.45'  
 L = 692.84'  
 E = 2.75'  
 e = ----  
 T.R. = ----  
 S.E. RUN = ----  
 P.C. STA. = 229+18.22  
 P.T. STA. = 236+11.06

EXIST. CURVE 242  
 PI STA. = 242+42.06  
 $\Delta = 2^\circ 12' 39''$  (LT)  
 D = 0° 14' 59"  
 R = 22,953.63'  
 T = 442.90'  
 L = 885.69'  
 E = 4.27'  
 e = ----  
 T.R. = ----  
 S.E. RUN = ----  
 P.C. STA. = 237+99.16  
 P.T. STA. = 246+84.85

-- 325, 42  
 -- (15, 21)RS-7, 22RS-4, 24RS-8

FILE NAME = c:\pwork\pwork\dot\sparksgw\10222005\0672067-sht-plan.dgn	USER NAME = sparksgw	DESIGNED - RTS	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>PLAN SHEET (RURAL)</b>		F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 40.0000' / in.	CHECKED -	REVISED -		SCALE:	SHEET NO. 7 OF 15 SHEETS	STA. TO STA.	•	•	MONTGOMERY	80
PLOT DATE = Aug-25-2011 10:16:05AM	DATE - 06-15-11	REVISED -	REVISED -				FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT	CONTRACT NO. 72D67	