

L25E
80% FED
20% STATE

L53E
90% FED
10% STATE

CODE NO.	ITEM	UNIT	TOTAL	CONST CODE 0005 OLD US 36	
				STP STATE	HSIP SAFETY
20200100	EARTH EXCAVATION	CU YD	437	437	
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	87		87
* 25000210	SEEDING, CLASS 2A	ACRE	0.50	0.50	
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	45.0	45.0	
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	45.0	45.0	
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	45.0	45.0	
* 25000700	AGRICULTURAL GROUND LIMESTONE	TON	1.0	1.0	
* 25100115	MULCH, METHOD 2	ACRE	1.0	1.0	
28100107	STONE RIPRAP, CLASS A4	SQ YD	222	222	
28200200	FILTER FABRIC	SQ YD	222	222	
35800100	PREPARATION OF BASE	SQ YD	278	278	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	4.38	4.38	
40600300	AGGREGATE (PRIME COAT)	TON	1.48	1.48	
40600895	CONSTRUCTING TEST STRIP	EACH	1	1	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	813	813	
40600990	TEMPORARY RAMP	SQ YD	25	25	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	93	93	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	1,232	907	325
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	10,800	10,800	
44000400	GUTTER REMOVAL	FOOT	3,473		3,473
44200140	PAVEMENT PATCHING, TYPE I, 12 INCH	SQ YD	10	10	
44200144	PAVEMENT PATCHING, TYPE II, 12 INCH	SQ YD	170	170	
44200148	PAVEMENT PATCHING, TYPE III, 12 INCH	SQ YD	145	145	
44200150	PAVEMENT PATCHING, TYPE IV, 12 INCH	SQ YD	120	120	
48203023	HOT-MIX ASPHALT SHOULDERS, 6 1/2"	SQ YD	3,868		3,868
64200105	SHOULDER RUMBLE STRIPS	FOOT	8,702		8,702
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6	
67100100	MOBILIZATION	L SUM	1	1	

*SPECIALTY ITEM

FILE NAME =	USER NAME = sparksgv	DESIGNED -	REVISED -
et\pwwork\pwwork\sparksgv\0222050\0672084.sht-S00.dgn		DRAWN -	REVISED -
	PLOT SCALE = 40.0000' / 1"	CHECKED -	REVISED -
	PLOT DATE = Aug-26-2011 02:43:59PM	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1610	22RS-10	SCOTT	42	3
CONTRACT NO. 72084				
ILLINOIS FED. AID PROJECT				