

LOCATION OF WORK				RURAL 90% FEDERAL 10% STATE	RURAL 90% FEDERAL 10% STATE	RURAL 90% FEDERAL 10% STATE	RURAL 90% FEDERAL 10% STATE	RURAL 90% FEDERAL 10% STATE	RURAL 90% FEDERAL 10% STATE
				CROSSOVERS	SN 054-0048 SN 048-0049	SN 054-0050	SN 054-0053 SN 054-0054	SN 054-0055 SN 054-0056	SN 054-0059
SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					
CODE NO.	ITEM	UNIT	TOTAL	0014	0014	0014	0014	0014	0014
50500505	STUD SHEAR CONNECTORS	EACH	58,068				18,612		39,456
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	<b>1,130,350</b>			<b>3,510</b>	573,690		553,150
50800515	BAR SPLICERS	EACH	488			36	280		172
51500100	NAME PLATES	EACH	4				2		2
52000110	PREFORMED JOINT STRIP SEAL	FOOT	794.5			106.0	432.0		256.5
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	36				36		
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	132				12		120
52100505	ANCHOR BOLTS, 5/8"	EACH	120				24		96
52100510	ANCHOR BOLTS, 3/4"	EACH	48						48
52100520	ANCHOR BOLTS, 1"	EACH	216				72		144
54213459	END SECTIONS 24"	EACH	2	2					
54244405	FLUSH INLET BOX FOR MEDIAN, STANDARD 542546	EACH	4	4					
58700300	CONCRETE SEALER	SQ FT	8,372				5,965		2,407
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	553				338		215
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2					
60240366	INLETS, TYPE B, WITH MEDIAN INLET (604106)	EACH	8	8					
60500040	REMOVING MANHOLES	EACH	1	1					
60500060	REMOVING INLETS	EACH	4	4					
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	654				654		
63301210	REMOVE AND REERECT STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	1,587.5	350.0			750.0		487.5
63302400	REMOVE AND REERECT TRAFFIC BARRIER TERMINALS, TYPE 5	EACH	2				2		
63302700	REMOVE AND REERECT TRAFFIC BARRIER TERMINALS, TYPE 6	EACH	8				4		4
64200105	SHOULDER RUMBLE STRIPS	FOOT	9,027	7,414		43	760		810
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	24				12		12
67100100	MOBILIZATION	L SUM	1				0.5		0.5
70100205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	EACH	4		2	1			
70100207	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	EACH	1			1			
70100410	TRAFFIC CONTROL AND PROTECTION, STANDARD 701416	EACH	2				1		1
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	3			3			
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1						1
70100815	TRAFFIC CONTROL AND PROTECTION, STANDARD 701446	L SUM	1			1			
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	9	8		1			
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	57	57					
70300100	SHORT TERM PAVEMENT MARKING	FOOT	4,857	4,422		435			
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	84,906	79,747		5,159			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	24,990	22,659		2,331			
70400100	TEMPORARY CONCRETE BARRIER	FOOT	4,650	4,225		425			
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	4,650	4,225		425			
70500100	TEMPORARY STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	600	600					
70500665	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	48				24		24
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	27				16		11
* 78200520	BARRIER WALL MARKERS, TYPE B	EACH	64				32		32
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	64				32		32

\*SPECIALTY  
ITEM



JOB : 2265.4  
FILE NAME : 0672E10-sh1-soq.dgn  
PLOT SCALE : 2.0000 / IN.  
PLOT DATE : 9/9/2011

DESIGNED - NAK  
DRAWN - TJD  
CHECKED - NAK  
DATE - 8/12/2011

REVISED -  
REVISED -  
REVISED -  
REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

FAI ROUTE 55  
SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	D6 LOGAN CO BR 2011	LOGAN	224	4
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
			CONTRACT NO. 72E10	