

LOCATION OF WORK				RURAL 90% FEDERAL 10% STATE	RURAL 90% FEDERAL 10% STATE	RURAL 90% FEDERAL 10% STATE	RURAL 90% FEDERAL 10% STATE	RURAL 90% FEDERAL 10% STATE	RURAL 90% FEDERAL 10% STATE
				CROSSOVERS	SN 054-0048 SN 048-0049	SN 054-0050	SN 054-0053 SN 054-0054	SN 054-0055 SN 054-0056	SN 054-0059
SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					
CODE NO.	ITEM	UNIT	TOTAL	0014	0014	0014	0014	0014	0014
78300100	PAVEMENT MARKING REMOVAL	SQ FT	23,593	22,892		701			
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	16				8	8	
5421D018	PIPE CULVERTS, CLASS D, TYPE 1 18" (TEMPORARY)	FOOT	164	164					
5421D024	PIPE CULVERTS, CLASS D, TYPE 1 24" (TEMPORARY)	FOOT	338	338					
542D0223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	165	165					
542D0229	PIPE CULVERTS, CLASS D, TYPE 1 24"	FOOT	397	397					
X0322288	MEDIAN CLOSURE	EACH	4	4					
X0323583	SPEED INDICATOR SIGN	CAL DA	862	862					
X0484300	MEDIAN INLET BOX REMOVAL	EACH	2	2					
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	1,364				1,063	301	
+ X2503000	MAINTENANCE MOWING	ACRE	34.9	34.9					
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	100	100					
X6330103	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL, TANGENT	EACH	2	2					
X6380205	TEMPORARY MODULAR GLARE SCREEN	FOOT	600	600					
X6380200	RELOCATE MODULAR GLARE SCREEN SYSTEM	FOOT	600	600					
X7050167	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)	EACH	4	4					
* X7200201	WIDTH RESTRICTION SIGNING	L SUM	1			1			
* X7800620	URETHANE PAVEMENT MARKING - LINE 5"	FOOT	35,037	33,366		1,671			
X8410102	TEMPORARY LIGHTING SYSTEM	L SUM	1	1					
Z0001899	JACK AND REMOVE EXISTING BEARINGS	EACH	24				24		
Z0004552	APPROACH SLAB REMOVAL	SQ YD	1,059				607	452	
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	88				88		
Z0003802	REMOVAL OF EXISTING BEARINGS	EACH	24				24		
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.4			0.3	0.3	
Z0021903	SILICONE JOINT SEALER, 3/4"	FOOT	73						73
Z0018002	DRAINAGE SCUPPERS, DS-11	EACH	6				6		
Z0021916	SILICONE JOINT SEALER, 3"	FOOT	133		133				
Z0029090	DIAMOND GRINDING (BRIDGE SECTION)	SQ YD	11,533				5,451	6,082	
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	2	1		1			
Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	2	1		1			
Z0041895	POLYMER CONCRETE	CU FT	17.1		9.4	7.7			
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	736				410	326	
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1				1		
Z0073500	TEMPORARY SUPPORT SYSTEM	L SUM	1				1		
X6100510	REMOVE AND REPLACE INLET BOX GRATES L 610001	EACH	20	18		2			
Z0010501	CLEANING AND PAINTING STEEL BRIDGE, NO.1	L SUM	1		1				
Z0010502	CLEANING AND PAINTING STEEL BRIDGE, NO.2	L SUM	1			1			
X5060601	CONTAINMENT AND DISPOSAL OF NON-LEAD PAINT CLEANING RESIDUES NO.1	L SUM	1		1				
X5060602	CONTAINMENT AND DISPOSAL OF NON-LEAD PAINT CLEANING RESIDUES NO.2	L SUM	1			1			
X5030530	FLOOR DRAIN EXTENSIONS	EACH	3			3			

+ NON-PARTICIPATING
100% STATE
* SPECIALTY
ITEM

CEC Cummins
Engineering
Corporation
Civil and Structural Engineering

JOB : 2265.4
FILE NAME : D672E10-ght-90q.dgn
PLOT SCALE : 2.0000 "/ IN.
PLOT DATE : 9/9/2011

DESIGNED - NAK
DRAWN - TJD
CHECKED - NAK
DATE - 8/12/2011

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

FAI ROUTE 55
SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	D6 LOGAN CO BR 2011	LOGAN	224	5
CONTRACT NO. 72E10			ILLINOIS FED. AID PROJECT	