

HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH		
LOCATION	WIDTH	SQ YD
PRE-STAGE 1		
NB I-55		
STA 525+78.00 TO STA 526+03.00	6.00'	16.67
STA 527+92.00 TO STA 528+17.00	6.00'	16.67
STA 568+75.45 TO STA 569+00.45	6.00'	16.67
STA 571+42.90 TO STA 571+67.90	6.00'	16.67
SB I-55		
STA 525+55.00 TO STA 525+80.00	6.00'	16.67
STA 528+17.50 TO STA 528+42.50	6.00'	16.67
STA 569+03.45 TO STA 569+28.45	6.00'	16.67
STA 571+14.60 TO STA 571+39.60	6.00'	16.67
TOTAL		100.02

TEMPORARY STEEL PLATE BEAM GUARDRAIL, TYPE A		FOOT
CROSSOVER		
PRESTAGE		
SB I-55 MEDIAN		
STA 533+08.30 TO STA 534+58.30		150.0
STA 553+66.63 TO STA 555+16.53		150.0
STAGE 1		
NB I-55 MEDIAN		
STA 540+48.85 TO STA 541+98.85		150.0
STA 562+24.49 TO STA 563+74.49		150.0
TOTAL		600.0

TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 6		EACH
CROSSOVER		
PRESTAGE		
SB I-55 MEDIAN		
STA 534+58.30 TO STA 535+01.45		1
STA 555+16.63 TO STA 555+59.78		1
STAGE 1		
NB I-55 MEDIAN		
STA 540+05.70 TO STA 540+48.85		1
STA 561+81.34 TO STA 562+24.49		1
TOTAL		4

TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)		EACH
CROSSOVER		
PRESTAGE		
SB I-55 MEDIAN		
STA 532+58.30 TO STA 533+08.30		1
STA 553+16.63 TO STA 553+66.63		1
STAGE 1		
NB I-55 MEDIAN		
STA 544+98.85 TO STA 542+48.85		1
STA 563+74.49 TO STA 564+24.49		1
TOTAL		4

REMOVE AND REERECT TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL, TANGENT		EACH
CROSSOVER		
PRESTAGE		
NB I-55 MEDIAN		
STA 530+51.76 TO STA 531+01.77		1
STA 571+53.18 TO STA 572+02.50		1
TOTAL		2

REMOVE AND REERECT STEEL PLATE BEAM GUARDRAIL, TYPE A		FOOT
SN 054-0053, 054-0054		
STAGE 1		
NB I-55 MEDIAN		
STA 532+51.74 TO STA 533+52.41		100.0
NB I-55 OUTSIDE		
STA 532+10.50 TO STA 532+98.00		87.5
STA 539+65.09 TO STA 541+40.09		175.0
STAGE 2		
SB I-55 MEDIAN		
STA 541+53.88 TO STA 542+91.38		137.5
SB I-55 OUTSIDE		
STA 533+78.70 TO STA 535+41.20		162.5
STA 542+09.17 TO STA 542+96.67		87.5

SN 054-0055, 054-0056		
STAGE 1		
NB I-55 MEDIAN		
STA 553+75.00 TO STA 555+00.00		125.0
NB I-55 OUTSIDE		
STA 553+79.73 TO STA 554+92.23		112.5
STAGE 2		
SB I-55 MEDIAN		
STA 562+39.25 TO STA 563+64.24		125.0
SB I-55 OUTSIDE		
STA 562+47.03 TO STA 563+72.03		125.0

CROSSOVER		
PRESTAGE		
NB I-55 MEDIAN		
STA 531+01.77 TO STA 531+51.74		50.0
STA 572+02.90 TO STA 574+96.56		300.0
TOTAL		1,587.5

REMOVE AND REERECT TRAFFIC BARRIER TERMINALS, TYPE 5		EACH
SN 054-0053, 054-0054		
STAGE 2		
NB I-55 OUTSIDE		
STA 539+50.42 TO STA 539+65.09		1
SB I-55 OUTSIDE		
STA 535+41.20 TO STA 535+55.86		1
TOTAL		2

REMOVE AND REERECT TRAFFIC BARRIER TERMINALS, TYPE 6		EACH
SN 054-0053, 054-0054		
STAGE 1		
NB I-55 MEDIAN		
STA 533+52.41 TO STA 533+93.55		1
NB I-55 OUTSIDE		
STA 532+98.00 TO STA 533+41.13		1
STAGE 2		
SB I-55 MEDIAN		
STA 541+10.73 TO STA 541+53.88		1
SB I-55 OUTSIDE		
STA 541+66.02 TO STA 542+09.17		1

SN 054-0055, 054-0056		
STAGE 1		
NB I-55 MEDIAN		
STA 555+00.00 TO STA 555+43.16		1
NB I-55 OUTSIDE		
STA 554+92.23 TO STA 555+35.38		1
STAGE 2		
SB I-55 MEDIAN		
STA 561+96.10 TO STA 562+39.25		1
SB I-55 OUTSIDE		
STA 562+03.88 TO STA 562+47.02		1
TOTAL		8

GUARDRAIL MARKERS TYPE A		EACH
SN 054-0053, 054-0054		
NB I-55 OUTSIDE		
STA 532+10.50 TO STA 533+41.14		2
STA 539+50.42 TO STA 541+40.09		3
NB I-55 MEDIAN		
STA 532+02.41 TO STA 533+95.56		3
SB I-55 OUTSIDE		
STA 533+78.68 TO STA 535+55.86		3
STA 541+66.01 TO STA 542+96.67		2
SB I-55 MEDIAN		
STA 541+10.73 TO STA 542+91.38		3
SN 054-0055, 054-0056		
NB I-55 OUTSIDE		
STA 553+80.38 TO STA 555+35.38		2
NB I-55 MEDIAN		
STA 553+75.01 TO STA 555+43.15		3
SB I-55 OUTSIDE		
STA 562+03.88 TO STA 563+72.01		3
SB I-55 MEDIAN		
STA 561+96.10 TO STA 563+64.24		3
TOTAL		27

BARRIER WALL MARKERS			
LOCATION	TYPE B	TYPE C	
	EACH	EACH	
SN 054-0053, 054-0054			
NB I-55 OUTSIDE			
STA 533+41.14 TO STA 539+50.42	8	8	
NB I-55 MEDIAN			
STA 533+95.56 TO STA 540+05.70	8	8	
SB I-55 OUTSIDE			
STA 535+55.86 TO STA 541+66.01	8	8	
SB I-55 MEDIAN			
STA 535+01.44 TO STA 541+10.73	8	8	

SN 054-0055, 054-0056			
NB I-55 OUTSIDE			
STA 555+35.38 TO STA 561+73.56	8	8	
NB I-55 MEDIAN			
STA 555+43.15 TO STA 561+81.34	8	8	
SB I-55 OUTSIDE			
STA 555+65.70 TO STA 562+03.88	8	8	
SB I-55 MEDIAN			
STA 555+57.92 TO STA 561+96.10	8	8	
TOTAL	64	64	

TEMPORARY CONCRETE BARRIER				FOOT
SN 054-0050				
STAGE 1				
NB I-55				
STA 13+45.35 TO STA 15+31.90	12:1 TAPER			187.5
STA 15+31.90 TO STA 17+69.75	TANGENT			237.5

CROSSOVERS				
STAGE 1				
STA 527+71.27 TO STA 568+70.60				4,100.0
STA 568+70.60 TO STA 569+95.20	12:1 TAPER			125.0
TOTAL				4,650.0

RELOCATE TEMPORARY CONCRETE BARRIER				FOOT
SN 054-0050				
STAGE 2				
NB I-55				
STA 13+45.35 TO STA 15+31.90	12:1 TAPER			187.5
STA 15+31.90 TO STA 17+69.75	TANGENT			237.5

CROSSOVERS				
STAGE 2				
STA 527+67.35 TO STA 529+35.00				175.0
STA 529+35.00 TO STA 569+85.00				4,050.0
TOTAL				4,650.0

TEMPORARY MODULAR GLARE SCREEN			FOOT
STAGE 1			
STA 528+00.00 TO STA 534+00.00			600
TOTAL			600

RELOCATE MODULAR GLARE SCREEN			FOOT
STAGE 2			
STA 563+15.00 TO STA 569+15.00			600
TOTAL			600

IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3			EACH
SN 054-0050			
STAGE 1			
NB I-155			
STA 13+45.35			1
NB I-55			
STA 569+90.60			1
TOTAL			2

IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3			EACH
SN 054-0050			
STAGE 2			
NB I-155			
STA 13+45.35			1
NB I-55			
STA 527+67.35			1
TOTAL			2

MEDIAN CLOSURE			EACH
SB I-55			
STA 524+20.00 TO STA 531+20.00			1
STA 569+85.00 TO STA 576+85.00			1
NB I-55			
STA 523+00.00 TO STA 530+00.00			1
STA 565+98.00 TO STA 572+98.00			1
TOTAL			4

RAISED REFLECTIVE PAVEMENT MARKER			EACH
SN 054-0053, 0054			
NB I-55			
STA 532+29.96 TO STA 541+35.82			12
SB I-55			
STA 533+84.73 TO STA 542+90.61			12
SN 054-0055, 0056			
NB I-55			
STA 553+83.64 TO STA 563+33.87			12
SB I-55			
STA 554+05.40 TO STA 563+55.63			12
TOTAL			48



JOB = 2265.4
 FILE NAME = D672E10-shr-sched.dgn
 PLOT SCALE = 2.0000 ' / IN.
 PLOT DATE = 9/8/2011

DESIGNED - NAK
 DRAWN - TJD
 CHECKED - NAK
 DATE - 8/12/2011

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

FAI ROUTE 55
 SCHEDULES OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	D6 LOGAN CO BR 2011	LOGAN	224	16
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
			CONTRACT NO. 72E10	