

URETHANE PAVEMENT MARKING - LINE 5"

LOCATION	DESCRIPTION	WHITE SKIP DASH FOOT	SOLID YELLOW LINE FOOT	SOLID WHITE LINE FOOT	TOTAL FOOT
<b>SN 054-0050</b>					
NB I-155					
STA 395+56.00	TO STA 398+94.34	SKIP DASH			90.00
STA 1+15.00	TO STA 7+87.00	SKIP DASH			170.00
STA 12+87.00	TO STA 19+92.10	MEDIAN EDGE LINE	705.10		705.10
STA 12+87.00	TO STA 19+92.10	OUTSIDE EDGE LINE		706.10	706.10
<b>CROSSOVERS</b>					
FINAL PHASE					
NB I-55					
STA 500+62.00	TO STA 574+76.00	SKIP DASH	1,860.00		1,860.00
STA 500+62.00	TO STA 574+76.00	OUTSIDE EDGE LINE		7,414.00	7,414.00
STA 500+62.00	TO STA 574+76.00	MEDIAN EDGE LINE		7,414.00	7,414.00
					0.00
					0.00
SB I-55					
STA 522+47.00	TO STA 596+56.00	OUTSIDE EDGE LINE		7,409.00	7,409.00
STA 522+47.00	TO STA 596+56.00	MEDIAN EDGE LINE	7,409.00		7,409.00
STA 522+47.00	TO STA 596+56.00	SKIP DASH	1,860.00		1,860.00
TOTAL			3,980.00	15,528.10	15,529.10

PAVEMENT MARKING REMOVAL

LOCATION	DESCRIPTION	LINE WIDTH INCHES	QTY SQ FT
<b>SN 054-0050</b>			
STAGE 1			
NB I-155			
STA 397+68.50	TO STA 398+94.34	SKIP DASH	5 20.83
STA 1+15.00	TO STA 7+87.00	SKIP DASH	5 75.00
STA 12+87.00	TO STA 19+65.00	MEDIAN EDGE LINE	5 282.50
STAGE 2			
NB I-155			
STA 395+56.00	TO STA 397+68.50	SKIP DASH	5 29.17
STA 12+87.00	TO STA 19+92.10	OUTSIDE EDGE LINE	5 293.79
<b>CROSSOVERS</b>			
STAGE 1			
NB I-55			
STA 500+62.00	TO STA 510+62.00	SKIP DASH	5 108.33
STA 520+50.00	TO STA 525+78.00	MEDIAN EDGE LINE	5 220.00
STA 571+68.00	TO STA 576+76.00	MEDIAN EDGE LINE	5 211.67
SB I-55			
STA 528+42.00	TO STA 569+04.00	MEDIAN EDGE LINE	5 1,692.50
STA 525+51.00	TO STA 568+71.00	SKIP DASH	5 454.17
STA 525+51.00	TO STA 568+71.00	OUTSIDE EDGE LINE	5 1,800.00
STA 573+71.00	TO STA 583+71.00	SKIP DASH	5 108.33
STAGE 2			
NB I-55			
STA 512+20.00	TO STA 522+20.00	SKIP DASH	5 108.33
STA 527+20.00	TO STA 569+81.00	OUTSIDE EDGE LINE	5 1,775.42
STA 528+17.00	TO STA 568+76.00	MEDIAN EDGE LINE	5 1,691.25
STA 527+20.00	TO STA 568+49.68	SKIP DASH	5 437.50
SB I-55			
STA 522+47.00	TO STA 525+55.00	MEDIAN EDGE LINE	5 128.33
STA 571+39.00	TO STA 574+68.00	MEDIAN EDGE LINE	5 137.08
STA 586+56.00	TO STA 596+56.00	SKIP DASH	5 108.33
FINAL PHASE			
NB I-55			
STA 500+62.00	TO STA 574+76.00	OUTSIDE EDGE LINE	5 3,089.17
STA 500+62.00	TO STA 574+76.00	MEDIAN EDGE LINE	5 3,089.17
STA 500+62.00	TO STA 574+76.00	SKIP DASH	5 779.17
SB I-55			
STA 522+47.00	TO STA 596+56.00	OUTSIDE EDGE LINE	5 3,087.08
STA 522+47.00	TO STA 596+56.00	MEDIAN EDGE LINE	5 3,087.08
STA 522+47.00	TO STA 596+56.00	SKIP DASH	5 779.17
TOTAL			23,593.37

TEMPORARY PAVEMENT MARKING - LINE 5"

LOCATION	SOLID YELLOW FOOT	SOLID WHITE FOOT	WHITE SKIP DASH FOOT	TOTAL FOOT	WORK ZONE PAVEMENT MARKING REMOVAL SQ FT
<b>SN 054-0050</b>					
STAGE 1					
NB I-155					
STA 397+68.50	TO STA 398+94.34		126	126	52.50
STA 1+15.00	TO STA 17+70.00		1,655	1,655	689.59
STA 12+87.00	TO STA 19+65.00	678		678	282.50
STAGE 2					
NB I-155					
STA 395+56.00	TO STA 398+94.34		339	339	141.25
STA 1+15.00	TO STA 17+70.00		1,655	1,655	689.59
STA 12+87.00	TO STA 19+92.10		706	706	294.17
<b>CROSSOVERS</b>					
STAGE 1					
NB I-55					
STA 500+62.00	TO STA 574+76.00		7,414	7,414	3,089.17
STA 520+62.00	TO STA 574+76.00	5,414		5,414	2,255.84
SB I-55					
STA 525+51.00	TO STA 583+71.00	5,820		5,820	2,425.00
STA 525+51.00	TO STA 568+71.00		4,320	4,320	1,800.00
WINTER SHUTDOWN					
NB I-55					
STA 500+62.00	TO STA 574+76.00	7,414	7,414	1,860	16,688
SB I-55					
STA 525+51.00	TO STA 583+71.00	5,820	5,820	1,460	13,100
STAGE 2					
NB I-55					
STA 512+20.00	TO STA 569+90.00	5,770		5,770	2,404.17
STA 527+20.00	TO STA 569+90.00	4,270	4,270		3,558.34
SB I-55					
STA 522+47.00	TO STA 575+19.00	5,272		5,272	2,196.67
STA 522+47.00	TO STA 596+56.00		7,409	7,409	3,087.09
TOTAL		40,458	41,128	3,320	84,906

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL

LOCATION	DESCRIPTION	EACH
SN 054-0053, 0054, 0055, 0056		
STAGE 1		
NB I-55		
STA 532+29.96	TO STA 533+29.96	SKIP DASH - WEST RAMP 054-0053
STA 540+35.82	TO STA 541+35.82	SKIP DASH - EAST RAMP 054-0053
STA 553+83.64	TO STA 554+83.64	SKIP DASH - WEST RAMP 054-0055
STA 562+33.87	TO STA 563+33.87	SKIP DASH - EAST RAMP 054-0055
STAGE 2		
SB I-55		
STA 533+84.73	TO STA 534+84.73	SKIP DASH - WEST RAMP 054-0054
STA 541+90.61	TO STA 542+90.61	SKIP DASH - EAST RAMP 054-0054
STA 554+05.40	TO STA 555+05.40	SKIP DASH - WEST RAMP 054-0056
STA 562+55.63	TO STA 563+55.63	SKIP DASH - EAST RAMP 054-0056
TOTAL		16

SHORT-TERM PAVEMENT MARKING

LOCATION	DESCRIPTION	NO. OF APPLICATIONS	NO. OF LINES	QTY FOOT	WORK ZONE PAVEMENT MARKING REMOVAL SQ FT
<b>SN 054-0050</b>					
NB I-155					
STA 395+56.00	TO STA 398+94.34	SKIP DASH	1	95	39.59
STA 1+15.00	TO STA 7+87.00	SKIP DASH	1	178	74.17
STA 12+87.00	TO STA 19+92.10	MEDIAN EDGE LINE	1	81	33.75
STA 12+87.00	TO STA 19+92.10	OUTSIDE EDGE LINE	1	81	33.75
<b>CROSSOVERS</b>					
NB I-55					
STA 511+83.00	TO STA 524+00.00	SKIP DASH	2	629	262.09
STA 526+83.00	TO STA 568+18.10	OUTSIDE EDGE LINE	2	847	352.92
STA 529+00.00	TO STA 566+09.90	MEDIAN EDGE LINE	2	762	317.50
SB I-55					
STA 529+06.10	TO STA 569+07.95	OUTSIDE EDGE LINE	2	820	341.67
STA 531+11.90	TO STA 566+92.65	MEDIAN EDGE LINE	2	736	306.67
STA 571+92.65	TO STA 584+08.00	SKIP DASH	2	628	261.67
TOTAL				4,857	2,023.78



JOB = 2265.4	DESIGNED - NAK	REVISED -
FILE NAME = 0672E10-shr-sched.dgn	DRAWN - TJD	REVISED -
PLOT SCALE = 2.0000' / IN.	CHECKED - NAK	REVISED -
PLOT DATE = 9/8/2011	DATE - 8/12/2011	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

FAI ROUTE 55  
SCHEDULES OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	D6 LOGAN CO BR 2011	LOGAN	224	17
FED. ROAD DIST. NO.			CONTRACT NO. 72E10	
ILLINOIS FED. AID PROJECT				