

NOTES

1. ANY REFERENCE TO A STANDARD IN THE PLANS SHALL BE INTERPRETED TO MEAN THE EDITION, AS INDICATED BY THE SUB-NUMBER LISTED IN THE INDEX OF SHEETS, OR THE COPY OF THE STANDARD INCLUDED IN THE PLANS
2. ACCESS MUST BE MAINTAINED TO ALL EXISTING PROPERTIES DURING CONSTRUCTION PER ARTICLE 107.09 UNLESS ARRANGEMENTS ARE MADE IN WRITING BY THE CONTRACTOR WITH THE PROPERTY OWNERS WITH A COPY TO THE ENGINEER FOR SHORT-TERM CLOSURES
3. THE DISTRICT BUREAU OF OPERATIONS SHALL BE NOTIFIED AT LEAST 14 DAYS PRIOR TO PLACEMENT OF FINAL PAVEMENT MARKINGS. PHONE: (217) 782-7314
4. THE EXISTING ROAD SIGNS THAT INTERFERE WITH CONSTRUCTION SHALL BE RELOCATED AS DIRECTED BY THE ENGINEER. AFTER THE CONSTRUCTION IS COMPLETE, THE CONTRACTOR SHALL REPLACE THE SIGNS AS DIRECTED BY THE ENGINEER. THIS WORK WILL NOT BE PAID FOR SEPARATELY, BUT CONSIDERED INCLUDED IN THE CONTRACT UNIT BID PRICES.
5. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING UTILITY PROPERTY FROM CONSTRUCTION OPERATIONS AS OUTLINED IN ARTICLE 107.31 OF THE STANDARD SPECIFICATIONS. THE JULIE NUMBER IS 800-892-0123.
6. SAW CUTS TO BE INCLUDED IN DRIVEWAY PAVEMENT REMOVAL PAY ITEM

INDEX OF SHEETS

- 1 COVER SHEET
- 2 GENERAL NOTES
- 3 SUMMARY OF QUANTITIES
- 4 SCHEDULE OF QUANTITIES
- 5 TYPICAL SECTIONS
- 6 - 12 PLAN SHEETS
- 13 RUMBLE STRIP DETAIL
- 14 SHOULDER WRAP AROUND DETAIL

MIXTURE REQUIREMENTS

Location(s):	FAP 614 (IL 78)	FAP 614 (IL 78)
Mixture Use(s):	HMA Shoulders (Bottom lifts)	HMA Shoulders (Top lift, 1.5" minimum)
PG:	PG 58-22	PG 64-22
Design Air Voids:	2% @ N=30	4% @ N=50
Mixture Composition:	BAM	IL 9.5 OR IL 12.5
Friction Aggregate:	N/A	MIX C

DISTRICT SIX	
EXAMINED <u>August 8</u> 20 <u>11</u> <i>Chris Walker</i>	
OPERATIONS ENGINEER	
EXAMINED <u>JULY 6</u> 20 <u>11</u> <i>Tommy F...</i>	
PROJECT IMPLEMENTATION ENGINEER	
EXAMINED <u>July 5,</u> 20 <u>11</u> <i>2RML</i>	
PROGRAM DEVELOPMENT ENGINEER	