## **INDEX OF SHEETS**

- COVER SHEET
- INDEX, GENERAL NOTES, STANDARDS, & SIGNATURES
- SUMMARY OF QUANTITIES
- 4.-7. BRIDGE LOCATION MAPS
- 8.-9. SCHEDULE OF QUANTITIES 10. BRIDGE PLAN SHEETS

## **HIGHWAY STANDARDS**

000001-06

001006

701201-04

701400-05

701406-06

701411-07

701501-06 701901-0**1** 

## **GENERAL NOTES**

THE CONCRETE SEALER SHALL BE APPLIED TO THE ENTIRE TOP SURFACE OF THE DECK, INCLUDING THE INSIDE FACES AND TOPS OF THE PARAPETS. WATER BASED CONCRETE SEALERS WILL NOT BE ALLOWED.

**COMMITMENTS** 

PROJECTS.

COMMITMENTS ARE NOT TO BE ALTERED WITHOUT THE WRITTEN

1. THE RESIDENT ENGINEER SHALL CONTACT STUDIES AND PLANS

CONCERNING ANY MAJOR PLAN CHANGE, TO MAKE SURE NO PREVIOUS COMMITMENTS (NOT LISTED) WERE MADE AFFECTING THE DESIGN AND ALLOW AN IMPROVED DESIGN FOR FUTURE

APPROVAL OF ALL PARTIES TO WHICH THE COMMITMENT WAS MADE.

Existing pavement markings shall be temporarily covered prior to application of the deck surface treatment, to prevent the material from being applied to the markings. The temporary covering shall be removed after application of the deck surface treatment and prior to opening to traffic. Cost included with Concrete Sealer.

DISTRICT SIX
EXAMINED JULY 13 20 11 OPERATIONS ENGINEER
EXAMINED JUNE 24 20 11
PROJECT IMPLEMENTATION ENGINEER
EXAMINED July 5 20 11
PROGRAM DEVELOPMENT ENGINEER

• DISTRICT 6 BRIDGE DECK SEALING 2011 " VARIOUS

	ILE NAME =	USER NAME = whitlingme	DESIGNED -	REVISED -	STATE OF ILLINOIS	INDEX OF SHEETS. GENERAL NOTES		F.A.	SECTION	COUNTY	TOTAL	SHEET
- 1	:\pw_work\pwidot\whitlingme\d0255541\06	72E24-sht-gennote.dgn	DRAWN -	REVISED -					•	••	10	2
- 1		PLOT SCALE = 40.0000 '/ in.	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION	AND COMMITMENTS			CONTRACT NO. 72E24			
		PLOT DATE = Aug-18-2011 01:22:08PM	DATE -	REVISED -		SCALE:	SHEET NO. 1 OF 1 SHEETS STA. TO STA.	<b>—</b>	ILLINOIS FE	D. AID PROJECT	110. 12	