

INDEX OF SHEETS

- 1 COVER SHEET
- 2 INDEX, GENERAL NOTES, STANDARDS
- 3 SUMMARY OF QUANTITIES
- 4 SCHEDULE OF QUANTITIES
- 5-8 BRIDGE LOCATION MAPS
- 9 BRIDGE PLAN SHEETS

HIGHWAY STANDARDS

- 701001-02
- 701006-03
- 701101-02
- 701106-02
- 701201-04
- 701400-05
- 701406-06
- 701901-01

GENERAL NOTES

THE CONCRETE SEALER SHALL BE APPLIED TO THE ENTIRE TOP SURFACE OF THE DECK, INCLUDING THE INSIDE FACES AND TOPS OF THE PARAPETS.

Existing pavement markings shall be temporarily covered prior to application of the deck surface treatment, to prevent the material from being applied to the markings. The temporary covering shall be removed after application of the deck surface treatment and prior to opening to traffic. Cost included with Concrete Sealer.

DISTRICT SIX	
EXAMINED	FEB 17 20 11
<i>Chris Wall</i>	
OPERATIONS ENGINEER	

EXAMINED	JANUARY 28 20 11
<i>Jimmy Felt</i>	
PROJECT IMPLEMENTATION ENGINEER	
EXAMINED	August 23 20 11
<i>ORMLI</i>	
PROGRAM DEVELOPMENT ENGINEER	

* VARIOUS ROUTES
 ** D6 BDGE DECK SEALING 2011-1
 *** VARIOUS