

S U M M A R Y O F Q U A N T I T I E S

CODE NO.	ITEM	UNIT	100% STATE
			0014
			TOTAL QTY
50102400	CONCRETE REMOVAL	CU. YD.	39.3
50300255	CONCRETE SUPERSTRUCTURE	CU. YD.	33.4
50800205	REINFORCEMENT BARS - EPOXY COATED	POUND	3410
50800515	BAR SPLICERS	EACH	56
* X7200201	WIDTH RESTRICTION SIGNING	L SUM	1
52000110	PREFORMED JOINT STRIP SEAL	FOOT	84
67100100	MOBILIZATION	L SUM	1
X7010208	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402 (SPECIAL)	EACH	1
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	3
Z0034393	MODULAR EXPANSION JOINT, 9"	FOOT	84
Z0034398	MODULAR EXPANSION JOINT, 15"	FOOT	84
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	3
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	270
70400100	TEMPORARY CONCRETE BARRIER	FDDT	2125
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FDDT	2125
78300100	PAVEMENT MARKING REMOVAL	SQ FT	3600
* X7800620	URETHANE PAVEMENT MARKING-LINE 5"	FDDT	7769
* 70300100	SHORT TERM PAVEMENT MARKING	FDDT	648

* SPECIALTY ITEM

QUANTITIES
FAI 72 (I-72)
SECTION (75,86)BJR-1
PIKE COUNTY