

80% FEDERAL
20% STATE

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		0011	0011
				SN 013-2012	SN 013-2013
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	296	167	129
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	201	75	126
20200100	EARTH EXCAVATION	CU YD	1569	1045	524
20400800	FURNISHED EXCAVATION	CU YD	507		507
20700110	POROUS GRANULAR EMBANKMENT	TON	715	715	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	113	70	43
28000305	TEMPORARY DITCH CHECKS	FOOT	268	226	42
28000400	PERIMETER EROSION BARRIER	FOOT	200		200
28100107	STONE RIPRAP, CLASS A4	SQ YD	124	124	
28100109	STONE RIPRAP, CLASS A5	SQ YD	662		662
28200200	FILTER FABRIC	SQ YD	786	124	662
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	1.6		1.6
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	128		128
40600300	AGGREGATE (PRIME COAT)	TON	3		3
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	367		367
40600990	TEMPORARY RAMP	SQ YD	24		24
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	419		419
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	107		107
40701961	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 14"	SQ YD	82		82
42000500	PORTLAND CEMENT CONCRETE PAVEMENT 10"	SQ YD	133	133	
42001200	PAVEMENT FABRIC	SQ YD	133	133	
44000100	PAVEMENT REMOVAL	SQ YD	136	63	73
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SQ YD	25		25
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	1198	533	665
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1	1	
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1		1
50200450	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL FOR STRUCTURES	CU YD	182		182
50800105	REINFORCEMENT BARS	POUND	36410		36410
50800515	BAR SPLICERS	EACH	20	20	
51500100	NAME PLATES	EACH	2	1	1

80% FEDERAL
20% STATE

SUMMARY OF QUANTITIES (Cont'd)			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		0011	0011
				SN 013-2012	SN 013-2013
54001001	BOX CULVERT END SECTIONS, CULVERT NO. 1	EACH	2	2	
54003000	CONCRETE BOX CULVERTS	CU YD	198		198
54011006	PRECAST CONCRETE BOX CULVERTS 10' X 6'	FOOT	118	118	
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	637.5		637.5
* 63000025	STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURES	FOOT	53		53
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4		4
63200310	GUARDRAIL REMOVAL	FOOT	753		753
66600105	FURNISHING AND ERECTING RIGHT OF WAY MARKERS	EACH	12	8	4
67100100	MOBILIZATION	L SUM	1	0.5	0.5
70300100	SHORT TERM PAVEMENT MARKING	FOOT	156		156
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	17		17
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	2081	900	1181
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	9		9
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	11		11
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4		4
* A2006416	TREE, QUERCUS ALBA (WHITE OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	7	7	
* A2007116	TREE, QUERCUS RUBRA (RED OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	12	7	5
* A2007616	TREE, TAXODIUM DISTICHUM (COMMON BALD CYPRESS), 2" CALIPER, BALLED AND BURLAPPED	EACH	5		5
* D2001772	EVERGREEN, PICEA ABIES (NORWAY SPRUCE), 6' HEIGHT, BALLED AND BURLAPPED	EACH	5		5
* D2002948	EVERGREEN, PINUS STROBUS (EASTERN WHITE PINE), 4' HEIGHT, BALLED AND BURLAPPED	EACH	7	7	
* X2501000	SEEDING, CLASS 2 (SPECIAL)	ACRE	1.1	0.7	0.4
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	770		770
X7011830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	EACH	2	1	1
Z0023602	GRANULAR CULVERT BACKFILL	CU YD	336		336
Z0054505	ROCK FILL - REPLACEMENT	TON	327		327
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	5	

* SPECIALTY ITEM