



EXCAVATION DETAIL

EARTHWORK SCHEDULE

| LOCATION | EARTH EXCAVATION CU. YD. | EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE CU. YD. | EMBANKMENT CU. YD. | EARTHWORK BALANCE WASTE (+) SHORTAGE (-) CU. YD. |
|----------------------|-----------------------------|---|-----------------------|--|
| STA 406+00 TO 410+00 | 1044 | 783 | | 783 |
| STA 406+00 TO 410+00 | | | 316 | -316 |
| EXCAVATION FOR BOX | 349 | 262 | | 262 |
| TOTALS | 1393 | 1045 | 316 | 729 |

| PCC PAVEMENT 10" | |
|----------------------|-----------|
| STA 407+73 TO 408+23 | 133 S. Y. |

| AGGREGATE SHOULDERS, TYPE B 6" | |
|--------------------------------|-----------|
| STA 406+00 TO 410+00 | 533 S. Y. |

| SEEDING, CLASS 2 (SPECIAL) | |
|----------------------------|----------|
| STA 406+00 TO 410+00 | 0.7 ACRE |

| PAINT PAVEMENT MARKING - LINE 4" | |
|----------------------------------|-----|
| STA 406+00 TO 410+00 EDGE LINES | 800 |
| STA 406+00 TO 410+00 DASHES | 100 |
| TOTAL | 900 |

| TREE REMOVAL (6-15 UNITS DIAMETER) | |
|------------------------------------|-----------|
| RT STA 406+75 TO 407+75 | 167 UNITS |

| TREE REMOVAL (OVER 15 UNITS DIAMETER) | |
|---------------------------------------|----------|
| RT STA 406+80 TO 407+75 | 75 UNITS |

| PAVEMENT FABRIC | |
|----------------------|-----------|
| STA 407+73 TO 408+23 | 133 S. Y. |