

RESURFACING SCHEDULE													
STATION TO STATION	LENGTH	AVERAGE PAVEMENT WIDTH	AREA	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	AGGREGATE SHOULDERS, TYPE B 6"	PAVEMENT REMOVAL	HOT-MIX ASPHALT PAVEMENT (FULL DEPTH) 14"	TEMPORARY RAMP
	FOOT	FOOT	SQ YD	SQ YD	SQ YD	GALLON	TON	TON	TON	SQ YD	SQ YD	SQ YD	SQ YD
333+85.00 TO 334+90.00	105.0	22.0	256.7	0.0	256.7	25.7	0.5	21.6	0.0	140.0	0.0	0.0	12.2
334+90.00 TO 336+16.00	126.0	22.0	308.0	308.0	0.0	30.8	0.6	25.9	100.3	168.0	0.0	0.0	0.0
336+16.00 TO 336+31.00	15.0	22.0	36.7	0.0	0.0	3.7	0.1	0.0	0.0	20.0	36.7	36.7	0.0
336+31.00 TO 336+32.75	1.8	22.0	4.3	0.0	0.0	0.4	0.0	0.0	0.0	2.3	0.0	4.3	0.0
336+32.75 TO 336+59.25	26.5	48.0	141.3	0.0	0.0	6.5	0.1	11.9	130.4	0.0	0.0	0.0	0.0
336+59.25 TO 336+61.00	1.8	22.0	4.3	0.0	0.0	0.4	0.0	0.0	0.0	2.3	0.0	4.3	0.0
336+61.00 TO 336+76.00	15.0	22.0	36.7	0.0	0.0	3.7	0.1	0.0	0.0	20.0	36.7	36.7	0.0
336+76.00 TO 338+65.00	189.0	22.0	462.0	462.0	0.0	46.2	0.9	38.8	188.0	252.0	0.0	0.0	0.0
338+65.00 TO 339+10.00	45.0	22.0	110.0	0.0	110.0	11.0	0.2	9.2	0.0	60.0	0.0	0.0	12.2
TOTALS				770.0	367.0	128.0	3.0	107.0	419.0	665.0	73.0	82.0	24.0

TREE REMOVAL SCHEDULE		
SN 013-2013	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	TREE REMOVAL (OVER 15 UNITS DIAMETER)
	UNIT	UNIT
NE QUAD	24	86
NW QUAD	90	40
SE QUAD	9	
SW QUAD	6	
TOTALS	129	126

PAVEMENT MARKING SCHEDULE							
STATION TO STATION	LENGTH	PAINT PAVEMENT MARKING - LINE 4" (WHITE)	PAINT PAVEMENT MARKING - LINE 4" (YELLOW)	TEMPORARY PAVEMENT MARKING - LINE 4"	SHORT-TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER
	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	SQ FT
333+85.00 TO 336+32.75	247.8	495.5	61.9	557.4	72.0	8.0	4.0
336+32.75 TO 336+59.25	26.5	53.0	6.6	59.6	12.0	1.3	1.0
336+59.25 TO 339+10.00	250.8	501.5	62.7	564.2	72.0	8.0	4.0
TOTALS		1050.0	131.0	1181.0	156.0	17.0	9.0