

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 80% FED. 20% STATE 0011
CODE NO	ITEM	UNIT		
20200100	EARTH EXCAVATION	CU YD	763	763
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	27	27
28000305	TEMPORARY DITCH CHECKS	FOOT	48	48
28000400	PERIMETER EROSION BARRIER	FOOT	1000	1000
28100207	STONE RIPRAP, CLASS A4	TON	749	749
28200200	FILTER FABRIC	SQ YD	833	833
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	119	119
40600300	AGGREGATE (PRIME COAT)	TON	2	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	213	213
40600990	TEMPORARY RAMP	SQ YD	239	239
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	307	307
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	100	100
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	56	56
44000100	PAVEMENT REMOVAL	SQ YD	402	402
44201863	CLASS D PATCHES, TYPE II, 18 INCH	SQ YD	26	26
44201867	CLASS D PATCHES, TYPE III, 18 INCH	SQ YD	18	18
48101200	AGGREGATE SHOULDERS, TYPE B	TON	208	208
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1
50200100	STRUCTURE EXCAVATION	CU YD	92	92
50300225	CONCRETE STRUCTURES	CU YD	65.2	65.2
50300255	CONCRETE SUPERSTRUCTURE	CU YD	290.3	290.3
50300260	BRIDGE DECK GROOVING	SQ YD	650	650
50300280	CONCRETE ENCASEMENT	CU YD	4.2	4.2
50300300	PROTECTIVE COAT	SQ YD	797	797
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1	1
50500505	STUD SHEAR CONNECTORS	EACH	1368	1368
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	71980	71980
50800515	BAR SPLICERS	EACH	676	676
51201610	FURNISHING STEEL PILES HP12X63	FOOT	760	760
51202305	DRIVING PILES	FOOT	760	760
51203610	TEST PILE STEEL HP12X63	EACH	2	2
51500100	NAME PLATES	EACH	1	1
52100520	ANCHOR BOLTS, 1"	EACH	24	24
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	96.2	96.2
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	4	4

SUMMARY OF QUANTITIES (Cont'd)			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 80% FED. 20% STATE 0011
CODE NO	ITEM	UNIT		
60100905	PIPE DRAINS 4"	FOOT	62	62
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	300	300
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4
63200310	GUARDRAIL REMOVAL	FOOT	567	567
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	1	1
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	7	7
67100100	MOBILIZATION	L SUM	1	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	184	184
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	1656	1656
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	24	24
70400100	TEMPORARY CONCRETE BARRIER	FOOT	412.5	412.5
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	312.5	312.5
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	1656	1656
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	8	8
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	2	2
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	9	9
* 78200520	BARRIER WALL MARKERS, TYPE B	EACH	2	2
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4
78300100	PAVEMENT MARKING REMOVAL	SQ FT	484	484
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	156	156
X2501000	SEEDING, CLASS 2 (SPECIAL)	ACRE	0.1	0.1
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	974	974
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	30	30
Z0026407	TEMPORARY SHEET PILING	SQ FT	1165	1165
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	1	1
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	168	168

* SPECIALTY ITEM

FILE NAME =	USER NAME = swartzw	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwork\pwork\swartzw\dms52812\d774280-sht-soq.dgn		DRAWN -	REVISED -			320	(102BY)B-1	MOULTRIE	48	3	
	PLOT SCALE = 48.0000' / in.	CHECKED -	REVISED -			CONTRACT NO. 74280					
	PLOT DATE = 8/8/2011	DATE -	REVISED -			SCALE: NA	SHEET NO. 1 OF 1 SHEETS	STA. TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT	