

RESURFACING SCHEDULE		LENGTH	AVERAGE PAVEMENT & SHOULDER WIDTH	AREA	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	AGGREGATE SHOULDERS, TYPE B	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	TEMPORARY RAMP
STATION TO STATION		FOOT	FOOT	SQ YD	GALLON	TON	TON	TON	TON	SQ YD	SQ YD	SQ YD	SQ YD
137+50.00	TO 137+80.00	30.0	32.0	106.7	10.7	0.2	0.0	9.0	9.1	0.0	0.0	106.7	13.3
137+80.00	TO 138+31.00	51.0	32.0	181.3	18.1	0.4	40.6	15.2	29.0	181.3	0.0	0.0	63.0
138+31.00	TO 139+97.00	166.0									55.8		
139+97.00	TO 142+20.00	223.0	32.0	792.9	79.3	1.6	266.4	66.6	160.8	792.9	0.0	0.0	149.3
142+20.00	TO 142+50.00	30.0	32.0	106.7	10.7	0.2	0.0	9.0	9.1	0.0	0.0	106.7	13.3
TOTALS				1188.0	119.0	2.0	307.0	100.0	208.0	974.0	56.0	213.0	239.0

GUARDRAIL SCHEDULE		GUARDRAIL REMOVAL	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	TRAFFIC BARRIER TERMINAL, TYPE 6	GUARDRAIL MARKERS, TYPE A	BARRIER WALL MARKERS, TYPE B	TERMINAL MARKERS - DIRECT APPLIED
LOCATION		FOOT	EACH	FOOT	FOOT	EACH	EACH	EACH
NORTHEAST CORNER		89.0	1.0	12.5	1.0			1.0
SOUTHEAST CORNER		189.0	1.0	125.0	1.0			1.0
NORTHWEST CORNER		189.0	1.0	125.0	1.0			1.0
SOUTHWEST CORNER		100.0	1.0	37.5	1.0			1.0
LEFT SIDE						4.0	1.0	
RIGHT SIDE						5.0	1.0	
TOTALS=		567.0	4.0	300.0	4.0	9.0	2.0	4.0

PAVEMENT MARKING SCHEDULE		LENGTH	PAINT PAVEMENT MARKING - LINE 4"	TEMPORARY PAVEMENT MARKING - LINE 4"	SHORT-TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	PAVEMENT MARKING REMOVAL
STATION TO STATION		FOOT	FOOT	FOOT	FOOT	SQ FT	EACH	EACH	SQ FT
135+48.00	TO 138+31.00	283.0	636.0	636.0	84.0	9.3	4.0	0.0	212.0
138+31.00	TO 139+95.00	164.0	368.0	368.0	16.0	5.3	0.0	2.0	54.7
139+95.00	TO 142+86.00	291.0	652.0	652.0	84.0	9.3	4.0	0.0	217.3
TOTALS			1656.0	1656.0	184.0	24.0	8.0	2.0	484.0

PAVEMENT PATCHING SCHEDULE		CLASS D PATCHES, TYPE II 18 INCH	CLASS D PATCHES, TYPE III 18 INCH
LOCATION		SQ YD	SQ YD
IL 121 (RT & LT)		26.0	18.0
TOTALS		26.0	18.0

PATCH THICKNESS BASED ON THE MAXIMUM EXISTING PAVEMENT THICKNESS