

SEEDING & FERTILIZER SCHEDULE	SEEDING, CLASS 2 (SPECIAL)	TEMPORARY EROSION CONTROL SEEDING	NITROGEN FERTILIZER NURTIENT *	PHOSPHORUS FERTILIZER NURTIENT *	POTASSIUM FERTILIZER NURTIENT *	MULCH, METHOD 2 *	AGRICULTURAL GROUND LIMESTONE *
	ACRE	POUND	POUND	POUND	POUND	ACRE	TON
STATION TO STATION							
136+00.0 TO 136+25.0	0.00	0.00	0.13	0.13	0.13	0.00	0.00
136+25.0 TO 136+50.0	0.00	0.29	0.26	0.26	0.26	0.00	0.01
136+50.0 TO 136+75.0	0.00	0.21	0.19	0.19	0.19	0.00	0.00
136+75.0 TO 137+00.0	0.00	0.09	0.09	0.09	0.09	0.00	0.00
137+00.0 TO 137+25.0	0.00	0.06	0.05	0.05	0.05	0.00	0.00
137+25.0 TO 137+50.0	0.00	0.03	0.03	0.03	0.03	0.00	0.00
137+50.0 TO 137+75.0	0.00	0.08	0.07	0.07	0.07	0.00	0.00
137+75.0 TO 138+00.0	0.00	0.25	0.22	0.22	0.22	0.00	0.00
138+00.0 TO 138+25.0	0.01	0.79	0.71	0.71	0.71	0.01	0.02
138+25.0 TO 138+50.0	0.02	1.99	1.79	1.79	1.79	0.02	0.04
138+50.0 TO 138+57.0	0.01	0.54	0.49	0.49	0.49	0.01	0.01
139+71.0 TO 139+75.0	0.00	0.13	0.12	0.12	0.12	0.00	0.00
139+75.0 TO 140+00.0	0.01	0.68	0.61	0.61	0.61	0.01	0.01
140+00.0 TO 140+25.0	0.01	0.74	0.67	0.67	0.67	0.01	0.01
140+25.0 TO 140+50.0	0.01	0.59	0.53	0.53	0.53	0.01	0.01
140+50.0 TO 140+75.0	0.00	0.47	0.42	0.42	0.42	0.00	0.01
140+75.0 TO 141+00.0	0.00	0.39	0.35	0.35	0.35	0.00	0.01
141+00.0 TO 141+25.0	0.00	0.33	0.30	0.30	0.30	0.00	0.01
141+25.0 TO 141+50.0	0.00	0.25	0.22	0.22	0.22	0.00	0.00
141+50.0 TO 141+75.0	0.00	0.29	0.26	0.26	0.26	0.00	0.01
141+75.0 TO 142+00.0	0.00	0.36	0.33	0.33	0.33	0.00	0.01
142+00.0 TO 142+25.0	0.00	0.25	0.23	0.23	0.23	0.00	0.01
142+25.0 TO 142+50.0	0.00	0.07	0.06	0.06	0.06	0.00	0.00
142+50.0 TO 0+00.0	0.00	0.00	0.00	0.00	0.00	0.00	0.00
TOTALS	0.10	27.00	8.00	8.00	8.00	0.10	0.20

* FOR INFORMATION ONLY: NOT A PAY ITEM

EARTHWORK SCHEDULE	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%)	EARTH FILL	EARTHWORK BALANCE, WASTE (+) OR SHORTAGE (-)
	CU YD	CU YD	CU YD	CU YD
STATION TO STATION				
137+50.00 TO 137+75.00	0.0	0.0	0.1	-0.1
137+75.00 TO 138+00.00	0.0	0.0	0.6	-0.6
138+00.00 TO 138+25.00	0.0	0.0	3.1	-3.1
138+25.00 TO 138+50.00	0.0	0.0	16.1	-16.1
138+50.00 TO 138+67.00	0.0	0.0	18.4	-18.4
BRIDGE	763.0	572.3	0.0	+572.3
139+61.00 TO 139+75.0	0.0	0.0	2.5	-2.5
139+75.00 TO 140+00.0	0.0	0.0	4.5	-4.5
140+00.00 TO 140+25.0	0.0	0.0	3.8	-3.8
140+25.00 TO 140+50.0	0.0	0.0	2.7	-2.7
140+50.00 TO 140+75.0	0.0	0.0	1.8	-1.8
140+75.00 TO 141+00.0	0.0	0.0	1.1	-1.1
141+00.00 TO 141+25.0	0.0	0.0	0.8	-0.8
141+25.00 TO 141+50.0	0.0	0.0	0.6	-0.6
141+50.00 TO 141+75.0	0.0	0.0	0.4	-0.4
141+75.00 TO 142+00.0	0.0	0.0	0.4	-0.4
142+00.00 TO 142+25.0	0.0	0.0	0.3	-0.3
142+25.00 TO 142+50.0	0.0	0.0	0.1	-0.1
TOTALS	763.0	572.0	57.0	+515.0