

SHOULDER SCHEDULE (Cont'd)	LENGTH	PROPOSED SHOULDER WIDTH	PAVED SHOULDER REMOVAL	EXCAVATING AND GRADING SHOULDER	HOT-MIX ASPHALT SHOULDERS, 8"	SHOULDER RUMBLE STRIPS
	FOOT	FOOT	SQ YD	UNIT	SQ YD	FOOT
482+48 TO 484+00	152.0	2.5	0.0	1.5	42.2	152.0
484+00 TO 485+75	175.0	2.5	0.0	1.0	27.8	100.0
485+75 TO 492+80	705.0	4.0	117.5	7.1	313.3	705.0
492+80 TO 494+76	196.0	2.5	0.0	2.0	54.4	196.0
494+76 TO 495+21	45.0	4.0	7.5	0.5	20.0	45.0
495+21 TO 507+27	1206.0	2.5	0.0	11.7	325.6	1172.0
507+27 TO 508+10	83.0	4.0	13.8	0.8	36.9	83.0
508+10 TO 511+25	315.0	2.5	0.0	3.2	87.5	315.0
511+25 TO 512+30	105.0	4.0	17.5	0.7	31.6	71.0
512+30 TO 516+75	445.0	2.5	0.0	4.5	123.6	445.0
516+75 TO 518+00	125.0	4.0	20.8	1.3	55.6	125.0
518+00 TO 526+68	868.0	2.5	0.0	8.7	241.1	868.0
526+68 TO 526+95	27.0	4.0	4.5	0.3	12.0	27.0
526+95 TO 530+00	305.0	2.5	0.0	3.1	84.7	305.0
530+00 TO 530+60	60.0	4.0	10.0	0.6	26.7	60.0
WESTBOUND						
163+53 TO 190+36	2683.0	3.5	0.0	25.4	1043.4	2537.0
190+36 TO 191+23	87.0	5.0	14.5	0.9	48.3	87.0
191+23 TO 192+64	141.0	3.5	0.0	1.4	54.8	141.0
192+64 TO 194+75	211.0	5.0	35.2	2.1	117.2	211.0
194+75 TO 195+70	95.0	3.5	0.0	1.0	36.9	95.0
195+70 TO 196+97	127.0	5.0	21.2	1.3	70.6	127.0
196+97 TO 210+50	1353.0	3.5	0.0	13.5	526.2	1353.0
210+50 TO 216+87	637.0	5.0	0.0	6.4	0.0	637.0
216+87 TO 225+70	883.0	5.0	0.0	8.8	0.0	883.0
225+70 TO 225+97	27.0	3.5	0.0	0.3	10.5	27.0
225+97 TO 228+60	263.0	5.0	43.8	2.6	146.1	263.0
228+60 TO 231+45	285.0	3.5	0.0	2.2	110.8	218.0
231+45 TO 243+70	1225.0	5.0	0.0	12.3	0.0	1225.0
243+70 TO 259+50	1580.0	3.5	0.0	13.3	614.4	1332.0
259+50 TO 267+00	750.0	5.0	0.0	7.5	0.0	750.0
267+00 TO 267+50	50.0	4.0	8.3	0.5	22.2	50.0
267+50 TO 269+83	233.0	2.5	0.0	2.3	64.7	233.0
269+83 TO 270+60	77.0	4.0	12.8	0.8	34.2	77.0

SHOULDER SCHEDULE (Cont'd)	LENGTH	PROPOSED SHOULDER WIDTH	PAVED SHOULDER REMOVAL	EXCAVATING AND GRADING SHOULDER	HOT-MIX ASPHALT SHOULDERS, 8"	SHOULDER RUMBLE STRIPS
	FOOT	FOOT	SQ YD	UNIT	SQ YD	FOOT
270+60 TO 273+35	275.0	2.5	0.0	2.0	76.4	204.0
273+35 TO 275+16	181.0	4.0	30.2	1.6	80.4	159.0
275+16 TO 275+62	46.0	2.5	0.0	0.3	12.8	25.0
275+62 TO 277+92	230.0	4.0	38.3	1.9	102.2	188.0
277+92 TO 278+36	44.0	2.5	0.0	0.4	12.2	44.0
278+36 TO 279+77	141.0	4.0	23.5	1.4	62.7	141.0
279+77 TO 280+95	118.0	2.5	0.0	1.2	32.8	118.0
280+95 TO 284+19	324.0	4.0	54.0	3.2	144.0	324.0
284+19 TO 288+61	442.0	2.5	0.0	4.0	122.8	401.0
288+61 TO 289+65	104.0	4.0	17.3	1.0	46.2	104.0
289+65 TO 294+58	493.0	2.5	0.0	4.9	136.9	493.0
294+58 TO 296+89	231.0	4.0	38.5	2.3	102.7	231.0
296+89 TO 310+66	1377.0	2.5	0.0	12.7	382.5	1270.0
310+66 TO 313+70	304.0	4.0	50.7	3.0	135.1	304.0
313+70 TO 315+56	186.0	2.5	0.0	0.8	51.7	79.0
315+56 TO 317+42	186.0	4.0	31.0	1.9	82.7	186.0
317+42 TO 320+04	262.0	2.5	0.0	2.6	72.8	262.0
320+04 TO 322+90	286.0	4.0	47.7	2.9	127.1	286.0
322+90 TO 324+74	184.0	2.5	0.0	0.4	51.1	43.0
324+74 TO 325+19	45.0	4.0	7.5	0.5	20.0	45.0
325+19 TO 327+95	276.0	2.5	0.0	2.1	76.7	210.0
327+95 TO 328+67	72.0	4.0	12.0	0.7	32.0	72.0
328+67 TO 332+28	361.0	2.5	0.0	2.4	100.3	237.0
332+28 TO 333+51	123.0	4.0	20.5	1.2	54.7	123.0
333+51 TO 335+52	201.0	2.5	0.0	1.3	55.8	130.0
335+52 TO 337+05	153.0	4.0	25.5	1.5	68.0	153.0
337+05 TO 339+01	196.4	2.5	0.0	1.3	54.5	125.4
339+01 BK= 339+00AH	0.0	0.0	0.0	0.0	0.0	0.0
339+00 TO 342+75	375.0	2.5	0.0	3.8	104.2	375.0
342+75 TO 343+85	110.0	4.0	18.3	1.1	48.9	110.0
343+85 TO 347+87	402.0	2.5	0.0	3.4	111.7	342.0
347+87 TO 348+60	73.0	4.0	12.2	0.7	32.4	73.0
348+60 TO 349+14	53.9	2.5	0.0	0.5	15.0	53.9
349+14 TO 349+46	32.3	0.0	0.0	0.0	0.0	0.0

FILE NAME =
c:\pwwork\pwwork\swartzr\0196168\d774

USER NAME = swartzr
22-sh-t-schedule.dgn
PLOT SCALE = 50.0000' / in.
PLOT DATE = 8/16/2011

DESIGNED -
DRAWN -
CHECKED -
DATE -

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: NA SHEET NO. 4 OF 5 SHEETS STA. TO STA.

F.A.P. RTE. SECTION COUNTY TOTAL SHEETS SHEET NO.
741 (11,12)T * 85 13
CONTRACT NO. 74422
ILLINOIS FED. AID PROJECT

• MACON & PIATT