



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

November 9, 2011

SUBJECT: Various Routes
Section 82-1-3 HB, 82-2N, 82-1-12RS
St. Clair County
Contract No. 76C51
Item No. 107, November 18, 2011 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Replaced the Schedule of Prices.
2. Revised sheets 3, 9, 212, 214, 215, 220 and 221 of the Plans.
3. Deleted sheets 179 - 197 of the Plans.
4. Revised page i of the Table of Contents to the Special Provisions.
5. Revised pages 7, 8, 9, 26 and 27 of the Special Provisions/

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Scott E. Stitt, P.E.
Acting Engineer of Design and Environment

A handwritten signature in cursive script, appearing to read 'Ted B. Walschleger', followed by a small 'P.E.' to the right.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Omer M. Osman, Region 5, District 8; Mike Renner; D.Carl Puzey;
Estimates

TBW:DB:jc

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 76C51

State Job # - C-98-029-10
 PPS NBR - 8-90000-0325
 County Name - ST CLAIR - -
 Code - 163 - -
 District - 8 - -
 Section Number - 82-1-3HB, 82-2N, 82-1-12RS

Project Number

Route

VARIOUS

*REVISED: NOVEMBER 08, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X0322054	REM PRC FL END SEC	EACH	6.000				
X0322400	PILE EXTRACTION	EACH	62.000				
X0322628	FILL EXIST PIEZOMETER	EACH	4.000				
X0324345	COMB SEW REM 24	FOOT	1,128.000				
X0324733	COMB SEW REM 30	FOOT	40.000				
X0325155	REM ABANDON GAS MAIN	FOOT	836.000				
X0326694	PLUG EX STORM SEWERS	CU YD	7.600				
X0326808	INTERST WKEND CLSR SP	L SUM	1.000				
X0326931	RECORDER WELL	EACH	1.000				
X0327235	LOC UNDERGR UTILITIES	FOOT	100.000				
X0327269	COMB SEW REM 18	FOOT	280.000				
X0327346	COMB SEWER CL A T2 8	FOOT	37.000				
X0327347	COMB SEW REM 6	FOOT	189.000				
X0327348	COMB SEW REM 10	FOOT	384.000				
X2010505	CLEARING SPECIAL	L SUM	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 76C51

State Job # - C-98-029-10
 PPS NBR - 8-90000-0325
 County Name - ST CLAIR - -
 Code - 163 - -
 District - 8 - -
 Section Number - 82-1-3HB, 82-2N, 82-1-12RS

Project Number

Route

VARIOUS

*REVISED: NOVEMBER 08, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X2020502	BRACED EXCAVATION	CU YD	125.000				
X2070304	POROUS GRAN EMB SPEC	CU YD	313.000				
X4200501	PCC PVT 10 JOINTD SPL	SQ YD	807.000				
X4403800	MEDIAN SURF REMOVAL	SQ FT	4,693.000				
X5011100	FOUNDATION REM	EACH	3.000				
X5080600	MECHANICAL SPLICERS	EACH	28.000				
X5210200	HLMR BRG GUID EXP 650	EACH	6.000				
X5610700	WATER MAIN REMOVAL	FOOT	24.000				
X6022810	MAN SAN 4 DIA T1F CL	EACH	1.000				
X6022820	MAN SAN 5 DIA T1F CL	EACH	4.000				
X6022830	MAN SAN 6 DIA T1F CL	EACH	1.000				
X6022840	MAN SAN 7 DIA T1F CL	EACH	1.000				
X6026054	SAN MAN REMOVED	EACH	12.000				
X6065750	CONC MED SURF 6 SPL	SQ FT	5,033.000				
X6065770	CONC MED SURF 10 SPL	SQ FT	1,218.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 76C51

State Job # - C-98-029-10
 PPS NBR - 8-90000-0325
 County Name - ST CLAIR- -
 Code - 163 - -
 District - 8 - -
 Section Number - 82-1-3HB, 82-2N, 82-1-12RS

Project Number

Route

VARIOUS

*REVISED: NOVEMBER 08, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X6370015	CONC BARRIER SP 32	FOOT	159.000				
X6370700	CONC BAR TRANS SPL	FOOT	56.000				
X7010216	TRAF CONT & PROT SPL	L SUM	1.000				
X7040600	FUR TEMP CONC BARRIER	FOOT	50.000				
*DELETE X7200305	SIGN PANEL T3 SPL	SQ FT	488.000				
X7800200	PAINT PVT MARK CURB	FOOT	1,343.000				
X7830068	GRV RCSD PVT LT N SYM	SQ FT	165.000				
X7830070	GRV RCSD PVT MRKG 5	FOOT	11,617.000				
X7830074	GRV RCSD PVT MRKG 7	FOOT	164.000				
X7830076	GRV RCSD PVT MRKG 9	FOOT	524.000				
X7830078	GRV RCSD PVT MRKG 13	FOOT	1,015.000				
Z0001600	APPROACH SLAB REPAIR	SQ YD	73.000				
Z0001850	ARC PREC CON PANEL	EACH	10.000				
Z0001899	JACK & REM EX BEARING	EACH	13.000				
Z0004556	HMA SURFACE RM (DECK)	SQ YD	1,552.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 76C51

State Job # - C-98-029-10
 PPS NBR - 8-90000-0325
 County Name - ST CLAIR- -
 Code - 163 - -
 District - 8 - -
 Section Number - 82-1-3HB, 82-2N, 82-1-12RS

Project Number

Route

VARIOUS

*REVISED: NOVEMBER 08, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
Z0012754	STR REP CON DP = < 5	SQ FT	599.000				
Z0012755	STR REP CON DP OVER 5	SQ FT	10.000				
Z0013798	CONSTRUCTION LAYOUT	L SUM	1.000				
Z0016200	DECK SLAB REP (PART)	SQ YD	408.000				
Z0022800	FENCE REMOVAL	FOOT	5,671.000				
Z0024110	FILL DEEP WELL	EACH	4.000				
Z0024112	WELL CONT CENTER MOD	L SUM	1.000				
Z0024120	FILL RECORDER WELL	EACH	1.000				
Z0030260	IMP ATTN TEMP FRN TL3	EACH	9.000				
Z0030330	IMP ATTN REL FRD TL3	EACH	4.000				
Z0046304	P UNDR FOR STRUCT 4	FOOT	194.000				
Z0048665	RR PROT LIABILITY INS	L SUM	1.000				
Z0062456	TEMP PAVEMENT	SQ YD	36.000				
Z0076602	TRAINEES SPL	HOUR	4,000.000		3.500		14,000.000
Z0076604	TRAINEES TPG	HOUR	4,000.000		10.000		40,000.000

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 76C51

State Job # - C-98-029-10
 PPS NBR - 8-90000-0325
 County Name - ST CLAIR - -
 Code - 163 - -
 District - 8 - -
 Section Number - 82-1-3HB, 82-2N, 82-1-12RS

Project Number

Route

VARIOUS

*REVISED: NOVEMBER 08, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
20100110	TREE REMOV 6-15	UNIT	132.000				
20100500	TREE REMOV ACRES	ACRE	0.500				
20200100	EARTH EXCAVATION	CU YD	42,850.000				
20800150	TRENCH BACKFILL	CU YD	1,925.000				
25000115	SEEDING CL 1B	ACRE	6.250				
25000400	NITROGEN FERT NUTR	POUND	551.000				
25000500	PHOSPHORUS FERT NUTR	POUND	551.000				
25000600	POTASSIUM FERT NUTR	POUND	551.000				
25100115	MULCH METHOD 2	ACRE	10.750				
28000250	TEMP EROS CONTR SEED	POUND	2,684.000				
28000305	TEMP DITCH CHECKS	FOOT	24.000				
28000400	PERIMETER EROS BAR	FOOT	12,335.000				
28000500	INLET & PIPE PROTECT	EACH	60.000				
28100107	STONE RIPRAP CL A4	SQ YD	164.000				
28200200	FILTER FABRIC	SQ YD	164.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 76C51

State Job # - C-98-029-10
 PPS NBR - 8-90000-0325
 County Name - ST CLAIR- -
 Code - 163 - -
 District - 8 - -
 Section Number - 82-1-3HB, 82-2N, 82-1-12RS

Project Number

Route

VARIOUS

*REVISED: NOVEMBER 08, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
35100700	AGG BASE CSE A 8	SQ YD	2,271.000				
35101100	AGG BASE CSE A 12	SQ YD	19,978.000				
35300500	PCC BSE CSE 10	SQ YD	2,262.000				
35300600	PCC BSE CSE 11	SQ YD	1,369.000				
40201000	AGGREGATE-TEMP ACCESS	TON	100.000				
40600200	BIT MATLS PR CT	TON	11.900				
40600300	AGG PR CT	TON	56.900				
40600982	HMA SURF REM BUTT JT	SQ YD	369.000				
40600985	PCC SURF REM BUTT JT	SQ YD	545.000				
40600990	TEMPORARY RAMP	SQ YD	256.000				
40603085	HMA BC IL-19.0 N70	TON	1,477.000				
40603340	HMA SC "D" N70	TON	2,366.000				
42000501	PCC PVT 10 JOINTED	SQ YD	9,137.000				
42001300	PROTECTIVE COAT	SQ YD	13,045.000				
42300400	PCC DRIVEWAY PAVT 8	SQ YD	155.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 76C51

State Job # - C-98-029-10
 PPS NBR - 8-90000-0325
 County Name - ST CLAIR - -
 Code - 163 - -
 District - 8 - -
 Section Number - 82-1-3HB, 82-2N, 82-1-12RS

Project Number

Route

VARIOUS

*REVISED: NOVEMBER 08, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
42400100	PC CONC SIDEWALK 4	SQ FT	28,401.000				
42400410	PC CONC SIDEWALK 8	SQ FT	339.000				
42400800	DETECTABLE WARNINGS	SQ FT	578.000				
44000100	PAVEMENT REM	SQ YD	23,156.000				
44000154	HMA SURF REM 1 1/4	SQ YD	2,703.000				
44000155	HMA SURF REM 1 1/2	SQ YD	7,379.000				
44000158	HMA SURF REM 2 1/4	SQ YD	395.000				
44000200	DRIVE PAVEMENT REM	SQ YD	577.000				
44000300	CURB REM	FOOT	2,704.000				
44000400	GUTTER REM	FOOT	440.000				
44000500	COMB CURB GUTTER REM	FOOT	9,472.000				
44000600	SIDEWALK REM	SQ FT	45,179.000				
44001980	CONC BARRIER REMOV	FOOT	151.000				
44003510	MEDIAN REMOVAL (PD)	SQ FT	777.000				
44004250	PAVED SHLD REMOVAL	SQ YD	1,963.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 76C51

State Job # - C-98-029-10
 PPS NBR - 8-90000-0325
 County Name - ST CLAIR - -
 Code - 163 - -
 District - 8 - -
 Section Number - 82-1-3HB, 82-2N, 82-1-12RS

Project Number

Route

VARIOUS

*REVISED: NOVEMBER 08, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
44201341	CL C PATCH T2 9	SQ YD	74.000				
44201347	CL C PATCH T4 9	SQ YD	765.000				
44201349	CL C PATCH T1 10	SQ YD	48.000				
44201353	CL C PATCH T2 10	SQ YD	156.000				
44201357	CL C PATCH T3 10	SQ YD	500.000				
44201359	CL C PATCH T4 10	SQ YD	336.000				
44300100	AREA REF CR CON TREAT	SQ YD	160.000				
45200100	JT CR RT PCC PAV/SHLD	FOOT	10,250.000				
45200300	JT OR CRACK FILLING	POUND	2,975.000				
48100100	AGGREGATE SHLDS A	TON	243.000				
48100500	AGGREGATE SHLDS A 6	SQ YD	308.000				
48101200	AGGREGATE SHLDS B	TON	163.000				
48300500	PCC SHOULDERS 10	SQ YD	559.000				
48300700	PCC SHOULDERS 12	SQ YD	1,059.000				
50100300	REM EXIST STRUCT N1	EACH	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 76C51

State Job # - C-98-029-10
 PPS NBR - 8-90000-0325
 County Name - ST CLAIR - -
 Code - 163 - -
 District - 8 - -
 Section Number - 82-1-3HB, 82-2N, 82-1-12RS

Project Number

Route

VARIOUS

*REVISED: NOVEMBER 08, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
50100400	REM EXIST STRUCT N2	EACH	1.000				
50102400	CONC REM	CU YD	155.000				
50105220	PIPE CULVERT REMOV	FOOT	245.000				
50157300	PROTECTIVE SHIELD	SQ YD	1,801.000				
50200100	STRUCTURE EXCAVATION	CU YD	563.000				
50300225	CONC STRUCT	CU YD	249.500				
50300255	CONC SUP-STR	CU YD	1,027.800				
50300260	BR DECK GROOVING	SQ YD	1,304.000				
50300280	CONCRETE ENCASEMENT	CU YD	17.400				
50300300	PROTECTIVE COAT	SQ YD	3,056.000				
50500105	F & E STRUCT STEEL	L SUM	1.000				
50500405	F & E STRUCT STEEL	POUND	10,740.000				
50500505	STUD SHEAR CONNECTORS	EACH	5,040.000				
50800205	REINF BARS, EPOXY CTD	POUND	317,030.000				
50800515	BAR SPLICERS	EACH	118.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 76C51

State Job # - C-98-029-10
 PPS NBR - 8-90000-0325
 County Name - ST CLAIR - -
 Code - 163 - -
 District - 8 - -
 Section Number - 82-1-3HB, 82-2N, 82-1-12RS

Project Number

Route

VARIOUS

*REVISED: NOVEMBER 08, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
50901050	STEEL RAILING TY SM	FOOT	341.000				
50901730	BRIDGE FENCE RAILING	FOOT	577.200				
50901735	BR FEN RAIL (SDWALK)	FOOT	694.400				
50901750	PARAPET RAILING	FOOT	353.400				
51100100	SLOPE WALL 4	SQ YD	599.000				
51201800	FUR STL PILE HP14X73	FOOT	3,627.000				
51201900	FUR STL PILE HP14X89	FOOT	2,565.000				
51202305	DRIVING PILES	FOOT	6,192.000				
51203900	TEST PILE ST HP14X89	EACH	1.000				
51204650	PILE SHOES	EACH	71.000				
51500100	NAME PLATES	EACH	1.000				
52000110	PREF JT STRIP SEAL	FOOT	239.000				
52100010	ELAST BEARING ASSY T1	EACH	13.000				
52100520	ANCHOR BOLTS 1	EACH	24.000				
52100530	ANCHOR BOLTS 1 1/4	EACH	50.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 76C51

State Job # - C-98-029-10
 PPS NBR - 8-90000-0325
 County Name - ST CLAIR - -
 Code - 163 - -
 District - 8 - -
 Section Number - 82-1-3HB, 82-2N, 82-1-12RS

Project Number

Route

VARIOUS

*REVISED: NOVEMBER 08, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
542A0217	P CUL CL A 1 12	FOOT	245.000				
54213657	PRC FLAR END SEC 12	EACH	6.000				
54213660	PRC FLAR END SEC 15	EACH	1.000				
550A0050	STORM SEW CL A 1 12	FOOT	100.000				
550A0340	STORM SEW CL A 2 12	FOOT	1,635.000				
550A0360	STORM SEW CL A 2 15	FOOT	215.000				
550A0380	STORM SEW CL A 2 18	FOOT	250.000				
550A0400	STORM SEW CL A 2 21	FOOT	191.000				
550A0410	STORM SEW CL A 2 24	FOOT	31.000				
55100400	STORM SEWER REM 10	FOOT	30.000				
55100500	STORM SEWER REM 12	FOOT	912.000				
55100700	STORM SEWER REM 15	FOOT	35.000				
55100900	STORM SEWER REM 18	FOOT	12.000				
55101200	STORM SEWER REM 24	FOOT	68.000				
58100200	WATERPRF MEMBRANE SYS	SQ YD	1,649.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 76C51

State Job # - C-98-029-10
 PPS NBR - 8-90000-0325
 County Name - ST CLAIR - -
 Code - 163 - -
 District - 8 - -
 Section Number - 82-1-3HB, 82-2N, 82-1-12RS

Project Number

Route

VARIOUS

*REVISED: NOVEMBER 08, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
58700300	CONCRETE SEALER	SQ FT	10,739.000				
59000200	EPOXY CRACK INJECTION	FOOT	52.000				
59100100	GEOCOMPOSITE WALL DR	SQ YD	134.000				
60107700	PIPE UNDERDRAINS 6	FOOT	581.000				
60108200	PIPE UNDERDRAIN 6 SP	FOOT	61.000				
60200305	CB TA 4 DIA T3F&G	EACH	4.000				
60201310	CB TA 4 DIA T20F&G	EACH	1.000				
60201340	CB TA 4 DIA T24F&G	EACH	21.000				
60204005	CB TA 5 DIA T3F&G	EACH	1.000				
60205010	CB TA 5 DIA T20F&G	EACH	1.000				
60218400	MAN TA 4 DIA T1F CL	EACH	6.000				
60221100	MAN TA 5 DIA T1F CL	EACH	4.000				
60221700	MAN TA 5 DIA T8G	EACH	1.000				
60237470	INLETS TA T24F&G	EACH	18.000				
60240220	INLETS TB T3F&G	EACH	3.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 76C51

State Job # - C-98-029-10
 PPS NBR - 8-90000-0325
 County Name - ST CLAIR - -
 Code - 163 - -
 District - 8 - -
 Section Number - 82-1-3HB, 82-2N, 82-1-12RS

Project Number

Route

VARIOUS

*REVISED: NOVEMBER 08, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
60240324	INLETS TB T20F&G	EACH	1.000				
60250200	CB ADJUST	EACH	3.000				
60250500	CB ADJ NEW T1F CL	EACH	3.000				
60253100	CB RECON NEW T1F CL	EACH	1.000				
60255500	MAN ADJUST	EACH	8.000				
60255800	MAN ADJ NEW T1F CL	EACH	13.000				
60257900	MAN RECONST	EACH	1.000				
60260100	INLETS ADJUST	EACH	5.000				
60260400	INLETS ADJ NEW T1F CL	EACH	2.000				
60261000	INLETS ADJ NEW T8G	EACH	1.000				
60264140	INL RECON NEW T24F&G	EACH	2.000				
60500040	REMOV MANHOLES	EACH	1.000				
60500050	REMOV CATCH BAS	EACH	6.000				
60500060	REMOV INLETS	EACH	24.000				
60500105	FILL MANHOLES	EACH	5.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 76C51

State Job # - C-98-029-10
 PPS NBR - 8-90000-0325
 County Name - ST CLAIR - -
 Code - 163 - -
 District - 8 - -
 Section Number - 82-1-3HB, 82-2N, 82-1-12RS

Project Number

Route

VARIOUS

*REVISED: NOVEMBER 08, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
60600095	CLASS SI CONC OUTLET	CU YD	2.000				
60602800	CONC GUTTER TB	FOOT	388.000				
60603800	COMB CC&G TB6.12	FOOT	1,102.500				
60605000	COMB CC&G TB6.24	FOOT	8,566.500				
60607400	COMB CC&G TB9.24	FOOT	358.000				
60608300	COMB CC&G TM2.12	FOOT	553.000				
60608521	COMB CC&G TM2.24	FOOT	283.000				
60608600	COMB CC&G TM6.06	FOOT	96.000				
60618300	CONC MEDIAN SURF 4	SQ FT	1,888.000				
63000001	SPBGR TY A 6FT POSTS	FOOT	300.000				
63100045	TRAF BAR TERM T2	EACH	2.000				
63100070	TRAF BAR TERM T5	EACH	1.000				
63100089	TRAF BAR TERM T6B	EACH	1.000				
63100167	TR BAR TRM T1 SPL TAN	EACH	2.000				
63200310	GUARDRAIL REMOV	FOOT	1,364.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 76C51

State Job # - C-98-029-10
 PPS NBR - 8-90000-0325
 County Name - ST CLAIR - -
 Code - 163 - -
 District - 8 - -
 Section Number - 82-1-3HB, 82-2N, 82-1-12RS

Project Number

Route

VARIOUS

*REVISED: NOVEMBER 08, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
63700805	CONC BAR TRANS	FOOT	10.000				
63700900	CONC BARRIER BASE	FOOT	169.000				
64200105	SHOULDER RUMBLE STRIP	FOOT	877.000				
66400305	CH LK FENCE 6	FOOT	4,381.000				
66407600	CH LK GATES 6X12 DBL	EACH	3.000				
66900200	NON SPL WASTE DISPOSL	CU YD	280.000				
66900450	SPL WASTE PLNS/REPORT	L SUM	1.000				
66900530	SOIL DISPOSAL ANALY	EACH	4.000				
67100100	MOBILIZATION	L SUM	1.000				
70103815	TR CONT SURVEILLANCE	CAL DA	160.000				
70300220	TEMP PVT MK LINE 4	FOOT	36,040.000				
70301000	WORK ZONE PAVT MK REM	SQ FT	12,213.000				
70400100	TEMP CONC BARRIER	FOOT	4,176.000				
70400200	REL TEMP CONC BARRIER	FOOT	491.000				
72000100	SIGN PANEL T1	SQ FT	704.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 76C51

State Job # - C-98-029-10
 PPS NBR - 8-90000-0325
 County Name - ST CLAIR - -
 Code - 163 - -
 District - 8 - -
 Section Number - 82-1-3HB, 82-2N, 82-1-12RS

Project Number

Route

VARIOUS

*REVISED: NOVEMBER 08, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
72400100	REMOV SIN PAN ASSY TA	EACH	28.000				
72400200	REMOV SIN PAN ASSY TB	EACH	21.000				
72400310	REMOV SIGN PANEL T1	SQ FT	33.000				
72400710	RELOC SIGN PANEL T1	SQ FT	21.000				
72400720	RELOC SIGN PANEL T2	SQ FT	153.000				
72800100	TELES STL SIN SUPPORT	FOOT	597.000				
73000100	WOOD SIN SUPPORT	FOOT	877.000				
73100100	BASE TEL STL SIN SUPP	EACH	25.000				
73600100	REMOV OH SIN STR-SPAN	EACH	2.000				
73700300	REM CONC FDN-OVHD	EACH	4.000				
78000200	THPL PVT MK LINE 4	FOOT	5,818.000				
78000500	THPL PVT MK LINE 8	FOOT	2,088.000				
78000600	THPL PVT MK LINE 12	FOOT	403.000				
78003100	PREF PL PM TB LTR-SYM	SQ FT	165.000				
78003110	PREF PL PM TB LINE 4	FOOT	11,617.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 76C51

State Job # - C-98-029-10
 PPS NBR - 8-90000-0325
 County Name - ST CLAIR - -
 Code - 163 - -
 District - 8 - -
 Section Number - 82-1-3HB, 82-2N, 82-1-12RS

Project Number

Route

VARIOUS

*REVISED: NOVEMBER 08, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
78003130	PREF PL PM TB LINE 6	FOOT	164.000				
78003140	PREF PL PM TB LINE 8	FOOT	524.000				
78003150	PREF PL PM TB LINE 12	FOOT	1,015.000				
78004200	PREF PL PM TB INL L&S	SQ FT	176.000				
78004210	PREF PL PM TB INL L4	FOOT	20,015.000				
78004230	PREF PL PM TB INL L6	FOOT	1,803.000				
78004250	PREF PL PM TB INL L12	FOOT	1,633.000				
78004280	PREF PL PM TB INL L24	FOOT	88.000				
78100100	RAISED REFL PAVT MKR	EACH	336.000				
78200300	PRISMATIC CURB REFL	EACH	201.000				
78200410	GUARDRAIL MKR TYPE A	EACH	14.000				
78200530	BAR WALL MKR TYPE C	EACH	24.000				
78201000	TERMINAL MARKER - DA	EACH	2.000				
78300100	PAVT MARKING REMOVAL	SQ FT	5,325.000				
78300200	RAISED REF PVT MK REM	EACH	104.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 76C51

State Job # - C-98-029-10
 PPS NBR - 8-90000-0325
 County Name - ST CLAIR - -
 Code - 163 - -
 District - 8 - -
 Section Number - 82-1-3HB, 82-2N, 82-1-12RS

Project Number

Route
 VARIOUS

*REVISED: NOVEMBER 08, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
80300100	LOCATE UNDERGR CABLE	FOOT	100.000				
81603035	UD 2#6 #6G XLPUSE 1	FOOT	130.000				
81900200	TR & BKFIL F ELECT WK	FOOT	100.000				
89502375	REMOV EX TS EQUIP	EACH	1.000				
89502380	REMOV EX HANDHOLE	EACH	4.000				
89502385	REMOV EX CONC FDN	EACH	6.000				

TABLE OF CONTENTS

LOCATION OF PROJECT	1
DESCRIPTION OF PROJECT	1
MONTHLY LABOR SUMMARY AND ACTIVITY REPORTING SYSTEM	1
EMBANKMENT	4
HOT-MIX ASPHALT SURFACE REMOVAL W/SKETCH OF ILLINOIS STANDARD W8-I106.....	4
TRAFFIC CONTROL PLAN.....	9
INSTALLATION OF TEMPORARY CONCRETE BARRIERS AND/OR TEMPORARY BRIDGE RAIL.....	10
TEMPERATURE CONTROL FOR CONCRETE PLACEMENT	11
CONSTRUCTION AND MAINTENANCE SIGN SUPPORTS	11
STATUS OF UTILITIES TO BE ADJUSTED	12
PROTECTION AND RESTORATION OF PROPERTY	12
ON-THE-JOB TRAINING SPECIAL PROVISIONS (NMRB).....	14
COMPLETION DATE (VIA CALENDAR DAYS) (BDE).....	18
RAILROAD PROTECTIVE LIABILITY INSURANCE (5 AND 10) (BDE).....	18
TEMPERATURE CONTROL FOR CONCRETE PLACEMENT	19
PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED) SPECIAL.....	19
TEMPORARY PAVEMENT.....	21
DRILL AND GROUT TIE BARS.....	21
CONCRETE BARRIER, SPECIAL, 32" HEIGHT.....	21
FURNISH TEMPORARY CONCRETE BARRIER.....	22
CONCRETE BARRIER TRANSITION (SPECIAL)	22
ARCHITECTURAL PRECAST CONCRETE PANEL.....	22
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES	25
FENCE REMOVAL	27
MEDIAN SURFACE REMOVAL	27
REMOVE EXISTING CONCRETE FOUNDATION.....	28
FOUNDATION REMOVAL.....	28
COMBINED SEWER REMOVAL.....	29
SANITARY MANHOLES TO BE REMOVED.....	29
REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT.....	30
REMOVE EXISTING HANDHOLE.....	31

Revised 11/9/2011

This page intentionally left blank.

Revised 11/9/2011

This page intentionally left blank.

Revised 11/9/2011

TRAFFIC CONTROL PLAN

Effective: July 12, 1993

Revised: May 12, 1997

Traffic control shall be in accordance with the applicable sections of the "Standard Specifications for Road and Bridge Construction", the applicable guidelines contained in the "National Manual on Uniform Traffic Control Devices for Streets and Highways", Illinois Supplement to the National Manual of Uniform Traffic Control Devices, these Special Provisions, and any special details and Highway Standards contained herein and in the plans.

Special attention is called to Articles 107.09 and 107.14 of the "Standard Specifications for Road and Bridge Construction and the following Highway Standards relating to traffic control:

701001 701011 701101 701106 701301 701311 701400 701401 701402 701406
701421 701426 701451 701456 701501 701502 701601
701701 701801 701901 704001

In addition, the following Special Provision(s) will also govern traffic control for this project:

Traffic Control and Protection (Special)
Contractor Cooperation
Impact Attenuators, Temporary
Work Zone Pavement Marking Removal
Temporary Pavement Marking
Temporary Concrete Barrier
Temporary Pavement
Temporary Ramp
Aggregate for Temporary Access
Maintenance of Roadways
Work During Peak Hours
Temporary Information Signing
Traffic Control Surveillance
Construction and Maintenance Sign Supports

Revised 11/9/2011

- B) The Environmental Firm shall continuously monitor for worker protection and the Contractor shall manage any excavated soils **within the construction limits of this project as fill**. Although the soil concentrations exceed a residential property's Tier 1 soil remediation objective for the ingestion exposure pathway, they can be utilized within the construction limits as fill because the roadway is not considered a residential property. All storm sewer excavated soils can be placed back into the excavated trench as backfill unless trench backfill is specified. If the soils cannot be utilized within the construction limits as fill then they must be managed off-site as a non-special waste. The following areas can be managed within the construction limits as fill.

Station 10+15 to Station 11+53 0 to 80 feet RT (Vacant Lot, Site 601V1-EU, 903 9th Street) – non-special waste. Contaminants of concern sampling parameters:
Lead.

Method of Measurement & Basis of Payment: REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES will be measured and paid for at the contract unit price as followed: NON-SPECIAL WASTE DISPOSAL per cubic yard, SPECIAL WASTE PLAN AND REPORTS per lump sum, and SOIL DISPOSAL ANALYSIS per each.

The balance of this page intentionally left blank.

Revised 11/9/2011

FENCE REMOVAL

Description. This work shall consist of removing and disposing the existing fence of all kinds as shown in the plans.

Construction Requirements: No removal work shall be completed without the approval of the Engineer. All associated hardware and appurtenances of the existing fence shall be removed off-site and disposed of by the Contractor in a legal disposal site. All postholes shall be backfilled and compacted to the satisfaction of the Engineer.

Method of Measurement: Fence removal shall be measured for payment per foot of FENCE REMOVAL and measured along the top of the fence from center to center of end post, including the length occupied by gates.

Basis of Payment: This work will be paid for at the contract unit price per foot for FENCE REMOVAL.

MEDIAN SURFACE REMOVAL

Description. This work shall consist of the removal of and satisfactory disposal of the existing median surface, approximately 4 inches thick, at locations shown on the plans and as directed by the Engineer.

Method of Measurement. This item of work will be measured for payment per square foot for removing the median surface as required in the plans, specifications and these Special Provisions.

Revised 11/9/2011