

SUMMARY OF QUANTITIES

URBAN

CODE NO.	ITEM	UNIT	TOTAL QUANTITIES	100% STATE FUNDED CONSTRUCTION TYPE CODE				
				ROADWAY 0004	9TH ST BRIDGE 0011	ST. CLAIR BRIDGE 0014	LANDSCAPING 0031	TRAINEES 0042
X5210200	HIGH LOAD MULTI-ROTATION BEARINGS, GUIDED EXPANSION, 650K	EACH	6		6			
X6022810	MANHOLES, SANITARY, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1				
X6022820	MANHOLES, SANITARY, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	4	4				
X6022830	MANHOLES, SANITARY, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1				
X6022840	MANHOLES, SANITARY, 7'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1				
X6026054	SANITARY MANHOLES TO BE REMOVED	EACH	12	12				
X6065750	CONCRETE MEDIAN SURFACE, 6 INCH (SPECIAL)	SQ FT	5,033	5,033				
X6370015	CONCRETE BARRIER, SPECIAL, 32" HEIGHT	FOOT	159	159				
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1				
X7040600	FURNISH TEMPORARY CONCRETE BARRIER	FOOT	50	50				
<del>X7800205</del>	<del>SIGN PANEL, TYPE 2 (SPECIAL)</del>	<del>SQ FT</del>	<del>180</del>	<del>180</del>				
* X7800200	PAINT PAVEMENT MARKING CURB	FOOT	1,343	1,343				
* X7830068	GROOVING FOR RECESSED PAVEMENT MARKING, LETTERS, NUMBERS AND SYMBOLS	SQ FT	165	165				
* X7830070	GROOVING FOR RECESSED PAVEMENT MARKING 5"	FOOT	11,617	11,617				
* X7830074	GROOVING FOR RECESSED PAVEMENT MARKING 7"	FOOT	164	164				
* X7830076	GROOVING FOR RECESSED PAVEMENT MARKING 9"	FOOT	524	524				
* X7830078	GROOVING FOR RECESSED PAVEMENT MARKING 13"	FOOT	1,015	1,015				
Z0001899	JACK AND REMOVE EXISTING BEARINGS	EACH	13		13			
Z0004556	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	1,552		1,552			
<del>Z0007801</del>	<del>BUILDING REMOVAL NO. 1</del>	<del>L SUM</del>	<del>1</del>	<del>1</del>				
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	599		599			
Z0012755	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SQ FT	10		10			
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1				
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	408		408			
Z0022800	FENCE REMOVAL	FOOT	5,671	5,671				
Z0024110	FILL DEEP WELL	EACH	4	4				
Z0024112	WELL CONTROL CENTER MODIFICATIONS	L SUM	1	1				
Z0024120	FILL RECORDER WELL	EACH	1	1				
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	9	9				
Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	4	4				
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	194		194			

SUMMARY OF QUANTITIES

URBAN

CODE NO.	ITEM	UNIT	TOTAL QUANTITIES	100% STATE FUNDED CONSTRUCTION TYPE CODE				
				ROADWAY 0004	9TH ST BRIDGE 0011	ST. CLAIR BRIDGE 0014	LANDSCAPING 0031	TRAINEES 0042
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1				
<del>Z0048665</del>	<del>REMOVAL AND DISPOSAL OF NON-RESIDENTIAL ADJUTANT, BUILDING NO. 1</del>	<del>L SUM</del>	<del>1</del>	<del>1</del>				
Z0062456	TEMPORARY PAVEMENT	SQ YD	36	36				
Z0076602	TRAINEES (SPECIAL)	HOUR	4,000					4,000
Z0076604	TRAINEES TPG	HOUR	4,000					4,000
X0327346	COMBINED SEWERS, CLASS A, TYPE 2, 8"	FOOT	37	37				
X0327347	COMBINED SEWER REMOVAL 6"	FOOT	189	189				
X0327348	COMBINED SEWER REMOVAL 10"	FOOT	384	384				
X0327349	COMBINED SEWER REMOVAL 18"	FOOT	280	280				
Z0001850	ARCHITECTURAL PRECAST CONCRETE PANEL	EACH	10	10				
<del>Z0003005</del>	<del>SHRUB, LEX DECIDUA (POCOONIAW) CONTAINER GROWN, 5-GALLON</del>	<del>EACH</del>	<del>15</del>					15
<del>Z0005385</del>	<del>TREE, METASEQUOIA GLYPTOSTROBILDES (DAWN REDWOOD) 2" CALIPER BALLED AND BURLAPPED</del>	<del>EACH</del>	<del>8</del>					8
<del>Z0006845</del>	<del>TREE, QUERUS PHELLOS (WILLOW OAK) 2" CALIPER, BALLED AND BURLAPPED</del>	<del>EACH</del>	<del>2</del>					2
<del>Z0007363</del>	<del>SHRUB, LINDERA BENZON (SPICEBUSH), CONTAINER GROWN, 3-GALLON</del>	<del>EACH</del>	<del>37</del>					37
X4200501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED) SPECIAL	SQ YD	807	807				
Z0001600	APPROACH SLAB REPAIR	SQ YD	73			73		
X6370700	CONCRETE BARRIER TRANSITION (SPECIAL)	FOOT	56	56				
X6065770	CONCRETE MEDIAN SURFACE, 10 INCH (SPECIAL)	SQ FT	1,218	1,218				
X5610700	WATER MAIN REMOVAL	FOOT	24	24				

\* SPECIALTY ITEM

REVISOR 10/31/2011

FILE NAME = DBTRI-76C51-sht-summary-01-04.dgn

USER NAME = pimsarno  
 DESIGNED KM  
 DRAWN BS  
 CHECKED DBM  
 DATE 08/18/2011  
 PLOT SCALE = 1.0000" = 1/4" IN.  
 PLOT DATE = 8/26/2011

REVISOR -  
 REVISOR -  
 REVISOR -  
 REVISOR -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 5 OF 5 SHEETS STA. ----- TO STA. -----

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	82-1-3HB, 82-2N, 82-1-12RS	ST. CLAIR	352	9
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT		CONTRACT NO. 76C51		