

STORM SEWER SCHEDULE

| I-64 MAINLINE | | | | | | | | STORM SEWER CLASS A TYPE 1 | STORM SEWER CLASS A TYPE 2 | STORM SEWER CLASS A TYPE 2 | STORM SEWER CLASS A TYPE 2 | STORM SEWER CLASS A TYPE 2 | STORM SEWER CLASS A TYPE 2 | COMBINED SEWER | |
|-------------------------------|------------------|------------------|--------------------|--------------------|-------------------|----------------|----------------------|----------------------------|----------------------------|----------------------------|----------------------------|----------------------------|----------------------------|----------------|-----------|
| PIPE NO | UP STREAM STR NO | UP STREAM INVERT | DOWN STREAM STR NO | DOWN STREAM INVERT | PIPE DIA (INCHES) | PIPE SLOPE (%) | TRENCH BACKFILL (CY) | 12" | 12" | 15" | 18" | 21" | 24" | 8" | |
| | | | | | | | | FOOT | FOOT | FOOT | FOOT | FOOT | FOOT | FOOT | |
| P-60 | S-60 | 394.38 | S-60A (EX) | 393.67 | 15 | 1.00 | 73.8 | | | 71 | | | | | |
| P-61 | S-61 (EX) | 392.33 | S-62 (EX) | 391.84 | 12 | 0.50 | 21.5 | | 98 | | | | | | |
| P-62 | S-62 (EX) | 391.84 | S-62A (EX) | 391.34 | 12 | 0.50 | 15.6 | 100 | | | | | | | |
| P-63 | S-63 | 390.65 | S-64 | 390.63 | 24 | 0.25 | 4.9 | | | | | | 8 | | |
| P-64 | S-64 | 390.63 | S-65 (EX) | 390.56 | 24 | 0.30 | 12.9 | | | | | | 23 | | |
| I-64 MAINLINE SUBTOTALS | | | | | | | | 128.7 | 100 | 98 | 71 | 0 | 0 | 31 | 0 |
| ST. CLAIR AVENUE | | | | | | | | | | | | | | | |
| P 7-01 | S 7-01 | 410.38 | EX STRUC | 410.06 | 12 | 4.00 | 2.5 | | 8 | | | | | | |
| P 8-01 | S 8-01 | 411.22 | EX STRUC | 409.66 | 12 | 4.00 | 8.4 | | 39 | | | | | | |
| P 8-02 | S 8-02 | 408.50 | EX STRUC | 408.43 | 12 | 1.00 | 3.0 | | 7 | | | | | | |
| P 8-03 | S 8-03 | 410.67 | EX STRUC | 410.62 | 12 | 1.00 | 1.5 | | 5 | | | | | | |
| P 9-04 | S 9-04 | 408.33 | EX STRUC | 407.61 | 12 | 4.00 | 6.1 | | 18 | | | | | | |
| P-50 | S-50 | 408.95 | EX MH | 408.85 | 12 | 1.00 | 5 | | 10 | | | | | | |
| P-38 | S-38 | 409.64 | S-37 | 409.53 | 12 | 1.00 | 5 | | 11 | | | | | | |
| P-38A | S-38A | 409.74 | S-38 | 409.64 | 12 | 1.00 | 5 | | 10 | | | | | | |
| P-36 | S-36 | 410.23 | S-35 | 410.14 | 12 | 1.00 | 4 | | 9 | | | | | | |
| P-30 | S-30 | 409.94 | S-29 | 409.86 | 12 | 1.00 | 4 | | 8 | | | | | | |
| P-49 | S-49 | 408.40 | EX MH | 408.30 | 12 | 1.00 | 5 | | 10 | | | | | | |
| P-41 | S-41 | 408.23 | S-42 | 407.90 | 12 | 1.00 | 21 | | 33 | | | | | | |
| P-41A | S-41A | 408.34 | S-41 | 408.23 | 12 | 1.00 | 6 | | 11 | | | | | | |
| P-54 | S-54 | 408.56 | S-41 | 408.23 | 12 | 1.00 | 19 | | 33 | | | | | | |
| P-40 | S-40 | 409.24 | S-41 | 408.23 | 12 | 1.00 | 12 | | 101 | | | | | | |
| P-48 | S-48 | 409.63 | S-49 | 408.40 | 12 | 1.00 | 14 | | 123 | | | | | | |
| ST. CLAIR AVENUE SUBTOTALS | | | | | | | | 121.5 | 0 | 436 | 0 | 0 | 0 | 0 | |
| 9TH STREET & RAMP P | | | | | | | | | | | | | | | |
| P-4 | S-4 | 407.49 | S-1 | 407.25 | 18 | 0.30 | 79 | | | | 79 | | | | |
| P-3 | S-3 | 411.16 | S-4 | 411.06 | 12 | 1.00 | 5 | | 10 | | | | | | |
| P-2 | S-2 | 411.55 | S-3 | 411.16 | 12 | 1.00 | 19 | | 39 | | | | | | |
| P-7 | S-7 | 407.82 | S-4 | 407.49 | 18 | 0.30 | 119 | | | | 110 | | | | |
| P-6 | S-6 | 412.01 | S-7 | 411.92 | 12 | 1.00 | 5 | | 9 | | | | | | |
| P-5 | S-5 | 412.44 | S-6 | 412.01 | 12 | 1.00 | 21 | | 43 | | | | | | |
| P-8 | S-8 | 408.00 | S-7 | 407.82 | 18 | 0.30 | 32 | | | | 61 | | | | |
| P-27 | S-27 | 409.37 | S-8 | 409.00 | 15 | 0.57 | 0 | | | 65 | | | | | |
| P-25 | S-25 | 409.71 | S-27 | 409.37 | 12 | 0.50 | 17 | | 68 | | | | | | |
| P-23 | S-23 | 411.37 | S-25 | 410.48 | 12 | 1.00 | 3 | | 89 | | | | | | |
| P-22 | S-22 | 412.70 | S-23 | 412.58 | 12 | 1.00 | 7 | | 12 | | | | | | |
| P-21 | S-21 | 411.79 | S-23 | 411.37 | 12 | 1.00 | 27 | | 42 | | | | | | |
| P-20 | S-20 | 414.12 | S-21 | 414.00 | 12 | 1.00 | 5 | | 12 | | | | | | |
| P-9 | S-9 | 408.45 | S-8 | 408.00 | 12 | 0.44 | 90 | | 103 | | | | | | |
| P-12 | S-12 | 408.88 | S-9 | 408.45 | 12 | 0.44 | 13 | | 98 | | | | | | |
| P-39 | S-39 | 410.39 | S-40 | 410.28 | 12 | 0.79 | 7 | | 14 | | | | | | |
| P-53 | S-53 | 409.50 | S-40 | 409.24 | 12 | 1.00 | 15 | | 26 | | | | | | |
| P-47 | S-47 | 409.73 | S-48 | 409.63 | 12 | 1.00 | 6 | | 10 | | | | | | |
| P-43 | S-43 | 408.98 | S-45 | 408.80 | 12 | 1.00 | 9 | | 18 | | | | | | |
| P-43A | S-43A | 409.08 | S-43 | 408.98 | 12 | 1.00 | 5 | | 10 | | | | | | |
| P-44 | S-44 | 409.03 | S-45 | 408.80 | 12 | 1.00 | 11 | | 23 | | | | | | |
| P-44A | S-44A | 409.13 | S-44 | 409.03 | 12 | 1.00 | 5 | | 10 | | | | | | |
| P-70 | S-70 | 415.65 | S-71 | 415.47 | 15 | 1.00 | 0 | | | 18 | | | | | |
| P-71 | S-71 | 415.47 | S-72 | 413.15 | 15 | 3.80 | 8 | | | 61 | | | | | |
| P-72 | S-72 | 413.15 | S-73 | 412.90 | 21 | 0.30 | 0 | | | | 84 | | | | |
| P-73 | S-73 | 412.9 | S-74 | 412.58 | 21 | 0.30 | 42 | | | | 107 | | | | |
| 9TH STREET & RAMP P SUBTOTALS | | | | | | | | 550 | 0 | 636 | 144 | 250 | 191 | 0 | |
| BAUGH AVENUE | | | | | | | | | | | | | | | |
| P-11 | S-11 | 412.93 | S-12 | 412.85 | 12 | 1.00 | 4 | | 8 | | | | | | |
| P-10 | S-10 | 413.33 | S-11 | 412.93 | 12 | 1.00 | 17 | | 40 | | | | | | |
| P-15 | S-15 | 409.54 | S-12 | 408.88 | 12 | 0.44 | 137 | | 149 | | | | | | |
| P-14 | S-14 | 412.27 | S-15 | 412.18 | 12 | 1.00 | 5 | | 9 | | | | | | |
| P-13 | S-13 | 412.59 | S-14 | 412.27 | 12 | 1.00 | 14 | | 32 | | | | | | |
| P-19 | S-19 | 410.36 | S-15 | 409.54 | 12 | 0.44 | 17 | | 186 | | | | | | |
| P-17 | S-17 | 410.40 | S-19 | 410.36 | 12 | 0.57 | 4 | | 7 | | | | | | |
| P-16 | S-16 | 410.57 | S-17 | 410.40 | 12 | 0.50 | 18 | | 34 | | | | | | |
| P-24 | N/A | 410.83 | EX MH | 410.46 | 8 | 1.00 | 16 | | | | | | | 37 | |
| BAUGH AVENUE SUBTOTALS | | | | | | | | 232 | 0 | 465 | 0 | 0 | 0 | 0 | |
| TOTALS | | | | | | | | 1032.2 | 100 | 1635 | 215 | 250 | 191 | 31 | 37 |

FILE NAME = DBTRI-76C51-Schedule_Drainage_01.dgn

USER NAME = searab
 PLOT SCALE = 20.0000' / in.
 PLOT DATE = MAR. 31, 2011

DESIGNED KM
 DRAWN KM
 CHECKED OP
 DATE 06/15/2011

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES - DRAINAGE

SCALE: N/A SHEET NO. 1 OF 3 SHEETS STA. TO STA.

| F.A. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|-----------------------|----------------------------|---------------------------|--------------|-----------|
| • | 82-1-3HB, 82-2N, 82-1-12RS | ST. CLAIR | 352 | 23 |
| • 9166/9180/9213/9214 | | CONTRACT NO. | 76C51 | |
| FED. ROAD DIST. NO. | | ILLINOIS FED. AID PROJECT | | |