

# SUMMARY OF QUANTITIES

## URBAN

					100% STATE			
CODE NO.	ITEM	UNIT	TOTAL QUANTITY					
				ROADWAY	I-70 OVER I-55, CSX, KCS RAILROADS BRIDGES STR NO 082- 0322	I-70 OVER I-55, CSX, KCS RAILROADS BRIDGES STR NO 082- 0324	TRAINEES	
				0001	0008	0008	0042	
63700900	CONCRETE BARRIER BASE	FOOT	1,285	1,285				
64200105	SHOULDER RUMBLE STRIPS	FOOT	1,485	1,485				
66400305	CHAIN LINK FENCE, 6'	FOOT	36	36				
66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	9,500	9,500				
* 66900210	HAZARDOUS WASTE DISPOSAL	CU YD	230	230				
* 66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1				
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	5	5				
67100100	MOBILIZATION	L SUM	1	1				
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	730	730				
70300100	SHORT TERM PAVEMENT MARKING	FOOT	6,500	6,500				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	13,306	13,306				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	11	11				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	4,323	4,323				
70400100	TEMPORARY CONCRETE BARRIER	FOOT	2,837.5	2,837.5				
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1,537.5	1,537.5				
* 72000100	SIGN PANEL - TYPE 1	SQ FT	17	17				
72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	3	3				
* 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	36	36				
* 73100100	BASE FOR TELESCOPING STEEL SIGN SUPPORT	EACH	1	1				
* 73300100	OVERHEAD SIGN STRUCTURE - SPAN, TYPE I-A (4'-0" X 4'-6")	FOOT	143	143				
* 73301810	OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	86	86				
* 73301840	OVERHEAD SIGN STRUCTURE WALKWAY, CANTILEVER, TYPE A	FOOT	18	18				
* 73302170	OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE II-C-A (36" X 5'-6")	FOOT	25	25				
73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	22.3	22.3				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	7,938	7,938				
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	736	736				
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	298	298				
* 78003110	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4"	FOOT	2,144	2,144				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	60	60				
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	15	15				
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	141	141				
78300100	PAVEMENT MARKING REMOVAL	SQ FT	3,888	3,888				
80300100	LOCATING UNDERGROUND CABLE	FOOT	100	100				
81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	455	455				
81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	7,337		6,339	998		

\* DENOTES SPECIALTY ITEM

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64/998	82-1-B-2	ST. CLAIR	399	8
FED. ROAD DIST. NO.			CONTRACT NO. 76C76	
ILLINOIS			FED. AID PROJECT	

SCALE: NONE SHEET NO. 4 OF 6 SHEETS STA. TO STA.