

SAFETY ITEM SCHEDULE

SHEET	STATION	TO	STATION	POROUS GRANULAR EMBANKMENT, SPECIAL	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6' POSTS	TRAFFIC BARRIER TERMINAL, TYPE 5	TRAFFIC BARRIER TERMINAL, TYPE 6	CONCRETE BARRIER, SINGLE FACE, 42 INCH HEIGHT	CONCRETE BARRIER, SINGLE FACE, 42 INCH HEIGHT (SPECIAL)	CONCRETE BARRIER, DOUBLE FACE, 42 INCH HEIGHT	CONCRETE BARRIER TRANSITION	CONCRETE BARRIER BASE	RELOCATE TEMPORARY CONCRETE BARRIER 2	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	GUARDRAIL MARKERS, TYPE A	BARRIER WALL MARKERS, TYPE C
				CU YD	FOOT	EACH	EACH	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	EACH
PLAN-1	194+17.33	TO	51+00.00	-	562.5	1	1	-	-	212	70	282	-	-	12	-
PLAN-2	51+00.00	TO	57+00.00	7	112.5	1	1	94	-	-	33	127	-	-	3	22
PLAN-3	57+00.00	TO	63+00.00	-	-	-	-	-	563	-	-	563	275.0	-	-	35
PLAN-4	63+00.00	TO	68+00 & 62+50	-	-	-	-	69	-	-	10	79	625.0	2	-	44
PLAN-5	68+00.00	TO	74+00.00	-	-	-	-	-	-	-	-	-	175.0	-	-	24
PLAN-6	74+00.00	TO	75+41.52	-	-	-	-	-	234	-	-	234	-	-	-	5
PLAN-7	62+50.00	TO	43+50.00	-	-	-	-	-	-	-	-	-	112.5	-	-	11
TOTALS				7	675.0	2	2	163	797	212	113	1,285	1,187.5	2	15	141

NOTES:

- SEE ROADWAY SCHEDULE FOR ADDITIONAL CONCRETE MEDIAN SURFACE QUANTITY.
- SEE TRAFFIC CONTROL SCHEDULE FOR ADDITIONAL QUANTITIES FOR TEMPORARY CONCRETE BARRIER AND IMPACT ATTENUATORS.

SEEDING SCHEDULE

STAGE	SEEDING, CLASS 2A 3	MULCH, METHOD 2 1.2	NITROGEN FERTILIZER NUTRIENT 3	PHOSPHORUS FERTILIZER NUTRIENT 3	POTASSIUM FERTILIZER NUTRIENT 3
	ACRE	ACRE	POUND	POUND	POUND
STAGE 1	4.50	4.50	405	405	405
STAGE 1A	0.25	0.25	23	23	23
STAGE 2	4.75	4.75	428	428	428
TOTALS	9.50	9.50	856	856	856
ROUNDED TOTALS	9.50	9.50	856	856	856

- SEE EROSION CONTROL SCHEDULE FOR ADDITIONAL MULCH, METHOD 2 QUANTITY.
- SEEDING & MULCH QUANTITIES ARE ROUNDED TO THE NEAREST 0.25 ACRE.
- LANDSCAPING IS NOT INCLUDED. QUANTITIES INCLUDED FOR COST ESTIMATE ONLY.

TRAFFIC CONTROL SCHEDULE - STAGE 1 & 1A

SHEET	STATION	TO	STATION	TEMPORARY PAVEMENT MARKING - LINE 4"	TEMPORARY PAVEMENT MARKING - LINE 24"	TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER	PAVEMENT MARKING REMOVAL	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3
				FOOT	FOOT	FOOT	FOOT	SQ FT	EACH	EACH
STAGE 1										
MOT-1	194+17.33	TO	59+00.00	-	-	-	-	34	-	-
MOT-2	59+00.00	TO	65+50.00	6,470	11	2,087.5	350.0	2,176	3	2
MOT-3	65+50.00	TO	MATCH LINE "A"	639	-	-	-	213	-	-
MOT-4	MATCH LINE "A"	TO	MATCH LINE "B"	-	-	-	-	-	-	-
MOT-5	MATCH LINE "B"	TO		-	-	-	-	-	-	-
MOT-6	75+50.00	TO	80+00.00	1,433	-	337.5	-	537	1	-
MOT-7	50+00.00	TO	62+00.00	4,765	-	62.5	-	928	1	-
STAGE 1A										
MOT-2	194+17.33	TO	59+00.00	-	-	350.0	-	-	2	-
MOT-7	59+00.00	TO	65+50.00	-	-	-	-	-	-	-
TOTALS				13,307	11	2,837.5	350.0	3,888	7	2