



I-70 OVER I-55, CSX, KCS RAILROADS
 BRIDGE STR 082-0322 & 082-0324
 STA 51+92.00 TO STA 74+78.50
 STA 54+99.00 TO STA 64+88.50
 SEE BRIDGE PLANS

I-70 OVER I-55, CSX, KCS RAILROADS
 BRIDGE STR 082-0322 & 082-0324
 STA 51+92.00 TO STA 74+78.50 (SN 082-0322)
 STA 54+99.00 TO STA 64+93.50 (SN 082-0324)
 SEE BRIDGE PLANS

- NOTES:**
- SEE ROADWAY DETAIL SHEET 3 OF 3 FOR MOUNDING OF PIER FOOTING DETAILS.
 - CONTRACTOR SHALL ENSURE AND ALLOW FOR ADEQUATE PROTECTION OF PIERS 4, 9, 10 (SN 082-0322) AND PIERS 5 & 6 (SN 082-0324) ONCE THEY ARE CONSTRUCTED WHETHER BY USING TEMPORARY CONCRETE BARRIER IN THIS CONTRACT OR BY COORDINATION WITH CONTRACTS 76C52 & 76C53 FOR USING OTHER ROADSIDE SAFETY ITEMS.

CONCRETE REMOVAL

POINT	STA	O/S
O	50+54.30	36.1' LT
P	50+53.54	29.9' LT

NOTES:
 ALL STATIONS AND OFFSETS ARE TAKEN OF RAMP 70E64E

LEGEND:

- PAVEMENT REMOVAL
- SHOULDER REMOVAL
- CONCRETE REMOVAL
- SIDEWALK REMOVAL
- LINEAR REMOVAL
- TREE REMOVAL (ACRES)
- TREE REMOVAL (UNITS)



USER NAME = searsb	DESIGNED OP	REVISED -
PLDT SCALE = 48.0000' / in.	DRAWN PHP	REVISED -
PLDT DATE = 7/1/2011	CHECKED DBM	REVISED -
	DATE 07-01-11	REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

ROADWAY PLAN
RAMP 70E55N/RAMP 70E64E

SCALE: 1" = 20' SHEET NO. 3 OF 7 SHEETS STA. 57+00 TO STA. 63+00

F.A.I. RTE. 64/998	SECTION 82-1-B-2	COUNTY ST. CLAIR	TOTAL SHEETS 399	SHEET NO. 25
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT		CONTRACT NO. 76C76		