



EROSION CONTROL SCHEDULE

BASELINE	STATION	OFFSET	INLET AND PIPE PROTECTION EACH
RAMP P	19+68.00	25.50' LT	1
RAMP P	19+95.54	31.43' RT	1
RAMP 70E55N	78+50.00	53.43' LT	1
RAMP 70E64E	63+02.59	4.87' LT	1
RAMP 70E64E	65+30.00	22.5' RT	1
RAMP 70E64E	65+30.00	38.50' LT	1
RAMP 70E64E	64+00.00	32.14' LT	1
TOTALS			7

STAGE	MULCH, METHOD 2 ACRE	TEMPORARY EROSION CONTROL SEEDING POUND	PERIMETER EROSION BARRIER FOOT	
STAGE 1	4.50	900	9,951	
STAGE 1A	0.25	50	278	
STAGE 2	4.75	950	10,229	
TOTALS		9.50	1,900	20,458

NOTE:
1. SEE SEEDING SCHEDULE FOR ADDITIONAL MULCH, METHOD 2 QUANTITY.

LEGEND

- TEMPORARY DITCH CHECK- ROLLED EXCELSIOR, SILT WEDGES
- EROSION CONTROL BLANKET
- TEMPORARY EROSION CONTROL SEEDING (INCLUDES MULCH, METHOD 2)
- PERIMETER EROSION BARRIER- SILT FILTER FENCE OR OTHER AS APPROVED BY THE ENGINEER
- INLET AND PIPE PROTECTION- STRAW BALES, FILTER FABRIC, AGGREGATES

USER NAME = pimsarho DESIGNED OP DRAWN OP CHECKED DBM DATE 07-01-11	REVISED - REVISED - REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	EROSION CONTROL PLAN SCALE: 1" = 50' SHEET NO. 3 OF 3 SHEETS STA. TO STA.	F.A.I. RTE. 64/998 SECTION 82-1-B-2 COUNTY ST. CLAIR TOTAL SHEETS 399 SHEET NO. 60 FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT
---	--	---	---	---