



Walkway and truss grating dimensions are nominal and may vary (width ± 1/2", depth ± 1/2") based on available standard widths.



SECTION A-A

Truss grating to facilitate inspection shall run full length of cantilevers. Cost of truss grating is included in Overhead Sign Structure Cantilever.

Handrail and walkway grating shall span a minimum of three brackets between splices. ** Use and location of handrail joints or grating splices are optional, based on lengths needed and material availability.

$$TGL = L - \left(\frac{\text{Post O.D.}}{2} + 6' \right)$$

Structure Number	Station	WGL	ED	TGL
8C0821070R002.8	69+42.00	18'-0"	7'-0"	18'-0"

Notes:
* Space walkway brackets WF(A-N)4x3.06 and sign brackets WF(A-N)4x1.79 for efficiency and within limits shown:
f = 12" maximum, 4" minimum (End of sign to center of nearest bracket)
g = 12" maximum, 4" minimum (End of walkway to center of nearest bracket)
h = 6'-0" maximum (center to center sign and/or walkway support brackets, WF(A-N)4x1.79 or WF(A-N)4x3.06)

*** If walkway bracket at safety chain location is behind sign, add angle to bracket. See alternate safety chain attachment on base sheet OSC-A-8.

For details of sign placement, sign/walkway brackets, truss and walkway gratings, grating splices and Section B-B, see Base Sheet OSC-A-7S.
For details of handrail, handrail joint, safety chain and Details F and G, see Base Sheet OSC-A-8.

BRACKET TABLE

WF(A-N)4x1.79 or WF(A-N)4x3.06 ASTM B308, Alloy 6061-T6		
Sign Width		Number Brackets Required
Greater Than	Less Than or Equal To	
8'-0"	14'-0"	2
14'-0"	20'-0"	3
20'-0"	26'-0"	4
26'-0"	32'-0"	5
		6

OSC-A-6S

7-1-10

FILE NAME =	USER NAME = pkissel	DESIGNED = PMK	REVISED =	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	CANTILEVER SIGN STRUCTURES – ALTERNATE STEEL WALKWAY DETAILS – ALUMINUM TRUSS & STEEL POST	F.A.I. RTE. = 64/998	SECTION = 82-1-B-2	COUNTY = ST. CLAIR	TOTAL SHEETS = 399	SHEET NO. = 121	
#FILE#	PLOT SCALE = 3.3673" / IN.	DRAWN = PMK	REVISED =			SCALE: N/A	SHEET NO. 7 OF 10 SHEETS	STA. N/A	TO STA. N/A	FED. ROAD DIST. NO. = ILLINOIS FED. AID PROJECT	CONTRACT NO. = 76C76
	PLOT DATE = 6/13/2011	CHECKED = MPW	REVISED =								
		DATE = 07-01-2011	REVISED =								