

SUMMARY OF QUANTITIES

100% STATE

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005 LOC 1	0005 LOC 2	0005 LOC 3	0005 LOC 4
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	40	16	11	7	6
40600300	AGGREGATE (PRIME COAT)	TON	66	26	18	12	10
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	1348	563	409	131	245
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	80	80			
40600990	TEMPORARY RAMP	SQ YD	178	44	46	33	55
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	2,109	948	511	369	281
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	22.7	22.5			0.2
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	18766		10062	4693	4011
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	8750	3768	1632	2112	1238
48101200	AGGREGATE SHOULDERS, TYPE B	TON	220	91		103	26
48203100	HOT-MIX ASPHALT SHOULDERS	TON	348		348		
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	657			469	188
67100100	MOBILIZATION	L SUM	1	0.25	0.25	0.25	0.25
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.25	0.25	0.25	0.25
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.25	0.25	0.25	0.25
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	0.25	0.25	0.25	0.25
70300100	SHORT TERM PAVEMENT MARKING	FOOT	876	377	93	214	192
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	54		35		19
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	61715	41430	8168	8448	3669
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	170	24	22		124
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	288	124	31	70	63
*78001100	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	54		35		19
*78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	24428	4143	8168	8448	3669
*78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	170	24	22		124
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	150	126			24
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	150	126			24

*SPECIALTY
ITEM

FILE NAME =	USER NAME = alfordb	DESIGNED -	REVISED -
o:\pwork\pwork\alfordb\0266246\d876	08-shr-plan.dgn	DRAWN -	REVISED -
PLOT SCALE = 100.0000' / 1"	CHECKED -	REVISED -	REVISED -
PLOT DATE = 9/9/2011	DATE -	REVISED -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	VAR. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
			VAR	D-8 RESURFACING 2012-2	MADISON	14	4
			CONTRACT NO. 76F06				
			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				