

SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	UNIT	HBP FUNDS
			80% FED 20% STATE
			BRIDGE 0014 RURAL
20100500	TREE REMOVAL, ACRES	ACRE	0.10
20200100	EARTH EXCAVATION	CU YD	40
20400800	FURNISHED EXCAVATION	CU YD	795
* 25000200	SEEDING, CLASS 2	ACRE	0.50
* 25000350	SEEDING, CLASS 7	ACRE	0.50
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	66
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	46
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	46
* 25000700	AGRICULTURAL GROUND LIMESTONE	TON	1.0
* 25100115	MULCH, METHOD 2	ACRE	1.00
25100630	EROSION CONTROL BLANKET	SQ YD	2682
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	50
28000400	PERIMETER EROSION BARRIER	FOOT	1612
35600716	HOT-MIX ASPHALT BASE COURSE WIDENING, 10"	SQ YD	270
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	342
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	18
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	174
40600990	TEMPORARY RAMP	SQ YD	28
40603090	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	167
40603320	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N90	TON	126
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	42
44000100	PAVEMENT REMOVAL	SQ YD	62
44004250	PAVED SHOULDER REMOVAL	SQ YD	270
48100700	AGGREGATE SHOULDERS, TYPE A 8"	SQ YD	64
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	433
48203037	HOT-MIX ASPHALT SHOULDERS, 10"	SQ YD	266
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1
50102400	CONCRETE REMOVAL	CU YD	5.3
50300225	CONCRETE STRUCTURES	CU YD	29.5
50300255	CONCRETE SUPERSTRUCTURE	CU YD	103.4
50300260	BRIDGE DECK GROOVING	SQ YD	1143

CODE NO.	ITEM DESCRIPTION	UNIT	HBP FUNDS
			80% FED 20% STATE
			BRIDGE 0014 RURAL
50300300	PROTECTIVE COAT	SQ YD	1221
50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)	SQ FT	8836
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	39800
50800515	BAR SPLICERS	EACH	494
* 50901050	STEEL RAILING, TYPE SM	FOOT	585
51500100	NAME PLATES	EACH	1
52000110	PREFORMED JOINT STRIP SEAL	FOOT	76
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	450
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4
63200310	GUARDRAIL REMOVAL	FOOT	483
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6
67100100	MOBILIZATION	L SUM	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	4
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	12
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	114
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	2524
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	880
70400100	TEMPORARY CONCRETE BARRIER	FOOT	550
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	550
72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	1
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	2524
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	7
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER(BRIDGE)	EACH	4
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	20
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4
78300100	PAVEMENT MARKING REMOVAL	SQ FT	841

*SPECIALTY ITEM



DESIGNED BKC	REVISIONS	<p align="center">STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</p> <p align="center">IL-145 (OVER BAY CREEK DITCH) SUMMARY OF QUANTITIES</p>	F.A.P. RTE. 132	SECTION 103BR-1	COUNTY POPE	TOTAL SHEETS 38	SHEET NO. 3
DRAWN BKC	REVISIONS		CONTRACT NO. 78164				
CHECKED MH	REVISIONS						
DATE 04/29/11	REVISIONS						