



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

November 9, 2011

SUBJECT: FAP 622 (IL 78)
Project TE-00D4(112)
Section 10-00078-00-MS (Lewistown)
Fulton County
Contract No. 89599
Item 029
November 18, 2011 Letting
Addendum (A)

TO PROSPECTIVE BIDDERS:

Due to clarify information necessary to revise the following:

Proposal – Page 3 of the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Scott Stitt
Acting Engineer of Design and Environment

A handwritten signature in cursive script, appearing to read "Ted B. Walschleger", followed by the initials "AE".

By: Ted B. Walschleger
Engineer of Project Development
and Implementation

BRICK GRINDING AND REPOINTING

BRICK REMOVAL AND REPLACEMENT

BRICK WATERPROOFING

This work shall consist of the repairs to the exterior brick of the Lewistown Visitor Center building at 222 S. Main Street. Repairs are planned for all four sides from the ground line to the roof line of the three-story building. Areas to be repaired will be determined and marked by the Engineer. All work shall be in accordance with the technical specifications (Section 4200 and Section 7100) that follow and applicable portions of the Standard Specifications.

Method of Measurement.

BRICK GRINDING AND REPOINTING will be measured for payment in place and the area computed in square feet. For a repair at a corner, both sides will be measured.

BRICK REMOVAL AND REPLACEMENT will be measured for payment as individual bricks and the unit of payment will be each.

BRICK WATERPROOFING will be measured for payment in place and the area computed in square feet.

Basis of Payment.

BRICK GRINDING AND REPOINTING will be paid for at the contract unit price per square foot.

BRICK REMOVAL AND REPLACEMENT will be paid for at the contract unit price each.

BRICK WATERPROOFING will be paid for at the contract unit price per square foot.

The sealant specified in Section 4200 shall be included in the various pay items involved and will not be paid for separately.

Revised 11/9/11